

**QUINEX ENERGY CORPORATION**

2225 East Murray Holladay Road, Suite 100  
Salt Lake City, Utah 84117  
(801) 272-9093

December 4, 1984


State of Utah  
Division of Oil Gas & Mining  
355 West North Temple  
3 Triad Center, Suite 350  
Salt Lake City, Utah 84180-1203

Gentlemen:

This application for Permit to Drill an oil and/or gas well on Ute-Allottee lands is a request for State approval, copies of which will be filed with the Vernal BLM office and the BIA at FortDuchesne.

Your prompt consideration of our request will be greatly appreciated.

Very Truly yours,  
QUINEX ENERGY CORPORATION

  
Lewis F. Wells,  
President

LFW/hw

Encl:

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

## 1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

## b. TYPE OF WELL

OIL  
WELL ☒GAS  
WELL ☐

OTHER

SINGLE  
ZONE ☐MULTIPLE  
ZONE ☒

## 2. NAME OF OPERATOR

QUINEX ENERGY CORPORATION

## 3. ADDRESS OF OPERATOR

2225 E. Murray Holladay Rd., #100 Salt Lake City, Utah 84117

## 4. LOCATION OF WELL (Reproduction clearly and in accordance with any State requirements.)\*

At surface

876' S of N line, 669' E of W line, Sec. 30 T 1 S, R 2 E

At proposed prod. zone

## 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

3.7 miles Southwest of LaPoint, Utah

## 15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST  
PROPERTY OR LEASE LINE, FT.  
(Also to nearest drlg. unit line, if any)

## 16. NO. OF ACRES IN LEASE

160

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

563.77

18. DISTANCE FROM PROPOSED LOCATION\*  
TO NEAREST WELL, DRILLING, COMPLETED,  
OR APPLIED FOR, ON THIS LEASE, FT.

N.A.

## 19. PROPOSED DEPTH

13,500'

## 20. ROTARY OR CABLE TOOLS

Rotary

## 21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5344' GR

## 22. APPROX. DATE WORK WILL START\*


Dec. 20, 1984

## 23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH

## Attachments:

1. Plat of Survey well site
2. Plat of Survey well location
3. Drilling Procedure and well information
4. Rig layout, U. S. Drilling Rig #48
5. Copy of State Bond
6. Copy of Designation of Operator form
7. Copy of U.S.G.S. Topo sheet showing terrain & other oil and gas well locations



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

TITLE

President

DATE

Dec 4-84

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE


DATE: 7/12/1984

BY: John A. Day

SECTION 30  
TOWNSHIP 1 SOUTH, RANGE 2 EAST  
UINTAH SPECIAL BASE AND MERIDIAN  
UINTAH COUNTY, UTAH

QUINEX ENERGY CORP.

WELL LOCATION: N.W.  $\frac{1}{4}$ , N.W.  $\frac{1}{4}$




SCALE 1"=1000'

SURVEYOR'S CERTIFICATE

I, Clinton S. Peatross, Duchesne, Utah, do hereby certify that I am a Registered Land Surveyor, and that I hold License No. 4779, as prescribed by the laws of the state of Utah, and that I have made a survey of the oil well location, as shown on this plat.

10/2/94  
Date

Clinton S. Peatross  
Clinton S. Peatross  
License No. 4779 (Utah)



## QUINEX ENERGY CORPORATION

## DRILLING PROCEDURE

Redcap

Field Bluebell Well J.D.C. #30-4-1A  
Location NE $\frac{1}{4}$ NW $\frac{1}{4}$  Sec. 30, T 1 S. R 1 E Duchesne County, Utah  
Drill x Deepen --- Elevation: GR 5344' KB --- Total Depth 13,500'  
Non-Op Interests ---

1. Casing Program (O = Old N = New)

	<u>Surface</u>	<u>O/N</u>	<u>Intermediate</u>	<u>O/N</u>	<u>Oil String/Liner</u>	<u>O/N</u>
Hole Size	<u>13 3/4"</u>		<u>9 7/8"</u>		<u>6 3/4"</u>	
Pipe Size	<u>10 3/4"</u>	<u>New</u>	<u>7 5/8"</u>	<u>New</u>	<u>5<math>\frac{1}{2}</math>"</u>	<u>New</u>
Grade	<u>K-55</u>	<u>New</u>	<u>N-80</u>		<u>P-110 SFJ</u>	<u>New</u>
Weight	<u>40.5#</u>		<u>26.4-29.7</u>		<u>20#</u>	
Depth	<u>2,000'</u>		<u>10,200'</u>		<u>10,000'</u>	
Cement	<u>1200 sx</u>		<u>450 sx</u>		<u>800</u>	
Time WOC	<u>12 hrs.</u>		<u>24 hrs.</u>		<u>24 hrs.</u>	
Casing Test	<u>3500#</u>		<u>5000#</u>		<u>5000#</u>	
BOP	<u>1) 1-10" Series 900 Shaffer, Double gate. 2) 1-10 900 Hydril</u>					

Remarks ---2. Mud Program

<u>Depth Interval</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Water Loss</u>
<u>Surf - 7,000'</u>	<u>water &amp; gel</u>	<u>8.5</u>	<u>35-45</u>	<u>---</u>
<u>7,000 - 10,200'</u>	<u>non dispersed low solids</u>		<u>32-34</u>	<u>10-12</u>
<u>10,200' - 13,500'</u>	<u>pre-mixed liquids w/ Barite added</u>		<u>35-45</u>	<u>"</u>
	<u>for weight control, (Do not over saturate)</u>			

3. Logging Program

Schlumberger

Surface Depth 10,200' up to 3,500' GR/DIL 10,200' up to 6,000'  
Intermediate Depth Litho, Den/Compensated Neutron, Temp. Cyberlook  
Oil String Depth ---  
Total Depth ---

4. Mud Logging Unit

Analex, Denver, CO

Scales: 5" = 100' 6,000 to 13,500 ; --- to ---5. Coring & Testing ProgramFormationsApproximate DepthApproximate Length of Core

Core --- DST --- No cores nor DST's are programmed  
Core --- DST ---

6. Objectives & Significant Tops: Objectives: Production: Tertiary Wasatch "B" andNeola 3 Fingers. 2nd, Green River/Wasatch TransitionBasal Green River.  
FormationsApproximate DepthFormationsApproximate Depth

<u>Green River</u>	<u>6750</u>		
<u>Green River/Wasatch Trans.</u>	<u>8700</u>		
<u>Wasatch</u>	<u>9100</u>		
<u>---</u>			
<u>---</u>			

7. Anticipated Bottom Hole Pressure: 9000#8. Completion & Remarks: A completion prognosis will be prepared, based on the outcome of the test well, prior to commencement of completion.Compiled By: John WellsApproved By: Shella





## DESIGNATION OF OPERATOR

The undersigned is, on the records of the Bureau of Land Management, holder of lease

DISTRICT LAND OFFICE: Oil and Gas Mining Lease  
SERIAL NO.: 14 - 20 - H62 - 4065

and hereby designates

NAME: QUINEX ENERGY CORPORATION  
ADDRESS: 2225 East Murray Holladay Road - Suite 100  
Salt Lake City, Utah 84117


as his operator and local agent, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the supervisor or his representative may serve written or oral instructions in securing compliance with the Operating Regulations with respect to (describe acreage to which this designation is applicable):

Township 1 South, Range 2 East, Section 30, N $\frac{1}{2}$  NW $\frac{1}{4}$ : Uintah  
County, Utah. 80 Acres.

It is understood that this designation of operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Operating Regulations. It is also understood that this designation of operator does not constitute an assignment of any interest in the lease.


In case of default on the part of the designated operator, the lessee will make full and prompt compliance with all regulations, lease terms, or orders of the Secretary of the Interior or his representative.

The lessee agrees promptly to notify the supervisor of any change in the designated operator.

  
(Signature of lessee)

12-4-84  
(Date)

2285 Lucky John Drive  
Park City, Utah 84060  
(Address)



QUINEX ENERGY CORP.  
EAST BLUEBELL PROPERTY  
J.D.C. 30-4 WELL

CONFIDENTIAL

OPERATOR

*Quincy Energy Corp.*

DATE

*12-5-84*

WELL NAME

*Redup J. D. C. #30-4-1A*

SEC

*NW NW 30*

T

*15*

R

*2E*

COUNTY

*Thurston*

*43-047-31591*

API NUMBER

*Indian*

TYPE OF LEASE

CHECK OFF:



PLAT



BOND



NEAREST WELL



LEASE



FIELD



POTASH OR  
OIL SHALE

PROCESSING COMMENTS:

*in Sec. 30*  
*No other well within 1/4 mi*  
*Need water permit*

APPROVAL LETTER:

SPACING:



A-3

UNIT



C-3-a

*131-27* *4/16/75*  
CAUSE NO. & DATE




C-3-b



C-3-c

STIPULATIONS:

*1-Water*  
*2-BOP = 5000 psi - 10 3/4" csq.*



**QUINEX ENERGY CORPORATION**

2225 East Murray Holladay Road, Suite 100  
Salt Lake City, Utah 84117  
(801) 272-9093

December 14, 1984

State of Utah  
Department of Natural Resources  
Division of Oil, Gas & Mining  
355 W. North Temple  
Suite 350  
Salt Lake City, Utah 84180  
Attn: Mr. Ron Firth

RE: Request for Exception  
East Bluebell Field

Dear Sir:

The proposed location for the Quinex Redcap JDC #30-4-1A well does not lie within the regulatory meets and bounds of the standard well site for a wasatch formation test on spaced lands in the Bluebell Field.

On December 11, 1984 an on-site field inspection was held. Those in attendance were; Amy Heuslem, B.L.M., Vernal; Bob Fuller, B.I.A., Ft. Duchesne; Paul Wells, H. J. Payne, and L. F. Wells, Quinex Energy, Salt Lake City; Drilling Superintendent, DeLoy Duncan, U.S. Drilling; and the earth construction contractors, John E. Fausett and Ned Mitchell. After review and study of field conditions, the consensus was that, the location would be satisfactory, provided the access road would be altered, the reserve pit relocated to the west side of the well spot, and the orientation of the rig lay out changed.

The area to the east and southeast is the old chanel for Deep Creek drainage, which carries sub surface water and the land is unstable and unsuitable due to the undulated and dissected lands and the topography is not adaptable to a good well site location.

A copy of the corrected and relocated plat is submitted herewith and in support of our request for a spacing exception and the approval of existing survey.

We are requesting a confidential status of this application. Should you require any other information or material in support of our request, please call our Salt Lake City office 272-9093.

Thanks for your review and consideration of this spacing exception.

Sincerely,

A handwritten signature in cursive script, appearing to read 'L. Wells'.

Lewis R. Wells  
QUINEX ENERGY CORPORATION

LFW:mlr

REVISED  
UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

## 1a. TYPE OF WORK

DRILL ☐DEEPEN ☐PLUG BACK ☐

## b. TYPE OF WELL

OIL  
WELL ☒GAS  
WELL ☐

OTHER

SINGLE  
ZONE ☐MULTIPLE  
ZONE ☒

## 2. NAME OF OPERATOR

QUINEX ENERGY CORPORATION

## 3. ADDRESS OF OPERATOR

2225 East Murray Holladay Rd., #100, Salt Lake City, Utah 84117

## 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.\*)

At surface  
876' S of N line, 669' E of W line, Sec. 30, T 1 S, R 2 E

At proposed prod. zone

## 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

3.3 miles southwest of LaPoint, Utah

## 15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST  
PROPERTY OR LEASE LINE, FT.  
(Also to nearest drlg. unit line, if any)18. DISTANCE FROM PROPOSED LOCATION\*  
TO NEAREST WELL, DRILLING, COMPLETED,  
OR APPLIED FOR, ON THIS LEASE, FT.

N.A.

## 16. NO. OF ACRES IN LEASE

80

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

563.77

## 19. PROPOSED DEPTH

13,500'

## 20. ROTARY OR CABLE TOOLS

Rotary

## 21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5344' GR

## 22. APPROX. DATE WORK WILL START\*

Dec. 20, 1984

## 23.

## PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
13 3/4"	10 3/4"	40.5	1500'	Returns to surface
9 3/4"	7 5/8"	26.4 - 29.7	10,200'	600 CF
6 3/4"	5 1/2"	20	13,500'	600 CF

Water rights from Floyd Angus or assigns have been filed with the State Engineer's office  
Vernal, Utah (water from Deep Creek)

Mr. Redcap, the surface owner has been contacted

The wellsite comprises a Allottee mineral lease in N $\frac{1}{2}$ NW $\frac{1}{4}$ , Section 30

CONFIDENTIAL

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

## 24.

SIGNED

TITLE

President

DATE

Dec 13-84

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING


APPROVED BY

TITLE

CONDITIONS OF APPROVAL, IF ANY:

DATE: 12/17/84  
BY: John A. Baya

SECTION 30  
TOWNSHIP 1 SOUTH, RANGE 2 EAST  
UINTAH SPECIAL BASE AND MERIDIAN  
UINTAH COUNTY, UTAH



QUINEX ENERGY CORP.

WELL LOCATION: N.W.¼, N.W.¼




SCALE 1"=1000'


SURVEYOR'S CERTIFICATE

I, Clinton S. Peatross, Duchesne, Utah, do hereby certify that I am a Registered Land Surveyor, and that I hold License No. 4779, as prescribed by the laws of the state of Utah, and that I have made a survey of the oil well location, as shown on this plat.

10/2/84  
Date

Clinton S. Peatross  
Clinton S. Peatross  
License No. 4779 (Utah)





## QUINEX ENERGY CORPORATION

2225 East Murray Holladay Road, Suite 100  
Salt Lake City, Utah 84117  
(801) 272-9093

Redcap J.D.C. #30-4-1A  
NW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E  
Uintah County, Utah  
December 13, 1984

### WELL PROGNOSIS

1. Surface Formation: Duchesne River formation

2. Estimated Formation Tops:

Green River Formation	6750'
Green River/Wasatch Transition	8700'
Wasatch Formation	9100'

3. Expected Mineral Bearing Depths:

Fresh Water	Surface to 1000'
Saline Water	1000 to TD
Oil & Gas	7500 to TD

4. Casing Program:

All casing is to be new.

Depth	Bit	Casing	Weight	Grade	Cement
Conductor-60'	30"	20"	Line Pipe		Cement to Surf.
Surf-1500'	13 3/4	10 3/4	40.5#	K55	Cement to Surf.
Surf-10,200	9 3/4	7 5/8	26#, 29#	N80	500 CF
10,200-13,500	6 3/4	5 1/2	20#	P110	500 CF

5. Pressure Control - See Attached Diagram:

Minimum 3000 PSI Double rams to be installed after setting Surface Pipe.

5000 PSI Double rams with Spherical BOP to be installed after setting 7 5/8" Long String.

BOP's to be tested to 3000 psi after installation and operated daily.

CONFIDENTIAL



6. Drilling Mud:

Well is to be drilled to 6500' with fresh water, Fresh gel mud, weighted with barite, as required, will be used from 6500' to TD. A minimum of 200 bbls of mud will be maintained in the mud tanks during normal operations. After setting the Long String, a minimum of 1000 sacks of barite will be on location.

7. Auxillary Equipment:

1) Top and bottom kelly cocks, (2) PVT equipment, and (3) stabbing valve will be maintained on the drilling floor, after reaching the top of the Wasatch fm. A Choke manifold with automatic choke and a gas buster will also be available when drilling overpressured intervals.

8. Formation Evaluation:

No cores or DST's are anticipated.

DIL - GR logs will be run from the Surface Pipe to TD.

CNL - FDC and mud logs will be run from 6,000' to TD.

9. Drilling Hazards:

Overpressured intervals are expected in the lower Wasatch Fm. Pressure control equipment, weighted muds, and mud monitoring, previously outlined will be adequate to maintain control of the well.

No other drilling hazards are anticipated.

10. Timing:

The anticipated spud date is December 27, 1984. Estimated drilling time is 80 days. The completion will take another 15 days.

December 13, 1984:



L. F. Wells  
Quinex Energy Corporation

CONFIDENTIAL

QUINEX ENERGY CORPORATION

DRILLING PROCEDURE

Field Bluebell Well Redcap J.D.C. #30-4-1A  
Location NE $\frac{1}{4}$ NW $\frac{1}{4}$  Sec. 30, T 1 S. R 2 E Duchesne County, Utah  
Drill x Deepen --- Elevation: GR 5344' KB --- Total Depth 13,500'  
Non-Op Interests ---

1. Casing Program (O = Old N = New)

	<u>Surface</u>	<u>O/N</u>	<u>Intermediate</u>	<u>O/N</u>	<u>Oil String/Liner</u>	<u>O/N</u>
Hole Size	<u>13 3/4"</u>		<u>9 3/4"</u>		<u>6 3/4"</u>	
Pipe Size	<u>10 3/4"</u>	<u>New</u>	<u>7 5/8"</u>	<u>New</u>	<u>5 1/2"</u>	<u>New</u>
Grade	<u>K-55</u>	<u>New</u>	<u>N-80</u>		<u>P-110 SFJ</u>	<u>New</u>
Weight	<u>40.5#</u>		<u>26.4-29.7</u>		<u>20#</u>	
Depth	<u>1,500'</u>		<u>10,200'</u>		<u>13,500'</u>	
Cement	<u>1200 sx</u>		<u>450 sx</u>		<u>800</u>	
Time WOC	<u>12 hrs.</u>		<u>24 hrs.</u>		<u>24 hrs.</u>	
Casing Test	<u>3500#</u>		<u>5000#</u>		<u>5000#</u>	
BOP	<u>1) 1-10" Series 900 Shaffer, Double gate. 2) 1-10 900 Hydril</u>					

Remarks ---

2. Mud Program

<u>Depth Interval</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Water Loss</u>
<u>Surf - 7,000'</u>	<u>water &amp; gel</u>	<u>8.5</u>	<u>35-45</u>	<u>---</u>
<u>7,000 - 10,200'</u>	<u>non dispersed low solids</u>		<u>32-34</u>	<u>10-12</u>
<u>10,200'- 13,500'</u>	<u>pre-mixed liquids w/ Barite added</u>		<u>35-45</u>	<u>"</u>
	<u>for weight control, (Do not over saturate)</u>			

3. Logging Program

Schlumberger  
Surface Depth 10,200' up to 3,500' GR/DIL 10,200' up to 6,000'  
Intermediate Depth Litho, Den/Compensated Neutron, Temp. Cyberlook 10,200'-T.D.  
Oil String Depth ---  
Total Depth ---

4. Mud Logging Unit Analex, Denver, CO  
Scales: 5"= 100' 6,000 to 13,500 ; --- to ---

5. Coring & Testing Program

	<u>Formations</u>	<u>Approximate Depth</u>	<u>Approximate Length of Core</u>
Core <u>---</u> DST <u>---</u>	<u>No cores nor DST's are programmed</u>		
Core <u>---</u> DST <u>---</u>			

6. Objectives & Significant Tops: Objectives: --- Production: Tertiary Wasatch "B" and Neola 3 Fingers. 2nd, Green River/Wasatch Transition

<u>Basal Green River.</u>	<u>Formations</u>	<u>Approximate Depth</u>	<u>Formations</u>	<u>Approximate Depth</u>
	<u>Green River</u>	<u>6750</u>		
	<u>Green River/Wasatch Trans.</u>	<u>8700</u>		
	<u>Wasatch</u>	<u>9100</u>		

7. Anticipated Bottom Hole Pressure: 10,500#

8. Completion & Remarks: A completion prognosis will be prepared, based on the outcome of the test well, prior to commencement of completion.

Compiled By: Debra L. Hume Approved By: L. Wells

CONFIDENTIAL

## DESIGNATION OF OPERATOR

The undersigned is, on the records of the Bureau of Land Management, holder of lease

DISTRICT LAND OFFICE: Oil and Gas Mining Lease  
SERIAL No.: 14 - 20 - H62 - 4065

and hereby designates

NAME: QUINEX ENERGY CORPORATION  
ADDRESS: 2225 East Murray Holladay Road - Suite 100  
Salt Lake City, Utah 84117

as his operator and local agent, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the supervisor or his representative may serve written or oral instructions in securing compliance with the Operating Regulations with respect to (describe acreage to which this designation is applicable):

Township 1 South, Range 2 East, Section 30, N $\frac{1}{2}$  NW $\frac{1}{4}$ : Uintah  
County, Utah. 80 Acres.

CONFIDENTIAL

It is understood that this designation of operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Operating Regulations. It is also understood that this designation of operator does not constitute an assignment of any interest in the lease.

In case of default on the part of the designated operator, the lessee will make full and prompt compliance with all regulations, lease terms, or orders of the Secretary of the Interior or his representative.

The lessee agrees promptly to notify the supervisor of any change in the designated operator.

*John D. Choresel*  
(Signature of lessee)

*Dec 4<sup>th</sup> - 1984*  
(Date)

*3385 Lucky John Dr.  
Park City, UTAH 84060*  
(Address)

APPLICANT'S CERTIF



I, Lewis Wells, do hereby certify that I am the hereinafter designated the applicant; that Clinton S going affidavit, is employed by the applicant as a 1 by the applicant to survey the location of a road ri the location of said right-of-way, 0.152 miles in le 44°45'36" East a distance of 1041.63 feet from the N R. 2E., USNM, Uintah County, Utah, and ending at a feet from said Northwest corner Section 30 is accurate survey as represented on this map has been adopted b tion of the right-of-way thereby shown; and that the the Secretary of the Interior or his duly authorized tion for said right-of-way to be granted the applica right to construct, maintain, and repair improvement poses and with the further right in the applicant, I this right-of-way by assignment, grant or otherwise.


This map is filed as part of the complete provisions of the Act of Feb. 5, 1948 (62 Stat. 17; 25 the Dept. of the Interior contained in Title 25, Code the grant of a right-of-way for ingress and egress.

Attest:

## Applic

**Title:**





HORZ. SCALE 1"=50'  
VERT. SCALE 1"=10'

NOTES -  
2525 Cu  
SOIL ST  
650 CuB  
5230 Cu  
920 FEE

ICATE

Representative for Quinex Energy Corp.,  
 . Pastors who subscribed to the fore-  
 and Surveyor and that he was directed  
 ght-of-way and to prepare this map, that  
 north beginning at a point being South  
 northwest corner of Section 30, T.15,  
 east being that a distance of 892.45'  
 fully represented on this map; that the  
 y the applicant as the definite loca-  
 map has been prepared to be filed with  
 representative as part of the applica-  
 nt. its successors and assigns, with the  
 s, therein and hereafter, for each par-  
 ts successors and assigns, to transfer  
 cation pursuant to the terms and pro-  
 U.S.C. 3221, and to the regulations of  
 of Federal Regulations, Part 169, for

ant:


*Stella*  
 President

Quinex Energy Corp.

NATURAL  
 GROUND

105'

FINISH GRADE = 5345




Job #246

# SURVEYOR'S AFFIDAVIT AND FIELDNOTES

State of Utah.....  
County of Duchesne.....

Clinton S. Peatross, being first duly sworn, depose and state that I am a Registered Land Surveyor, and that I hold License No. 4779, as prescribed by the laws of the state of Utah, that the survey was prepared by me; that I have examined the notes of the survey for a road and pipeline right-of-way as described and shown on this map, that the map was prepared under my direction from said notes; and that said right-of-way being 0.142 miles in length and beginning at a point being South 44°45'36" East a distance of 1043.63 feet from the Northwest corner of Section 30, Township 1 South, Range 2 East, Uintah Special Base and Meridian, Uintah County, Utah; thence the following 4 courses to the Point of Termination, North 18°24'44" East a distance of 253.00 feet; thence North 25°07' East a distance of 124.54 feet; thence North 7°55' East a distance of 1044.44 feet; thence North 1°00' East a distance of 228.17 feet; thence North 10°00' East a distance of 155.40 feet to the Point Of Termination; said point being on the North line said section a distance of 872.45 feet East of said Northwest section corner; I further certify that this is accurately shown on this map.

*Clinton S. Peatross*  
Clinton S. Peatross  
License No. 4779 (Utah)



Subscribed and sworn to before me this 3rd day of Oct, 1984

*Clis Peatross*  
Notary Public. My commission expires November 16, 1987.

JOB # 246


10/2/84

PREPARED FOR  
QUINEX ENERGY CORP.  
2225 EAST 4800 SOUTH SALT LAKE CITY, UTAH 84117

QUINEX - J.D.C. #30-4-1A  
N.W. 1/4, N.W. 1/4, SECTION 30, T.1S., R.2E., ASB&M  
UINTAH COUNTY, UTAH

PREPARED BY  
**PEATROSS LAND SURVEYS**

REGISTERED LAND SURVEYORS  
P.O. BOX 271  
DUCHESNE, UTAH 84021  
(801) 738-2386



QUINEX - JOB # 30-4-1A

BIG YARDS CUT FOR TOP  
DICK HILL (STRIP 1/2)  
BIG YARDS CUT PIT  
BIG YARDS FILL (IMPORT) FOR PAD  
T OF NEW ROAD CONSTRUCTION


APPLICANT'S CERTIFICATE

I, Lewis Wells, do hereby certify that I am the hereinafter designated the applicant; that Clinton going affidavit, is employed by the applicant as a by the applicant to survey the location of a road the location of said right-of-way, 0.174 miles in 44°45'36" East a distance of 1043.63 feet from the R.2E., T.28N., W.28W., Uintah County, Utah, and ending at a feet from said Northwest corner Section 30 is accu survey as represented on this map has been adopted tion of the right-of-way thereby shown; and that t the Secretary of the Interior or his duly authoriza tion for said right-of-way to be granted the appli right to construct, maintain, and repair improve poses and with the further right in the applicant, this right-of-way by assignment, grant or otherwise



This map is filed as part of the complete app visions of the Act of Feb. 5, 1948 (62 Stat. 17; 2 the Dept. of the Interior contained in Title 25, Co the grant of a right-of-way for ingress and egress

Attest: C.R. Welton

Appl  
Titl







HORZ. SCALE 1"=50'  
 VERT. SCALE 1"=10'



NOTES-  
 2525 C  
 SOIL ST  
 650 C  
 5230 C  
 920 FE

IFICATE


he Representative for Quinex Energy Corp.,  
S. Postross who subscribed to the fore-  
Land Surveyor and that he was directed  
 right-of-way and to prepare this map; that  
 length beginning at a point being South  
 Northwest corner of Section 30, T.1S.,  
 point being East a distance of 1098.70  
 cately represented on this map; that the  
 by the applicant as the definite loca-  
 ne map has been prepared to be filed with  
 ad representative as part of the applica-  
 cant, its successors and assigns, with the  
 its, thereon and thereafter, for such pur-  
 its successors and assigns, to transfer  
 e.  
 lication pursuant to the terms and pro-  
 5 U.S.C. 323), and to the regulations of  
 e of Federal Regulations, Part 169, for

licant:

President  
Quinex Energy Corp.



Job #246




# SURVEYOR'S AFFIDAVIT AND FIELDNOTES

State of Utah.....  
 County of Duchesne.....

Clinton S. Peatross, being first duly sworn, depose and state that I am a Registered Land Surveyor, and that I hold License No. 4779, as prescribed by the laws of the state of Utah, that the survey was prepared by me; that I have examined the notes of the survey for a road and pipeline right-of-way as described and shown on this map, that the map was prepared under my direction from said notes; and that said right-of-way being 6.174 miles in length and beginning at a point bearing South 44°45'36" East a distance of 1043.63 feet from the Northwest corner of Section 30, Township 1 South, Range 2 East, Uintah Special Base and Meridian, Uintah County, Utah; thence the following 5 courses to the Point of Termination, North 18°24'44" East a distance of 253.00 feet; thence North 25°07' East a distance of 124.54 feet; thence North 65°06'32" East a distance of 266.82 feet; thence North 100°36'33" East a distance of 129.09 feet; thence North 19°36'21" East a distance of 155.40 feet to the Point of Termination; said point being on the North line said section a distance of 1098.70 feet East of said Northwest section corner; I further certify that this is accurately shown on this map.

*Clinton S. Peatross*  
 Clinton S. Peatross  
 License No. 4779 (Utah)



Subscribed and sworn to before me this 3rd day of Oct, 1987  
*Clas Peatross*  
 Notary Public. My commission expires November 16, 1987.

JOB # 246

10/2/84

1000 YARDS CUT FOR TOP  
 2000 YARDS (STRIP 12)  
 1000 YARDS CUT PIT  
 1000 YARDS FILL (IMPORT) FOR PAD  
 T OF NEW ROAD CONSTRUCTION



PREPARED FOR <b>QUINEX ENERGY CORP.</b> 2225 EAST 4800 SOUTH SALT LAKE CITY, UTAH 84117
QUINEX - J.D.C. #30-4-1A Redcap N.W. 1/4, N.W. 1/4, SECTION 30, T.1S., R.2E., USB&M UTAH COUNTY, UTAH
PREPARED BY <b>PEATROSS LAND SURVEYS</b> REGISTERED LAND SURVEYORS P.O. BOX 271 DUCHESNE, UTAH 84021 (801) 738-2386

QUINEX - JDC #30-4-1A



STATE OF UTAH  
NATURAL RESOURCES  
Oil, Gas & Mining

Scott M. Matheson, Governor  
Temple A. Reynolds, Executive Director  
Dianne R. Nielson, Ph.D., Division Director

4241 State Office Building • Salt Lake City, UT 84114 • 801-533-5771

December 17, 1984

Quinex Energy Corporation  
2225 East Murray Holladay Rd., #100  
Salt Lake City, Utah 84117

Gentlemen:

Re: Well No. Redcap J. D. C. #30-4-1A - NW NW Sec. 30, T. 1S, R. 2E  
876' FNL, 669' FWL - Uintah County, Utah

Approval to drill the above referenced oil well is hereby granted in accordance with Order of Cause No. 131-27 dated April 16, 1975 subject to the following stipulations:

1. Prior to commencement of drilling, receipt by the Division of evidence providing assurance of an adequate and approved supply of water.

In addition, the following actions are necessary to fully comply with this approval:


1. Spudding notification to the Division within 24 hours after drilling operations commence.
2. Submittal to the Division of completed Form OGC-8-X, Report of Water Encountered During Drilling.
3. Prompt notification to the Division should you determine that it is necessary to plug and abandon this well. Notify John R. Baza, Petroleum Engineer, (Office) (801) 538-5340, (Home) 298-7695 or R. J. Firth, Associate Director, (Home) 571-6068.
4. Compliance with the requirements and regulations of Rule C-27, Associated Gas Flaring, General Rules and Regulations, Oil and Gas Conservation.

Quinex Energy Corporation  
Well No. Redcap J.D.C. #30-4-1A  
December 17, 1984  
Page 2

5. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-31591.

Sincerely,



R. J. Firth  
Associate Director, Oil & Gas

as

Enclosures

cc: Branch of Fluid Minerals  
Bureau of Land Management

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☐

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL  
WELL ☒

GAS  
WELL ☐

OTHER

SINGLE  
ZONE ☐

MULTIPLE  
ZONE ☒

2. NAME OF OPERATOR

QUINEX ENERGY CORPORATION

3. ADDRESS OF OPERATOR

2225 East Murray Holladay Rd., #100, Salt Lake City, Utah 84117

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)\*

At surface  
876' S of N line, 669' E of W line, Sec. 30, T 1 S, R 2 E

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

3 3 miles southwest of LaPoint, Utah

15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST  
PROPERTY OR LEASE LINE, FT.  
(Also to nearest drlg. unit line, if any)

16. NO. OF ACRES IN LEASE

80

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

563.77

18. DISTANCE FROM PROPOSED LOCATION\*

TO NEAREST WELL, DRILLING, COMPLETED,  
OR APPLIED FOR, ON THIS LEASE, FT.

N.A.

19. PROPOSED DEPTH

13,500'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5344' GR

22. APPROX. DATE WORK WILL START\*

Dec. 20, 1984

23.


PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
13 3/4"	10 3/4"	40.5	1500'	Returns to surface
9 3/4"	7 5/8"	26.4 - 29.7	10,200'	600 CF
6 3/4"	5 1/2"	20	13,500'	600 CF

Water rights from Floyd Angus or assigns have been filed with the State Engineer's office  
Vernal, Utah (water from Deep Creek)

Mr. Redcap, the surface owner has been contacted

The wellsite comprises a Allottee mineral lease in N<sup>1</sup>/<sub>2</sub>NW<sup>1</sup>/<sub>4</sub>, Section 30



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

*[Signature]*

TITLE

*President*

DATE

*Dec 13 - 84*

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

*[Signature]*

TITLE

DISTRICT MANAGER

DATE

*12-20-84*

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

21080-5M-093

CONDITIONS OF APPROVAL ATTACHED  
TO OPERATOR'S COPY

OGIM

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL  
WITHIN THE UINTAH OURAY RESERVATION

Company Quinex Energy Corp. Well No. 30-4-1A

Location Sec. 30 T1S R2E Lease No. 14-20-H62-4065

Onsite Inspection Date 12-11-84

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Order No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A. DRILLING PROGRAM

1. All fresh water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

BOP and choke manifold systems will be consistent with API RP 53. Pressure tests will be conducted before drilling out from under all casing strings which are set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection recorded on the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

The District Office should be notified, with sufficient lead time, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Prior to drilling out the surface casing shoe, the ram-type and bag-type preventers shall be tested to 2,100 psi.

The District Office should be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing strings and cementing.

4. Mud Program and Circulating Medium

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the authorized officer (AO).

6. No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The spud date will be reported orally to the AO within 48 hours after spudding. If the spudding occurs on a weekend or holiday, the report will be submitted on the following regular work day. The oral report will be followed up with a Sundry Notice.

In accordance with Onshore Oil and Gas Order No. 1, this well will be reported on Form 3160-6 "Monthly Report of Operations", starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report will be filed, in duplicate, to the Vernal BLM District Office, 170 South 500 East, Vernal, Utah 84078.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.



Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than 5 days following the date on which the well is placed on production.

Pursuant to NTL-2B, with the approval of a District Engineer, produced water may be temporarily disposed of into unlined pits for a period of up to 90 days. During the period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the District Engineer.

Pursuant to NTL-4A, lessees or operators are authorized to vent/flare gas during initial well evaluation tests, not exceeding a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the District Engineer and approval received, for any venting/flaring of gas beyond the initial 30 day or authorized test period.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in 43 CFR 3162.7 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

A first production conference will be scheduled within 15 days after receipt of the first production notice.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within 30 days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

Pursuant to Onshore Oil and Gas Order No. 1, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in a manner which conforms with applicable Federal laws and regulations and with State and local laws and regulations to the extent that such State and local laws are applicable to operations on Federal or Indian lands.

B. THIRTEEN POINT SURFACE USE PLAN

7. Planned Access Roads

All travel will be confined to existing access road rights-of-way.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved right-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

8. Location of Tank Batteries and Production Facilities

If a tank battery is constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain  $1\frac{1}{2}$  times the storage capacity of the battery.

All loading lines will be placed inside the berm surrounding the tank battery.

All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with the API standards for liquid hydrocarbons and the AGA standard for natural gas measurement.

9. Methods of Handling Waste Disposal

Storage tanks will be used if drill sites are located on tribal irrigable land or on lands under crop production. All reserve pits will be lined. Two pounds dry bentonite liner per square foot, unless determined inadequate during construction. BIA personnel will inspect the reserve pit during construction.

Burning will not be allowed.

Produced waste water will be confined to a lined pit for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, along with required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance, and will be grounds for issuing a shut-in order.

10. Well Site Layout

The reserve pit will be located on the west side of the location-centered on point No. 9.

The stockpiled topsoil will be stored on the southwest corner of the location near point No. 8.

Access to the well pad will be from the north near Fl.

11. Plans for Restoration of Surface

Immediately upon completion of drilling, the location and surrounding area will be cleared of all debris, materials, trash and junk not required for production.

Before any dirt work to restore the location takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc. will be removed. If a plastic nylon reinforced liner is used, it should be torn and shredded before backfilling of the reserve pit.

Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.

Seed will be broadcast or drilled at a time specified by the BIA. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.

BIA will supply a seed mixture at the time of restoration.

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) reestablishing irrigation systems where applicable, (b) reestablishing soil conditions in irrigated fields in such a way as to insure cultivation and harvesting of crops, and (c) insuring revegetation of the disturbed areas to the specifications of the BIA at the time of abandonment.

12. Surface and Mineral Ownership

Ute Indian allotted surface and Indian minerals.

13. Other Information

Once production starts, the whole location will be fenced and a gate and cattleguard will be installed at the entrance.

There will be no deviation from the proposed drilling and/or work-over program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

This permit will be valid for a period of one year from the date of approval. After permit termination, a new application will be filed for approval for any future operations.

14. Lessee's or Operators Representative and Certification

All roads constructed by operators on the Uintah and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) the name of the operator, (b) that firearms are prohibited to all non-Ute Tribal members, (c) that permits must be obtained from the B.I.A. before cutting firewood or other timber products and (d) only authorized personnel permitted.



United States Department of the Interior  
BUREAU OF INDIAN AFFAIRS  
UINTAH AND OURAY AGENCY

Fort Duchesne, Utah 81026  
(801) 722-2406 Ext. 33, 34

IN REPLY REFER TO:

Real Property Management  
Ten. and Mgmt.

DEC 17 1984

MEMORANDUM

TO: District Manager, Bureau of Land Management

FROM: **Acting**  
Superintendent, Uintah and Ouray Agency

SUBJECT: Quinex Energy Corporation, Well JDC 30-4-1A  
in the NW $\frac{1}{4}$ , Section 30, T. 1 S., R. 2 E., Uinta meridian, Utah.

We (concur with or, recommend) approval of the Application for Permit to Drill subject well.


Based on available information on December 17, 1984, we have cleared the proposed location in the following areas of environmental impact.

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>	Listed threatened or endangered species.
YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>	Critical wildlife habitat.
YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>	Archaeological or cultural resources.
YES	<input type="checkbox"/>	NO	<input type="checkbox"/>	Air quality aspects (to be used only if project is in or adjacent to a Class I area of attainment)
YES	<input type="checkbox"/>	NO	<input type="checkbox"/>	Other (if necessary)

REMARKS: Pit fenced, cattle guards placed at entrance into pasture and at location entrance, location reversed to place pit on west side of pad, access road re-routed, whole location fenced once production starts, pit lined with 2 lbs. dry Bentonite per square foot, unless determined inadequate during construction. BIA personnel will inspect pit during construction.

The necessary surface protection and rehabilitation requirements are as per approved APD.

*Reggie L. Coover*






STATE OF UTAH  
NATURAL RESOURCES  
Water Rights

23 East Main Street • P.O. Box 879 • Vernal, UT 84078 • 801-789-3714

Scott M. Matheson, Governor  
Temple A. Reynolds, Executive Director  
Dee C. Hansen, State Engineer

December 28, 1984



*Quincy*

John Robert Justice  
P. O. Box 719  
Roosevelt, Utah 84066

RE: Temporary Change 84-43-96

Dear Mr. Justice:

The above numbered Temporary Change Application has been approved, subject to prior rights.

A copy is herewith returned to you for your records and future reference.

Sincerely yours,

*G. Blake Wahlen*

G. Blake Wahlen  
for Dee C. Hansen, P. E.  
State Engineer

DCH:GBW/ln

Enclosure

cc: Oil, Gas & Mining

Kenneth J. Young  
Roosevelt, Utah 84066

APPLICATION NO. 84-43-96  
DISTRIBUTION SYSTEMApplication For Temporary Change of Point of Diversion,  
Place or Purpose of Use  
STATE OF UTAH

(To Be Filed in Duplicate)

Vernal, Utah

Place

December 21, 1984

Date

For the purpose of obtaining permission to temporarily change the point of diversion, place or purpose of use  
(Strike out written matter not needed)

- of water, the right to the use of which was acquired by 43-716  
(Give No. of application, title and date of Decree and Award No.)  
to that hereinafter described, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.
- The owner of right or application is John Robert Justice and Charman Justice
  - The name of the person making this application is John Robert Justice
  - The post office address of the applicant is P O Box Lapoint, Utah 84039 84066

## PAST USE OF WATER

- The flow of water which has been used in second feet is 1.714 cfs.
- The quantity of water which has been used in acre feet is none
- The water has been used each year from 1 (Month) to 12 (Month) 1 (Day) to 31 (Day) incl.
- The water has been stored each year from 1 (Month) to 12 (Month) 1 (Day) to 31 (Day) incl.
- The direct source of supply is Deep Creek in Uintah County.
- The water has been diverted into a pond at a point located N. 400' from the SE corner of Section 24, T1S, R1E 1) N. 740' W. 1080' from SE Cor. Sec. 17 T1N. R2E USBEM; 2) N. 200' W. 70' from S 1/4 Cor. Sec. 20 T1N. R2E. USBEM.
- The water involved has been used for the following purpose: stock watering & irrigation

Total                      acres.

NOTE: If for irrigation, give legal subdivisions of land and total acreage which has been irrigated. If for other purposes, give place and purpose of use.

## THE FOLLOWING TEMPORARY CHANGES ARE PROPOSED

- The flow of water to be changed in cubic feet per second is
- The quantity of water to be changed in acre-feet is 3 acre feet per well
- The water will be diverted into the pipeline ditch at a point located N. 400' from the SE corner of Section 24, T1S, R1E canal
- The change will be made from December 13 19 84 to December 13 19 85  
(Period must not exceed one year)
- The reasons for the change are drilling of oil well for Quinex Energy Corporation
- The water involved herein has heretofore been temporarily changed n/a years prior to this application.

(List years change has been made)

- The water involved is to be used for the following purpose: Drilling of the Redcap-JDC  
1-30-A2E in Section 30, T1S, R2E, Uintah County, Utah

30-4-1ATotal                      acres.

NOTE: If for irrigation, give legal subdivisions of land to be irrigated. If for other purposes, give place and purpose of proposed use.

## EXPLANATORY

Water will be pumped from a point N. 400' from SE corner of Section 24.

The 3" line will go through a culvert under the highway &amp; run to a

clay lined earthen reserve pit 1100' from NE corner of Section 30,

T1S, R2E

A filing fee in the sum of \$5.00 is submitted herewith. I agree to pay an additional fee for either investigating or advertising this change, or both, upon the request of the State Engineer.

John Robert Justice  
Signature of Applicant

## RULES AND REGULATIONS

(Read Carefully)

This application blank is to be used only for temporary change of point of diversion, place or nature of use for a definitely fixed period not to exceed one year. If a permanent change is desired, request proper application blanks from the State Engineer.

Application for temporary change must be filed in duplicate, accompanied by a filing fee of \$7.50. Where the water affected is under supervision of a Water Commissioner, appointed by the State Engineer, time will be saved if the Application is filed with the Commissioner, who will promptly investigate the proposed change and forward both copies with filing fee and his report to the State Engineer. Applications filed directly with the State Engineer will be mailed to the Water Commissioner for investigation and report. If there be no Water Commissioner on the source, the Application must be filed with the State Engineer.

When the State Engineer finds that the change will not impair the rights of others he will authorize the change to be made. If he shall find, either by his own investigation or otherwise, that the change sought might impair existing rights he shall give notice to persons whose rights might be affected and shall give them opportunity to be heard before acting upon the Application. Such notice shall be given five days before the hearing either by regular mail or by one publication in a newspaper. Before making an investigation or giving notice the State Engineer will require the applicant to deposit a sum of money sufficient to pay the expenses thereof.

Address all communications to:

State Engineer  
State Capitol Building  
Salt Lake City, Utah

### STATE ENGINEER'S ENDORSEMENTS

(Not to be filled in by applicant)

Change Application No. .... (River System)

1. .... Application received by Water Commissioner .....  
(Name of Commissioner)
- Recommendation of Commissioner .....
2. 12/24/84 Application received over counter by mail in State Engineer's Office by GBW
3. .... Fee for filing application, \$7.50 received by ..... ; Rec. No. ....
4. .... Application returned, with letter, to ..... for correction.
5. .... Corrected application resubmitted over counter by mail to State Engineer's Office.
6. .... Fee for investigation requested \$ .....
7. .... Fee for investigation \$ ..... received by ..... ; Rec. No. ....
8. .... Investigation made by ..... ; Recommendations: .....
9. .... Fee for giving notice requested \$ .....
10. .... Fee for giving notice \$ ..... received by ..... ; Rec. No. ....
11. .... Application approved for advertising by publication by mail by .....
12. .... Notice published in .....
13. .... Notice of pending change application mailed to interested parties by ..... as follows: .....
14. .... Change application protested by .....  
(Date Received and Name)
15. .... Hearing set for ..... at .....
16. .... Application recommended for rejection approval by .....
17. 12/27/84 Change Application rejected approved and returned to GBW

THIS APPLICATION IS APPROVED SUBJECT TO THE FOLLOWING CONDITIONS:

1. ....
2. ....
3. ....

DEE C. HANSEN, P. E.

State Engineer

FOR



DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**SPUDDING INFORMATION

API #43-047-31591

NAME OF COMPANY: QUINEXWELL NAME: Red Cap J.D.C. #30-4-1ASECTION NW NW 30 TOWNSHIP 1S RANGE 2E COUNTY UintahDRILLING CONTRACTOR Montgomery DrillingRIG # 32SPUDDED: DATE 3-10-85TIME 11:00 AMHOW Rotary

DRILLING WILL COMMENCE \_\_\_\_\_

REPORTED BY L. F. WellsTELEPHONE # 278-8100DATE 3-11-85 SIGNED SB

CONFIDENTIAL

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

APR 26 1985

1. oil ☒ well gas ☐ well other ☐  
2. NAME OF OPERATOR Quinex Energy Corporation  
3. ADDRESS OF OPERATOR 2225 E. Murray Holladay Rd., SLC, Ut  
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: C, NW $\frac{1}{4}$ , Sec. 30, T 1 S, R 2 E  
AT TOP PROD. INTERVAL:  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:  
TEST WATER SHUT-OFF ☐ ☐  
FRACTURE TREAT ☐ ☐  
SHOOT OR ACIDIZE ☐ ☐  
REPAIR WELL ☐ ☐  
PULL OR ALTER CASING ☐ ☐  
MULTIPLE COMPLETE ☐ ☐  
CHANGE ZONES ☐ ☐  
ABANDON\* ☐ ☐  
(other) Run & cement 10 3/4" casing

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

From March 10, 1985 the Redcap JDC 30-4-1A well was drilled with a 14 3/4" hole to a depth of 1540' 3/15/85. At that time we ran 37 joints of 10 3/4" casing, 40.5#, 1500.35 feet. Cemented casing with 790 sacks of B.J. Lite and 200 sacks of class "G" cement with 40# celoflake and 198# CaCl. Had 40 bbls. of cement return to surface.

Drilled 9 7/8" hole out from under th 10 3/4" surface casing.

5. LEASE  
14-20-H62-4065  
6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
Redcap  
7. UNIT AGREEMENT NAME  
  
8. FARM OR LEASE NAME  
  
9. WELL NO.  
Redcap JDC 30-4-1A  
10. FIELD OR WILDCAT NAME  
Bluebell  
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA  
NW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E  
12. COUNTY OR PARISH Uintah 13. STATE Utah  
14. API NO.  
43-047-31591  
15. ELEVATIONS (SHOW DF, KDB, AND WD)  
5344 GR-- 5369 KB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Pres. DATE 4-24-85

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

# CONFIDENTIAL

Form 9-331  
Dec. 1973

Form Approved.  
Budget Bureau No. 42-R1424

## UNITED STATES DEPARTMENT OF THE INTERIOR GEOLOGICAL SURVEY

### SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ well    gas ☐ well    other ☐

2. NAME OF OPERATOR  
Quinex Energy Corporation

3. ADDRESS OF OPERATOR  
2225 East Murray Holladay Rd. SLC, Ut

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: C. NW $\frac{1}{4}$ , Sec. 30, T 1 S, R 2 E  
AT TOP PROD. INTERVAL:  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <u>Run &amp; cement 7 5/8" intermediate casing.</u>	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

The Redcap JDC 30-4-1A well drilled a 9 7/8" hole to a depth of 10,400' at which time we ran 7 5/8" casing--71 joints of N-80, 29.7# (2973.43') and 167 joints of N-80, 26.4# (7408.36') for a total of 238 joints, set at 10,362.79'. Cemented with 270 sacks of B.J. Lite and 300 sacks of Class "H" cement. Bumped float collar with 484 bbls. of fluid. Pressure tested 7 5/8" casing and BOP's to 5000 psi. Held OK.

Drilled 6 3/4" hole out from under 7 5/8" casing.

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Pres DATE 4-24-85

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

5. LEASE  
14-20-H62-4065

6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
Redcap

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

9. WELL NO.  
Redcap JDC 30-4-1A

10. FIELD OR WILDCAT NAME  
Bluebell

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA  
NW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E

12. COUNTY OR PARISH  
Uintah

13. STATE  
Utah

14. API NO.  
43-047-31591

15. ELEVATIONS (SHOW DF, KDB, AND WD)  
5344 GR---5369 KB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

Geology Report

QUINEX ENERGY CORPORATION

Redcap J.D.C 30-4-1A

NW NW Sec. 30, T. 1S., R. 2 E.  
Uintah County, Utah

A. P. I. No. 43-047-31591

Elevation: G.R. 5,344' - K.B. 5,369

CONFIDENTIAL

QUINEX ENERGY CORPORATION  
Geology Report

Redcap J.D.C. 30-4-1A

The Quinex Energy Corporation, Redcap J.D.C. 30-4-1A well was spudded on March 11, 1985 and drilled to a total depth of 13,550 feet, which depth was reached on May 15, 1985. The geophysical logs were run by schlumberger-Vernal, Utah and Gearhart-Vernal, Utah. In addition, 12 side wall cores were cut by Gearhart, using a diamond core-head wireline tool. A total of 11 cores were recovered.

The following formation tops were determined from well logs and sample description:

<u>Formation or Member</u>	<u>Depth in Feet</u>	<u>Elevation</u>
Uinta Formation	2,315'	+3,057'
Green River Formation	5,828'	- 456'
Black Shale	8,906'	-3,534'
Wasatch Transition Zone	9,104'	-3,732'
Wasatch Formation	9,547'	-4,175'
Wasatch B	12,596'	-7,224'
Neola 3 Fingers	12,969'	-7,597'

The geology of the area is similar to the Bluebell and Bluebell East part of the Greater Altamont-Bluebell Field of the Uinta Basin and is considered to be part of this field. The lithologies of formations have similar composition, textures and fossils as found in the Hayden area of the Bluebell Field which is located 6 miles west of the Redcap J.D.C. well.

The well was spudded in the Duchesne River Formation which is dated as Late Eocene-Early Oligocene age and is composed of red and green mudstone, sandstone, and conglomerate with minor occurrence of tuffs. The porous formations are saturated with fresh water with minor saline, carbonate and sulfate ion content. The Uinta Formation was encountered at 2315' and extended to 5825' in depth. It is composed of red and green mudstone and sandstone with minor occurrence of

conglomerate, limestone and volcanic tuffs. The lower part of the Uinta Formation contains minor units of lacustrine origin, indicative of a fluctuating change from the underlying Green River Formation. It is dated as Middle and Late Eocene in age and represents a continuation of the fluvial deposition found in the overlying Duchesne River Formation.

The Green River Formation was topped at 5828' and bottomed at 9104'. No attempt was made to differentiate it into members except the lowermost member, the Black Shale Facies which was present from 8906' to 9104'. The Black Shale Facies is thinning toward the east from the Bluebell area. The formation is composed of marlstone, shale, mudstone, limestone, dolomite, sandstone, evaporites, siltstone and minor volcanic tuffs. Numerous beds designated as marlstone contain sufficient organic content to be designated as oil shale. The formation is dated as Early and Middle Eocene and represents lithologies deposited in a lacustrine environment. All members of the formation are recognized in the area of the Redcap J.D.C. well.

The Wasatch and Wasatch Transition are similar to the units located in the Bluebell and Bluebell East Field. The Wasatch Transition was present from 9104' to 9547' and was composed of sandstone, conglomerate, red and grey-green mudstone, and minor limestone. It represents a transition between the lacustrine environment of the Green River and the continental-fluvial environment of deposition present in the Upper Wasatch. The Wasatch Formation is composed of an upper fluvial-continental sequence and a lower lacustrine sequence with additional fluvial-continental rocks at the base. The main lacustrine facies is located below 11,900 feet in the well. The overlying fluvial-continental sequence is composed of red and grey-green mudstone, sandstone and very minor anhydrite and limestone. The lacustrine facies consists of similar lithologies to the Green River Formation. It is composed of marlstone, shale, mudstone, sandstone, siltstone limestone and dolomite, all of lacustrine environment with minor continental-fluvial units.

A noted occurrence in the lacustrine facies of the Wasatch Formation was the presence of abundant gilsonite type solid hydrocarbon, representing fracture fillings by the rare solid black waxy hydrocarbon.

The Wasatch Formation has been dated as being of Paleocene age. The Wasatch has been divided into the Colton, Flagstaff and North Horn by some workers, with the Flagstaff being a limestone-dolomite section of lacustrine origin which was cut in the Redcap J.D.C. at 1259' to 12,647'.

The following shows were encountered in the Quinex Energy Corporation Redcap J.D.C. 30-4-1A well:

<u>Show #</u>	<u>Interval</u>	<u>Calculated Units</u>	<u>Mud At</u>	<u>Gas Kicks, Comments</u>
1.	5,524-40	12,873 units	8.4	1200 units, lt. brn oil
2.	6,210-18	100 "	8.4	56 " , oil, sat. sd.
3.	6,380-90	2,115 "	8.4	340 " , tr oil film
4.	6,498-500	272 "	8.4	160 " ,
5.	6,528-32	1,032 "	8.4	225 " , bk oil increase
6.	7,846-54	238 "	8.4	125 "
7.	8,052-66	592 "	8.4	252 "
8.	8,222-38	855 "	8.4	220 " , sl oil sat
9.	8,550-700	150 "	8.4	90 " , oil sat sd
10.	8,980-9000	1,180 "	8.7	320 " , bk oil to surf
11.	9,118-40	1,734 "	8.8	550 " , oil increase
12.	9,898-9916	845 "	8.7	110 " , oil stn ss
13.	10,072-78	217 "	8.7	60 " , oil stn ss
14.	11,062-72	469 "	10.0	190 "
15.	11,470-76	82 "	10.0	53 "
16.	11,819-56	43 "	10.0+	41 "
17.	11,890-900	1,253 "	10.0+	642 " , bk oil to surf
18.	11,936-58	5,990 "	10.1	1,344 " , grn oil to surf
19.	11,974-86	10,787 "	10.1	1,200 " , grn oil to surf
20.	12,018-24	10,809 "	10.1	1,500 " , oil increase
21.	12,064-70	1,059 "	10.1	507 " , blk oil incr

Show #	Interval	Calculated	Units				
22.	12,078-84	4,302	"	10.1	1,800	"	, oil incr
23.	12,108-26	84,380	"	10.1	5,230	"	, abdt oil
24.	12,156-62	12,760	"	10.1	2,990	"	, incr oil
25.	12,154-60	2,795	"	11.4	565	"	, incr blk oil
26.	12,278-300	12,834	"	11.4	9,600	"	, abdt brn oil
27.	12,364-58	560	"	12.0	280	"	
28.	12,584-96	30,340	"	12.5	2,240	"	, incr oil
29.	12,618-30	3,417	"	12.5	960	"	, tr blk oil
30.	12,704-50	4,514	"	12.5	1,630	"	, brn oil incr
31.	12,778-80	25,401	"	12.5	7,440	"	, oil incr
32.	12,836-70	103,895	"	12.5	14,380	"	, abdt grn oil 20 ft. flare
33.	12,878-84	14,725	"	12.5	5,500	"	, abdt grn oil 15-20 ft flare
34.	12,916-30	18,878	"	12.6	3,100	"	, abdt blk oil over shaker, 15-20 ft flare
35.	12,948-58	122,500	"	12.6	15,400	"	, abdt grn oil over shaker, 20 ft flare
36.	13,000-004	13,564	"	13.1	1,900	"	, abdt grn oil over shaker, 3 ft flare
37.	13,028-30	29,111	"	13.1	4,000	"	, incr oil to surf 4 ft flare
38.	13,066-72	11,397	"	13.1	2,300	"	, oil sat sd
39.	13,170-80	14,092	"	13.1	7,250	"	, oil incr 4 ft flare
40.	13,274-94	49,437	"	13.1	1,001	"	, sl oil incr
41.	13,320-52	22,909	"	13.1	2,800	"	, grn oil to surf
42.	13,457-74	28,960	"	13.2	4,800	"	, dk grn oil incr
43.	13,482-88	2	"	13.2+			oil stn in sd



The top of the over-pressure zone was reached with the oil show at approximately the 13,100 foot depth. Shows found above this zone may be considered for recompletion after the well has produced for some time from the Wasatch Formation over-pressure zone.

Side wall cores were obtained by use of the Gearhart wireline side wall diamond coring device. This tool allowed collection of data not available in the area, excepting the very costly diamond core, not usually run in the Altamont-Bluebell Field. The core points were selected from Density-Neutron logs and from areas where the Caliper log indicated a good potential for recovery of the side wall core. Recovery was excellent, with 11 cores recovered from the 12 cores cut. The core data indicated that porosity data as read from the Compensated Neutron Formation Density Log was reliable when the drill hole was in gauge.

The Quinex Redcap J.D.C. 30-4-1A well was selectively perforated in 13 zones from 12,101 through 13,476 feet on June 18, 1985. The pressures built up to a stable pressure of 3000 psi on the wellhead during perforation. The well was tested, flowing yellow-green oil and gas, then prepared for acid fracing. It was acidized on June 24 with 20,000 gallons of 15% HCl, 280,000 cu. ft. of Nitrogen and 160 gallons of corrosion inhibitor. Average breakdown pressure was 9,980 psi. Shut in pressure after acid frac was 5,900 psi.

Following the acid frac the well was completed, flowing through a 12/48" choke at a rate of 673.4 barrels of oil, 18.54 barrels of acid water and 420 m.c.f. gas. The flow pressure during completion testing was 2,200 psi.



De Forrest Smouse  
Consulting Geologist



OPERATOR ANIRIX ENERGY CORP  
WELL RESCAP J.B.C. 30 - 4 - A1

SEC 30 TWP 1E RNG 2E  
JOB# 04660 UTMAR CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 1 Formation KINTAN F.M. Time 11:00 am  
Date 3/29/85

Depth Interval from 5524' to 5540' with X liberated \_\_\_\_\_ produced gas

Gross Ft 16 Net Ft 10

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	5.2	30	30	0.5	.38	.003	.001	0	0	0	0
5524	1.4	30	30	0.5	.38	.003	.001	0	0	0	0
5526	0.5	30	30	0.5	.38	.003	.001	0	0	0	0
5528	0.4	30	30	0.5	.38	.003	.001	0	0	0	0
5530	0.4	30	30	0.5	.38	.003	.001	0	0	0	0
5532	0.4	200	200	2.0	.84	.031	.01	0	16.4	51.1	0
5534	0.4	600	600	6.0	3.84	.10	.075	.104	35.7	46.8	33.3
5536	0.9	900	900	9.0	4.75	.15	.095	.138	29.7	46.5	31.7
5538	2.1	1200	1200	12.0	6.90	.22	.176	.206	51.3	37.3	31.7
5540	2.5	600	600	6.0	3.84	.10	.075	.104	35.7	46.8	33.3
BACKGROUND	1.8	30	30	0.5	.39	.003	.001				



GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ sho \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 70 ) ( 30 ) ( ) ( ) ( ) ( )

Color air, trap Grain/Xtal Size f-m gr Shape sph-sang Sorting poor Cmt & Mtx sale Acc \_\_\_\_\_

POROSITY: n p m f g X intgran \_\_\_\_\_ inbdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color lt brn \_\_\_\_\_ even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_

FLUORESCENCE: Color yellow \_\_\_\_\_ even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % navi \_\_\_\_\_

CHLOROTHENE CUT: Color gal Development good streaming Residual \_\_\_\_\_

CUT FLUORESCENCE: Color gal Development good Residual \_\_\_\_\_

MUD PROPERTIES: WR 8.4 FV 27 FH 11/C WOB 35 RPM 70 SPM 108 PP 2300

REMARKS: 12,875 units calculated, Grade 1+, br lt brn oil over shaker Bit Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation done of by any of its agents, servants or employees.

Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



SHOW REPORT# 4 Formation GRAND RIVER


Time 9:30 PM

Date 3/26/85

Depth Interval from 6400 to 6200 with X liberated        produced gas

Gross Ft 2 Net Ft 2

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

[illegible]

GAS RATIO EVALUATION: \_\_\_\_\_ at \_\_\_\_\_ gas \_\_\_\_\_ cond \_\_\_\_\_ the \_\_\_\_\_ and \_\_\_\_\_

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_

%: ( 100 ) ( ) ( ) ( ) ( ) ( )

Color wh. glr Grain/Meal Size fine Shape short-oblong Sorting prime sort Cnt & Mix gala Acc           

POROSITY: n p m f g 8 intran inclin moldic trac vuggy other

STAIN: Color blue even I spotted        pinpoint        bleeding % in total cuttings       

FLUORESCENCE: Color yellow even    spotted    pinpoint    % in total cuttings    % mmt   

CHLOROTHENE CUT: Color BROWN Development                      Residue                     

CUT FLUORESCENCE: Color blue Development                      Residual fine

MUD PROPERTIES: WR 2.4 FV 25 FH      %OH 2 CI 20 Jt 2.0 WOB 35 RPM 35 SPM 200 FT 2500

REMARKS: RM-38, RM-908, GK-160, OS-1 (no glow), Grade 4 with 272 calc units.


Reel Type \_\_\_\_\_ Mrs \_\_\_\_\_ Footage \_\_\_\_\_

Analyst cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analyst shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or sub-servants.

SHOW REPORT # 3 Formation GREEN RIVER FM 11 D  
Depth Interval from 6528' to 6532 with 1 liberated \_\_\_\_\_ produced gas  
Gross Ft 4' Net Ft 4'

Time 4:00 am  
Date 3/27/85

**RATIO PLOT:**  $\frac{C_1}{C_2}$   $\frac{C_1}{C_3}$   $\frac{C_1}{C_4}$

[illegible]

GAS RATIO EVALUATION: 3 oil 3 gas      cond.      the      wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 30 ) ( 30 ) ( 20 ) ( ) ( ) ( )

Color white Grain/Meal Size 11-15 Shape short-oblong Sorting moderate Cmt & Mix oats Acc           

POROSITY: n p m f g X intgran \_\_\_\_\_ intdin \_\_\_\_\_ moldic \_\_\_\_\_ trac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color same even spotted pinpoint bleeding % in total cuttings           

FLUORESCENCE: Color yellow even 8 spotted pinpoint % in total cuttings 5 % mmt

CHLOROTHENE CUT: Color yellow Development from green to Residual                     

CUT FLUORESCENCE: Color 291 Development fair Residual           

MUD PROPERTIES: Wt 8.3 PV 25 FI 2/C %OI 2 CI 50 pH 9.8 WOB 25 RPM 25 SPM 100 FT 2300


REMARKS: SN. 407, SN. 9533, SN 225, SN 24, Grade 2 with 9032 scale units SN Type SEC 224F Nrs 56 Footage

Amlex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Amlex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 6 Formation GREEN SLATE Time 2:30 PM  
Date 3/31/85

Depth Interval from 7846 to 7854 with x liberated      produced gas

Gross Ft      Net Ft     

[illegible]

**GAS RATIO EVALUATION:** \_\_\_\_\_ of \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lbs \_\_\_\_\_ wt

LITHOLOGY TYPE: ☒ SS ☐ SH ☐ BLST ☐ LG ☐ DOL ☐ Other ☐ MS. ST. ANATO

46: ( 30 ) ( 30 ) ( 35 ) ( ) ( ) ( 45. 00 )

Color wh, air Grain/Meal Size 3/4-C Shape strange Sorting u Cmt & Mtx sale, sil Acc carb mat.

POROSITY: n p m f g X isopore        inter        nodic        frac        vuggy        other       

STAIN: Color BROWN even spotted pinpoint bleeding % in total cuttings       

FLUORESCENCE: Color BKNS \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint % in total cuttings \_\_\_\_\_ % max: \_\_\_\_\_

CHLOROTHENE CUT: Color 2073 Development \_\_\_\_\_ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color 2022 Development \_\_\_\_\_ Residual \_\_\_\_\_

DDOF:     n   of   ed

WETTABILITY TEST:           +           -

MUD PROPERTIES: W 2.4 PV 27 FH 24 %OS 0 CI 200 pH 11.0 WOB 35 RPM 60 SPM 100 PP 2500

REMARKS: SK 125, IN .49, OS 1, IN .933, GRADE 4 @ 250 gals. units.

**Shot Type** \_\_\_\_\_ **Ans** \_\_\_\_\_ **Footage** \_\_\_\_\_

Amlex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Amlex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.





OPERATOR OUTREX ENERGY CORP  
WELL RESCAP J.B.C. 30 - 4 - 41

SEC 30 TWP 1 S RNG 2 E  
JOB# 84660 KITAM CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 7 Formation GREEN RIVER  
Time 4:00 am  
Date 4/1/85

Depth Interval from 8052 to 8066 with X liberated \_\_\_\_\_ produced gas

Gross Ft 14 Net Ft 8

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

G F P	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
	BACKGROUND	4.2	130	1.3	.66	.021	.025	.01			
	8054	2.0	125	1.25	.66	.021	.025	.01	0	0	0
	8056	1.5	270	2.7	1.62	.051	.048	.0019	32.0	41.7	106.7
	8058	3.0	114	1.4	.39	.005	.025	.01	0	0	0
	8060	4.2	114	1.14	.39	.005	.025	.01	0	0	0
	8062	2.4	366	3.66	1.81	.103	.105	.10	14.0	14.4	12.8
	8064	2.4	366	3.66	1.81	.103	.105	.10	14.0	14.4	12.8
	8066	3.6	200	2.0	1.19	.051	.075	.057	17.7	10.6	11.3
	8068	3.4	132	1.32	.69	.013	.025	.01	0	0	0
	BACKGROUND										



GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lite \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 10 ) ( 70 ) ( 20 ) ( ) ( ) ( ) ( )

Color sh-ely Grain/Xtal Size vf-f Shape sharp-shang Sorting med Cmt & Mtx slt-calc Acc \_\_\_\_\_

POROSITY: n p m f g X Ingran \_\_\_\_\_ Inbsh \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color BORS \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_

FLUORESCENCE: Color BORS \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % rawl \_\_\_\_\_

CHLOROTHENE CUT: Color BORS \_\_\_\_\_ Development \_\_\_\_\_ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color BORS \_\_\_\_\_ Development \_\_\_\_\_ Residual \_\_\_\_\_

MUD PROPERTIES: WR 8.8 PV 37 FI 5/c %OH 5/c CI 280 pH 11.0 WOB 55 RPM 55/60 SPM 128 PP 2300

REMARKS: calc units 391.7 u. Grade 3 Bit Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.





OPERATOR QUINCY ENERGY CORP  
WELL RECAP J.B.C. 30 - 4 - A1

SEC 30 TWP 1 E RNG 2 E  
JOB# 04660 SERIAL CO., STATE UTAH


**analex**  
DIVISION OF XCO

SHOW REPORT# 8 Formation GREEN RIVER  
Depth Interval from 8222' to 8236' with X liberated \_\_\_\_\_ produced gas  
Gross Ft 14 Net Ft \_\_\_\_\_

Time 7:00 am  
Date 4/2/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
		UNITS	% M.E.	C1	C2	C3	E C4	MINUS BACKGROUND		
								$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	2.0	100	1.8	.87	.045	.061	.035			
8222	2.3	290	2.9	1.91	.876	.086	.048	28.6	25.6	29.1
8224	1.3	400	4.0	1.94	.101	.127	.073	19.1	16.2	22.8
8226	1.2	270	2.7	1.34	.066	.08	.048	22.4	12.1	21.4
8228	1.3	275	2.75	1.34	.066	.10	.048	22.4	12.1	21.4
8230	2.2	380	3.8	2.09	.096	.098	.042	23.9	32.9	76.3
8232	1.7	360	3.6	2.09	.096	.098	.042	23.9	32.9	76.3
8234	1.7	340	3.4	1.79	.096	.098	.042	13.0	24.9	97.5
8236	2.7	290	2.9	1.51	.876	.086	.042	28.6	25.6	40.8
BACKGROUND										



GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lto \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 30 ) ( 30 ) ( 20 ) ( ) ( ) ( )

Color wh,slr Grain/Size fine Shape sph-sang Sorting med Cmt & Mtx sil-sls Acc \_\_\_\_\_

POROSITY: n p in f g X Ingran \_\_\_\_\_ Inbdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color SCES \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_

FLUORESCENCE: Color sl yel \_\_\_\_\_ even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mml \_\_\_\_\_

CHLOROTHENE CUT: Color yel Development dry streaming w/ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color yel Development DMF Residual \_\_\_\_\_

MUD PROPERTIES: Wt 8.4 FV 27 PH 8.5 %OH 2 Cl 30 pH 10.5 WOB 35 RPM 65 SPM 100 PP 3000

REMARKS: 855-25 calc units, Grade 3 BR Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



OPERATOR SHINEX ENERGY  
WELL REDCAP JEC 30-4-41

SEC 30 TWP 1 S RNG 2 E  
JOB# 84-660 SUTAN CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 9 Formation GREEN RIVER Time 8:00 PM  
Date 4/3/85

Depth Interval from 8330 to 8700 with 1 liberated \_\_\_\_\_ produced gas

Gross Ft 120 Net Ft 120

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	2.6	86		.86	.38	.821	.831	.849			
8336	1.7	190		1.50	.67	.843	.860	.838	13.6	11.2	17.2
8624	2.2	160		1.60	.81	.849	.852	.839	16.3	13.1	20.8
8634	3.2	116		1.16	.54	.836	.848	.827	13.9	11.2	20.8
8646	3.1	120		1.20	.91	.833	.841	.889	15.4	12.4	17.6
8656	3.2	125		1.25	.99	.836	.820	.821	16.4	11.8	19.0
8668	2.3	145		1.45	.65	.844	.857	.836	14.6	11.4	16.0
8676	2.8	135		1.35	.97	.828	.850	.828	13.0	11.4	20.4
8676	3.4	100		1.00	.43	.838	.837	.824	13.3	11.6	17.9
BACKGROUND	2.4	100		1.00	.43	.828	.837	.824			



GAS RATIO EVALUATION: \_\_\_\_\_ oil \_\_\_\_\_ gas 1 cond. \_\_\_\_\_ the \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 10 ) ( 10 ) ( 80 ) ( ) ( ) ( )

Color brn Grain/Xtal Size mf-fst Shape shrd Sorting st Cmt & Mtx calc, sil Acc \_\_\_\_\_

POROSITY: n p m f g 1 intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color brn-blt 1 even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings 60

FLUORESCENCE: Color dark yelgrn even 1 spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings 20 % mmi 30

CHLOROTHENE CUT: Color brt yel Development slw strng Residual gd yel sng

CUT FLUORESCENCE: Color \_\_\_\_\_ Development \_\_\_\_\_ Residual \_\_\_\_\_

MUD PROPERTIES: WR 8.4 PV 27 FI \_\_\_\_\_ %OH 8 CI 288 pH 11.8 WOB 35 RPM 65 GPM 400 PP 2500

REMARKS: IR 1.2, IR 1.22, GR 74, GS 2.0, GRADE 5, 150 calc units

SH Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.


OPERATOR QUINEX ENERGY CORPWELL NECAP J.B.C. 30-4-1SEC 30 TWP 1 S. RNG 2 E.JOB# 04660 HINTAN CO., UTAH

analex

DIVISION OF NCO

SHOW REPORT# 10 Formation GREEN RIVER Time 10:00 AM  
Date 4/4/85RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$ Depth Interval from 8980' to 9000' with X liberated        produced gasGross Ft 20 Net Ft       


DEPTH	MINFT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	4.0	130	1.3	.64	.05	.066	.038			
8982	3.5	130	1.4	.64	.05	.066	.038	0	0	0
8984	3.3	300	3.0	1.55	.156	.19	.084	8.3	7.1	19.1
8986	3.0	300	3.0	1.55	.156	.19	.084	8.3	7.1	19.1
8988	3.1	430	4.3	1.98	.224	.253	.131	7.5	7.0	14.1
8990	3.6	430	4.5	1.98	.224	.253	.131	7.5	7.0	14.1
8992	3.6	430	4.5	1.98	.224	.253	.131	7.5	7.0	14.1
8994	3.8	400	4.0	1.55	.18	.197	.099	6.77	6.71	14.4
9000	3.8	400	4.0	1.55	.18	.197	.099	6.77	6.71	14.1
BACKGROUND										

GAS RATIO EVALUATION: X oil X gas        cond.        the        wetLITHOLOGY TYPE: SS SH SLTST LS BOL Other       %: ( 60 ) ( 30 ) ( 10 ) (        ) (        ) (        )Color wh, air, lt brn Grain/Coal Size fine Shape sphere-sphere Sorting med Cmt & Mtx calc Acc       POROSITY: n p m f g X in gran        in chn        moldic        frac        vuggy        other       STAIN: Color lt brn X even X spotted        pinpoint        bleeding        % in total cuttings       FLUORESCENCE: Color sl yellow        even X spotted        pinpoint        % in total cuttings 10 % mwt       CHLOROTHENE CUT: Color red Development good streaming Residual       GUT FLUORESCENCE: Color red Development good Residual       MUD PROPERTIES: WR 0.4 PV 27 FI 85 WCM 0 CIBD        pH 11.0 WOB 35 RPM 65 SPM 108 PP 2500REMARKS: 1100.7 calc units, Grade 2 Bit Type        Hrs        Footage       

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

OPERATOR GREEN ENERGYWELL WISHP JIS 20-4-A1SEC 30 TWP 1 S RNG 2 EJOB# 84-660 WYMAN CO., WYMANanalex  
DIVISION OF XCOSHOW REPORT# 11 Formation GREEN RIVERTime 7:00 PM  
Date 4/4/85RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$ Depth Interval from 9118 to 9140 with X liberated \_\_\_\_\_ produced gasGross Ft 22 Net Ft 10

G F P	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
	BACKGROUND	3.7	630	6.30	2.42	.224	.316	.128			
	9118	1.4	820	8.20	3.25	.421	.519	.374	7.7	7.9	18.7
	9120	1.8	580	5.80	3.72	.484	.569	.328	7.7	7.9	16.3
	9124	3.8	700	7.00	2.84	.326	.557	.128	8.7	8.0	22.2
	9130	3.3	1200	12.00	4.81	.610	.628	.336	7.9	7.6	14.3
	9132	3.3	1200	12.00	4.81	.610	.628	.336	7.9	7.6	14.3
	9134	4.1	800	8.00	3.20	.398	.390	.165	8.0	8.2	79.4
	BACKGROUND	3.7	560	5.60	2.36	.263	.332	.112			

GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lte \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_

%: ( 60 ) ( 10 ) ( 30 ) ( ) ( ) ( ) ( )

Color sh. gr Grain/Xtal Size med Shape sub-sph Sorting mod Cmt & Mtx calc Acc \_\_\_\_\_POROSITY: n p m f g X intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_STAIN: Color lt-dr brn X even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_FLUORESCENCE: Color swl yellow \_\_\_\_\_ even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings 20 % surf 20CHLOROTHENE CUT: Color gal Development slow stng Residual lt gal stngCUT FLUORESCENCE: Color gal Development \_\_\_\_\_ Residual \_\_\_\_\_MUD PROPERTIES: WR 2.7 PV 27 FI 2/A %OH 0 CI 600 pH 9.0 WOB 55 RPM 65 SPW 400 PP 2500REMARKS: RE 643, RE 578, RE 2, RE 572B; GRAIN 1 W/ 573A calc. mite Bit Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



OPERATOR OTIS ENERGY CORP  
WELL RESCAP 2, D.C. 30-A-41

SEC 30 TWP 1 S RNG 2 E  
JOB# 04660 USTAN CO., WY

**analex**  
DIVISION OF XCO


SHOW REPORT# 12 Formation WASATCH FTL  
Time 4:00 am  
Date 4/19/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

Depth Interval from 9998' to 9996' with 1 liberated \_\_\_\_\_ produced gas

Gross Ft 10 Net Ft \_\_\_\_\_

DEPTH	MINFT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	6.7	280	2.8	.78	.09	.088	.096			
9996	3.0	320	3.2	1.10	.11	.11	.049	16.0	14.5	0
9998	1.4	380	3.8	1.44	.12	.12	.071	22.0	20.6	44.0
9980	2.0	390	3.9	1.44	.12	.13	.071	22.0	20.6	44.0
9902	3.2	380	3.8	1.44	.12	.12	.071	22.0	20.6	44.0
9904	3.7	320	3.2	1.10	.11	.11	.071	16.0	14.5	44.0
9906	4.0	380	3.8	1.44	.12	.12	.071	22.0	20.6	44.0
9908	5.0	380	3.8	1.44	.12	.12	.071	22.0	20.6	44.0
9910-11	2.0	380	3.8	1.44	.12	.12	.071	22.0	20.6	44.0
BACKGROUND										



GAS RATIO EVALUATION: 1 oil 1 gas \_\_\_\_\_ cond. \_\_\_\_\_ the 1 wet

LITHOLOGY TYPE: SS SH SLTST LS BOL Other \_\_\_\_\_  
%: ( 78 ) ( 30 ) ( ) ( ) ( ) ( )

Color slate Grain/Obj Size fine Shape spherical Sorting med Cnt & Mtx. anisomous Acc \_\_\_\_\_

POROSITY: n p m f g 1 intgrn \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color dk brn \_\_\_\_\_ even 1 spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings 90

FLUORESCENCE: Color brn \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mwi \_\_\_\_\_

CHLOROTHIENE CUT: Color br yel Development good streaming Residual \_\_\_\_\_

CUT FLUORESCENCE: Color yel Development good Residual \_\_\_\_\_

MUD PROPERTIES: WR 2.8 PV 27 FI 25 %OH 95 CI 200 pH 12.0 WOB 50 RPM 90 SPM 100 PP 2500

REMARKS: GRADE 3, TYPE 845 units, Run time was after show # 12 1500 units, no more gas before show # 12 1552 Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.


ODOR: n s l g

WETTABILITY TEST: + -

SHOW REPORT# 15 Formation MARATHI Fm D  
Depth Interval from 10072' to 10079' with X liberated \_\_\_\_\_ produced gas  
Gross Ft 6 Net Ft \_\_\_\_\_

Time 6:00 am  
Date 4/11/85

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

[illegible]

GAS RATIO EVALUATION: 8 oil 8 gas        cond.        the        wet

LITHOLOGY TYPE: SS SH SLTST LS BOL Other \_\_\_\_\_  
%: ( 30 ) ( 35 ) ( ) ( ) ( ) ( )

Color pink Grain/Meal Size 2-4 Shape bird-shaped Sorting pear Cmt & Mix only Acc           

POROSITY: n p m f g X intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color dk. brown even 3 spotted pinpoint bleeding % in total cuttings 90

FLUORESCENCE: Color all salmon even X spotted pinpoint % in total cuttings 90 % marl           

CHLOROTHENE CUT: Color br. and Development good screening Residual           

CUT FLUORESCENCE: Color yes Development good Residual           

MUD PROPERTIES: Wt \_\_\_\_\_ FV \_\_\_\_\_ FI \_\_\_\_\_ WOB \_\_\_\_\_ CI \_\_\_\_\_ pH \_\_\_\_\_ WOB 50/50 \_\_\_\_\_ RPM 30 \_\_\_\_\_ SPM 100 \_\_\_\_\_ FT 1000 \_\_\_\_\_

REMARKS: 247.3 sale units. Grade 4. v oil increase is oil over shaker. Mfr Type: Mfr: Footage:

Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.





OPERATOR GENEX ENERGY CORP  
WELL RECAP J.B.C. 3-4-A1

SEC 30 TWP 1 E RNG 2 E  
JOB# 04660 BLTAN CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 14 Formation WASATCH FM. Time 12:30 pm  
Date 4/25/85

Depth Interval from 11062' to 11072' with X liberated \_\_\_\_\_ produced gas

Gross Ft 10 Net Ft 0

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	7.0	13	.13	.039	.005	0	0			
11062	4.0	163	1.63	.146	.007	0	0	53.5	0	0
11064	4.5	12	.12	.012	0	0	0	0	0	0
11066	2.5	12	.12	.012	0	0	0	0	0	0
11068	2.0	15	.15	.018	0	0	0	0	0	0
11070	2.0	205	2.05	1.07	.038	.005	0	31.2	206.2	0
11072	3.5	85	.85	.66	.015	0	0	62.4	0	0
BACKGROUND										



GAS RATIO EVALUATION: \_\_\_\_\_ oil X gas \_\_\_\_\_ cond. X the \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 10 ) ( 90 ) ( ) ( ) ( ) ( ) ( )

Color white Grain/Grain Size 1/4-1/2 Shape spherical Sorting good Cmt & Mtx calc Acc \_\_\_\_\_

POROSITY: n 5 m 1 g X intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color same \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_

FLUORESCENCE: Color same \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mvt \_\_\_\_\_

CHLOROTHENE CUT: Color same Development \_\_\_\_\_ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color same Development \_\_\_\_\_ Residual \_\_\_\_\_

MUD PROPERTIES: WR 30 PV 32 FI 32 WOI 0 CI 600 pH 8.1 WOB 30 RPM 210 SPM 55 PP 3000

REMARKS: No gas, clear, color, or odor. Grade 4, 464 mile units Bit Type CIRIS B 321 Hrs 5 Footage \_\_\_\_\_


Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 15 Formation MSATCH FRI.Time \_\_\_\_\_  
Date \_\_\_\_\_

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 11420' to 11476' with X liberated \_\_\_\_\_ produced gas

Gross Ft 6 Net Ft 4

[illegible]

GAS RATIO EVALUATION: \_\_\_\_\_ oil X gas \_\_\_\_\_ cond. \_\_\_\_\_ lbs X wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_

●: ( ) ( ) ( ) ( ) ( ) ( )

Color slr. wh Grain/xtal Size xf-m Shape shrd-stang Sorting poor Cmt & Mtx calc-sil Acc

POROSITY: ☐ a ☐ p ☐ m ☐ f ☐ g ☒  $\Sigma$  ☐ intgran ☐ intbin ☐ moldic ☐ frac ☐ vuggy ☐ other \_\_\_\_\_

STAIN: Color Brown even spotted pinpoint bleeding % in total cuttings           

FLUORESCENCE: Color None even spotted pinpoint % in total cuttings        % mmi       

CHLOROTHENE CUT. Color red Development near stressing Residual           

CUT FLUORESCENCE: Color red Development poor Residual           

MUD PROPERTIES: WR 20 FV 43 FE 11.2 %OH 0 CI 400 FS 11.0 WOB 18/22 RPM 110 SPM 53 FT 1900

REMARKS: no chain, flr, or edr, @1.3 sale units, minor grade      SK Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



SHOW REPORT# 16 Formation WASATCH


Time 9:00 PM  
Date 5/1/85

RATIO PLOT:  $\frac{C_1}{C_2}$        $\frac{C_1}{C_2}$        $\frac{C_1}{C_2}$

Depth interval from 1194 to 1196 with 1 liberated        produced gas

Gross Ft 42 Net Ft 10

G	F	P	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
					UNITS	% N.E.	C1	C2	C3	Σ C4	MINUS BACKGROUND		
			BACKGROUND								$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
			13.2	19	.19	.020	.0	.0	.0				
			13816	4.4	.22	.023	.0	.0	.0	0	0	0	
			13818	5.0	.24	.025	.0	.0	.0	0	0	0	
			13820	13.2	.27	.044	.0	.0	.0	0	0	0	
			13824	9.7	.43	.07	.02	.005	.0	2.5	34	0	
			13840	8.0	.50	.22	.029	.007	.0	7.5	31	0	
			13856	12.5	.60	.23	.031	.012	0	7.4	19	0	
			BACKGROUND	13.4	.20	.055	.011						



**GAS RATIO EVALUATION:** \_\_\_\_\_ oil \_\_\_\_\_ gas \_\_\_\_\_ cond. X lbs \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 100 ) ( ) ( ) ( ) ( ) ( )

Color wh. air Grain/Meal Size wt-f Shape slang-srd Sorting frs Cnt & Mtx ely Acc carb.

POROSITY: n p m f g X intgran \_\_\_\_\_ intaln \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color none even    spotted    pinpoint    bleeding    % in total cuttings   

FLUORESCENCE: Color None even spotted pinpoint % in total cuttings        % mmi       

CHLOROTHENE CUT: Color none Development                      Residual                     

CUT FLUORESCENCE: Color none Development                      Residual                     

MUD PROPERTIES: W 24 PV 35 FM 10 %OB 0 CL 350 SH 10 WOB 12/20 RPM 100/110 RPM 36 FT 1700

REMARKS: WINDOR SENSORS 38, 39, 40, 43 calculated units respectively with no oil in samples or over on Type REC NS 40 Mts Footage 124'

**Abstract**

Amstar cannot and does not guarantee the accuracy or completeness of this data and information. Amstar shall not be held liable or responsible for any losses, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

ODOR: n n po

**WETTABILITY TEST:** + -





OPERATOR QUINEX ENERGY  
WELL REDCAP JEC 30-4-A1

SEC 30 TWP 1 S 5 RNG 2 E  
JOB# 84-660 UPTAH CO., UTAH

**analex**  
DIVISION OF XCO

SHOW REPORT# 18 Formation WASATCH


Time 3:00 PM  
Date 5/2/85

Depth Interval from 11936 to 11958 with x liberated \_\_\_\_\_ produced gas

Gross Ft 22 Net Ft 10

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

G F P	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
			UNITS	% M.E.	C1	C2	C3	Σ C4	MINUS BACKGROUND		
									$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
	BACKGROUND	12.5	41	.41	.068	.003	0	0			
	11936	9.3	176	1.76	.238	.103	.039	.008	7.16	18.9	92.2
	11942	8.9	1385	13.85	2.76	.50	.24	.011	5.52	41.5	26.9
	11944	11.5	384	1.84	.72	.11	.052	.013	6.54	13.8	55.4
	11946	13.0	140	1.40	.62	.10	.047	.013	6.20	14.2	51.5
	11958	8.5	340	3.40	1.30	.21	.10	.041	6.19	15.0	31.7
	BACKGROUND	10.5	85	.85	.30	.04	.018	0			



GAS RATIO EVALUATION: ☒ oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ silo \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: (10-20) (90-80) ( ) ( ) ( ) ( ) ( )

Color sh, sil Grain/Size fine Shape subang-ed Sorting med Cmt & Mtx sil-sale Acc carb

POROSITY: n p m f g x Intgran \_\_\_\_\_ Intbin \_\_\_\_\_ moldic \_\_\_\_\_ x frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color lt brn \_\_\_\_\_ even x spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings 5

FLUORESCENCE: Color none \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mmi \_\_\_\_\_

CHLOROTHEME CUT: Color none Development \_\_\_\_\_ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color none Development \_\_\_\_\_ Residual \_\_\_\_\_

MUD PROPERTIES: WR 30.1 PV 46 FH 11 %OH 0 Cl 100 pH 10 WOB 10/20 RPM 110 SPM 36 PP 4700

REMARKS: GRADE 1+ W/2990 CALC. UNITS, FR-G OIL OVER SHAKER

Bit Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.


SHOW REPORT# 19 Formation WASATCH

Time 2:00 AM  
Date 5/3/85

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 11974 to 11986 with        liberated x produced gas

Gross Ft 12 Net Ft 8

[illegible]

**GAS RATIO EVALUATION:**   X   oil        gas        cond.        lbs        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: (10-20) (90-80) ( ) ( ) ( ) ( )

Color sh. gr Grain/Coal Size 1-4 Shape ang-shang Sorting mod v Cnt & Mtx sil Acc sl 65%

POROSITY: n p m f g x intgran \_\_\_\_\_ intxin \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color light brown even X spotted        pinpoint        bleeding        % in total cuticles       

FLUORESCENCE: Color none even spotted pinpoint % in total cuttings        % moist       

CHLOROTRINE CUT. Color none Development                      Residual                     

**CUT FLUORESCENCE:** Color None Development                      Residual                     

ODOR: n o d

**WETTABILITY TEST:**      +      -

MUD PROPERTIES: SR 30-1 PV 46 FH 11 WOB 0 CI 100 BS 30 WOB 25/20 RPM 110 SPM 5% TP 2700

REMARKS: GRADE 1-- 15/17/87 CALC UNITS, MED OIL OVER SHAKER

Reel Type \_\_\_\_\_ Mms \_\_\_\_\_ Footage \_\_\_\_\_

Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.


OPERATOR QUINEX ENERGYWELL BRICAP JEC 30-A-A1SEC 30 TWP 1 S 6 RNG 2 EJOB# BA-660 HUNTAN CO., UTAH

analex

DIVISION OF XCO

SHOW REPORT# 20 Formation MASACHTime 7:00 AMDate 5/3/85RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$ Depth Interval from 12018 to 12024 with 3 liberated \_\_\_\_\_ produced gasGross Ft 6 Net Ft 6

	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND		9.0	450	1.6	.30	.051	.039	.08			
12018		8.0	460	1.6	.30	.051	.039	0	5.88	7.69	0
12020		4.5	3660	16.6	6.29	1.19	.62	.39	5.26	10.31	28.52
12022		5.4	230	2.3	.38	.062	.050	0	8.33	7.60	0
12024		30.4	430	1.5	.26	.043	.021	0	6.05	12.4	0
BACKGROUND											

GAS RATIO EVALUATION: ☒ oil ☒ gas \_\_\_\_\_ cond. \_\_\_\_\_ tile \_\_\_\_\_ wetLITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
% ( 20 ) ( 80 ) ( ) ( ) ( ) ( )Color wh. sil Grain/Clst Size vi-f Shape sphg Sorting mod v Cmt & Mtx arg. sil Acc silPOROSITY: n p m f g ☒ Intgran \_\_\_\_\_ inbdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_STAIN: Color wh. sil \_\_\_\_\_ even ☒ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings \_\_\_\_\_FLUORESCENCE: Color wh. sil \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mwt \_\_\_\_\_CHLOROTHENE CUT: Color wh. sil Development \_\_\_\_\_ Residual \_\_\_\_\_CUT FLUORESCENCE: Color wh. sil Development \_\_\_\_\_ Residual \_\_\_\_\_MUD PROPERTIES: WR 30.1 PV AA FI 30 %OH 0 CI 400 pH 11 WOB 10/22 RPM 110 SPM 54 PP 1200REMARKS: GRADE 1+ w/ TOROS CALC UNITS and TR OIL INCREASE IN MUD

SH Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analx shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation furnished by any of its agents, servants or employees.

WETTABILITY TEST: + -

**OPERATOR**      **QUINEX ENERGY CORP**

**WELL** RECAP J.D.C. 32-4-A1

SEC 30 TWP 1 S. RNG 2 E.

**JOB#** BA660 **UNIT** UNITAN **CO.** STAN

**analex**

#### DIVISION OF XCO

SHOW REPORT# 22 Formation WRSATCH FEN.


Time 6:00 pm

Date 3/3/85

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 12078 to 12084 with x liberated \_\_\_\_\_ produced gas

Gross Ft 6 Net Ft         

[illegible]

**GAS RATIO EVALUATION:** \_\_\_\_\_ y oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ the \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other CALC FRAC  
%: ( 10 ) ( 80 ) ( ) ( 10 ) ( ) ( )

Color wh Grain/Meal Size fine rln Shape \_\_\_\_\_ Sorting \_\_\_\_\_ Cnt & Mtx \_\_\_\_\_ Acc \_\_\_\_\_

POROSITY: n p m f g \_\_\_\_\_ Intergran \_\_\_\_\_ Interst \_\_\_\_\_ moldic X frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color pink even X spotted    pinpoint    bleeding % in total cuttings   

FLUORESCENCE: Color none even spotted pinpoint % in total cuttings        % resin       

CHLOROTHENE CUT. Color same Development                      Residual                     

CUT FLUORESCENCE: Color None Development                      Residual                     

MUD PROPERTIES: Wt \_\_\_\_\_ FV \_\_\_\_\_ FH \_\_\_\_\_ %OH \_\_\_\_\_ G \_\_\_\_\_ S \_\_\_\_\_ WOB \_\_\_\_\_ FI \_\_\_\_\_ FIW \_\_\_\_\_ Y \_\_\_\_\_

REMARKS:	Oil sta free & free sale. AEO2 sale units. GRADE 1.	SW Type	Mts	Footage
----------	---	---------	-----	---------

Analyst contact and does not guarantee the accuracy or correctness of this data and interpretation. Analyst shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

ODOR: n si od

WETTABILITY TEST: + -




OPERATOR ONIX ENERGY CORPWELL RECAP J.B.C. 30-A-41SEC 30 TWP 1 S. RNG 22 E.JOB# 84660 HINTAH CO., UTAH

analex

DIVISION OF XCO

SHOW REPORT# 25 Formation WASATCH FM.Time 10:30 pmDate 5/3/85RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$ Depth Interval from 12108' to 12126' with x liberated x produced gasGross Ft        Net Ft       

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	9.6	170	1.7	.53	.065	.026	0			
12108	6.8	2800	26.0	6.62	1.08	.628	.381	6.0	10.12	15.98
12110	5.5	3500	35.0	12.58	3.78	2.41	.50	3.79	5.05	24.1
12112-116	3.5	2500	25.0	5.8	.98	.60	.381	6.27	9.99	15.05
12118	4.5	3400	34.0	14.57	3.24	1.88	.50	4.42	7.57	28.08
12120	3.9	2730	27.3	5.56	1.62	1.26	.50	3.23	4.08	10.86
12122	5.1	3400	34.0	13.51	2.70	1.47	.50	4.92	8.99	25.96
12124	4.8	1090	10.1	3.97	.54	.314	.24	7.24	11.94	14.33
BACKGROUND										

GAS RATIO EVALUATION: x oil x gas        cond.        lite        wetLITHOLOGY TYPE: SS SH SLTST LS DOL Other WILSONITE  
%: ( 20 ) ( 60 ) ( ) ( 10 ) ( ) ( 10 )Color slt. sh Grain/Size fine Shape abraded Sorting med Cmt & Mtx calc sil Asc       POROSITY: n p gr i g x Intgran inbdn moldic frac vuggy otherSTAIN: Color none even spotted pinpoint bleeding % in total cuttings       FLUORESCENCE: Color none even spotted pinpoint % in total cuttings        % mwt       CHLOROTHIENE CUT: Color none Development        Residual       CUT FLUORESCENCE: Color none Development        Residual       MUD PROPERTIES: Wt 10.1 FV        FI        %OH        Cl        ph        WOB        RPM        SPM        PP       REMARKS: AMT BLK OIL OVER SHAKER. SA. 380 calc units. GRADE 1... Bit Type        Hrs        Footage       

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



Andur, cannot and does not guarantee the accuracy or correctness of this data and interpretation. Andur shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customers resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

### WEARABILITY TEST



OPERATOR QUINCY ENERGY CORP  
WELL BRICAP J.B.C. 30-4-A1

SEC 30 TWP 4S RNG 3E  
JOB# 84660 HUNTAH CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 26 Formation WASATCH FM.  
Depth Interval from 12278' to 12300' with x liberated x produced gas  
Gross Ft 22 Net Ft       

Time 11:00am-2:00pm  
Date 5/15/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

SHOW EVALUATION

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND			
		UNITS	% M.E.	C1	C2	C3	Σ C4	C1 C2	C1 C3	C1 C4	
BACKGROUND	8.5	120	1.2	.26	.021	.01	0				
12276	9.4	340	3.4	1.17	.19	.075	.032	5.38	14.0	26.4	
12278	10.4	890	8.9	3.37	.62	.296	.071	5.19	10.87	43.8	
12280	11.7	1600	16.0	6.3	1.23	.61	.097	5.00	10.07	68.93	
12282	10.6	1700	17.0	6.65	1.33	.70	.353	4.88	9.26	18.10	
12284	9.2	220	23.3	9.16	1.85	.98	.004	4.79	9.37	22.03	
12286	12.1	1880	18.8	8.37	1.66	.87	.361	4.95	9.43	22.47	
12288	12.1	3600	36.0	12.98	2.62	1.36	.543	4.89	9.42	23.43	
12290	10.2	3800	38.0	14.49	2.87	1.48	.543	4.99	9.68	26.21	
12292	8.4	3800	38.0	14.49	2.87	1.48	.543	4.99	9.68	26.21	
12294	11.0	3450	34.5	15.32	3.08	1.6	.543	4.92	9.47	27.73	
12296	11.8	4800	48.0	23.54	4.44	2.47	.957	4.82	8.65	22.23	
BACKGROUND											



GAS RATIO EVALUATION: x oil x gas        cond.        the        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other         
% ( 20 ) ( 60 ) ( 10 ) ( 10 ) ( ) ( )

Color wh. blk Grain/Size mf-f Shape shd-shang Sorting med Cmt & Mtr calc Acc       

POROSITY: n p m i g x Intgran        Intbdn        moldic        frac        vuggy        other       

STAIN: Color dk brn-blk        even x spotted        pinpoint        bleeding        % in total cuttings 2r

FLUORESCENCE: Color none        even        spotted        pinpoint        % in total cuttings        % mtr       

CHLOROTHENE CUT: Color none Development        Residual       

CUT FLUORESCENCE: Color none Development        Residual       

MUD PROPERTIES: Wt 34.4 PV        FI        %ON        CI        pH        WOB        RPM        BPM        PP       

REMARKS: slmt dk brn-blk oil over shaker, 12,834 units calc, GRADE 1-- BR Type        Hrs        Footage       

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.


SHOW REPORT# 27 Formation WASATCH

Time 4:00 AM  
Date 5/5/95

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 12546 to 12558 with x liberated        produced gas

Gross Ft 12 Net Ft 6

[illegible]

**GAS RATIO EVALUATION:** 1 oil        gas        cond. 1 the        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_

%: ( 30 ) ( 60 ) ( 30 ) ( 0 ) ( ) ( )

Color sh. o/p Grain/xtal Size sf-r Shape shaded Sorting med Cmt & Mtx sil-calc Acc carb

POROSITY: n p m f g x integran \_\_\_\_\_ inxch \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color BROWN even spotted pinpoint bleeding % in total cuttings       

FLUORESCENCE: Color same even spotted pinpoint % in total cuttings        % mnt       

CHLOROTHENE CUT: Color BONE Development                      Residual                     

CUT FLUORESCENCE: Color BROWN Development \_\_\_\_\_ Residual \_\_\_\_\_

**ODOR:** nsl

WETTABILITY TEST:           +           -

MUD PROPERTIES: SR 12-0 PV 36 FI 2-2 WOB 1 CI 300 SR 12 WOB 28/20 RPM 110 RPM 56 FT 2003

REMARKS: SR107 1, no issue in oil. SR Type Hrs Footage

Amlex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Amlex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof or by any of its agents, servants or employees.



**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Kit Type \_\_\_\_\_ Mfr \_\_\_\_\_ Footage \_\_\_\_\_


Analix correct and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 29 Formation WASATCH PBL. Time 4:00 pm  
Date 5/7/85

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 12610' to 12630' with x liberated \_\_\_\_\_ produced gas

Gross Ft 12 Net Ft           

[illegible]

GAS RATIO EVALUATION: 1 oil 1 gas        cond.        titr        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other ~~GELSPHINTS~~

%: ( 10/ ) ( 80 ) ( ) ( ) ( ) ( )

Color wh,clr,SLP Grain/Meal Size 1-2 gr Shape shrd-shang Sorting mod Cnt & Mtx calc Acc

POROSITY: n p m f g x intgran        intdn        moldic        frac        vuggy        other       

STAIN: Color None even spotted pinpoint bleeding % in total cuticles       

FLUORESCENCE: Color same even spotted pinpoint % in total cuttings        % reml       

CHLOROTHRENE CUT: Color None Development                      Residual                     

**CUT FLUORESCENCE:** Color None Development                      Residual                     

MUD PROPERTIES: Wt 22.5 FV 1.1 FI 20.1 SLOI 4 Cl 200 pH 10.0 WOB 20 RPM 120 SPM 53 FP 2000

REMARKS:	tr blk oil over shaker. 347.2 calc units. GRADE 2	SR Type	Nr	Footage
----------	---	---------	----	---------

Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any losses, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, carriers or employees.

**ODOR:**     a     si     od

WETTABILITY TEST + -



OPERATOR QUINEX ENERGY  
WELL WESCAP / JC 30-4-A1

SEC 30 TWP 1 S 5 RNG 2 E  
JOB# BA-660 NITAM CO., NEAR

**analex**  
DIVISION OF XCO


SHOW REPORT# 30 Formation MASACH Time 5:30 AM  
Date 5/8/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

Depth Interval from 12,704 to 12,750 with        liberated x produced gas

Gross Ft 46 Net Ft 22

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	11.2	120	1.20	.350	.066	.031	0			
12704	13.2	1750	17.50	3.000	1.430	.980	.385	4.03	6.24	15.1
12706	13.4	900	9.00	3.030	.680	.369	.148	4.45	8.42	20.5
12708	11.6	300	5.00	1.330	.320	.120	.040	4.16	11.08	35.2
12712	10.8	850	8.50	2.750	.610	.300	.131	4.51	9.17	21.0
12714	11.2	400	4.00	1.090	.230	.130	.070	4.74	8.38	15.6
12716	9.3	420	4.20	1.100	.250	.140	.070	4.40	7.86	15.7
12718	9.7	420	4.20	1.100	.250	.140	.070	4.40	7.86	15.7
12720	13.8	430	4.80	1.200	.270	.150	.070	4.44	8.00	17.1
12736	10.1	400	4.00	1.090	.230	.130	.070	4.74	8.38	15.5
12748	5.4	450	4.50	1.280	.290	.140	.070	4.81	9.14	18.3
BACKGROUND	11.1	350	3.50	.960	.220	.120	.040			



GAS RATIO EVALUATION: x oil        gas        cond.        the        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other WLSL, SILS  
%: ( 82 ) ( 40 ) ( 82 ) ( 40 ) (        ) ( 82, 20 )

LS- Color dark brn Grain/Xtal Size avg fss Shape        Sorting        Cmt & Mtx micritic-shl Acc OSTR

POROSITY: n p m i g        intran x inbdn        moldic x frac        vuggy        other       

STAIN: Color dk brn        even x spotted        pinpoint        bleeding % in total cuttings 40

FLUORESCENCE: Color brn        even x spotted        pinpoint % in total cuttings 5 % mwt 400

CHLOROTHENE CUT: Color brn        Development x slow fast Residual g brn        sh       

CUT FLUORESCENCE: Color        Development        Residual       

MUD PROPERTIES: W 12.5 FV 42 PH 10.5 %OH 1 Cl 380 ph 12 WOB 30/22 RPM 110 SPM 53 PP 3000

REMARKS: GRADE 2 W/ 4514 o/s units. Incr in a brn oil over shaker. All continued bleeding till BN type        Nrs        Footage       

next show.

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



**WETTABILITY TEST:** + -





OPERATOR QUINCY ENERGY  
WELL REDCAP JEC 30-4-41

SEC 30 TWP 1 S 8 RNG 2 E  
JOB# BA-660 HINTAH CO., UTAH

**analex**  
DIVISION OF XCO

SHOW REPORT# 32 Formation MESAZON


Time 7:00 AM  
Date 5/9/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

Depth Interval from 12836 to 12870 with liberated X produced gas

Gross Ft 34 Net Ft 14

DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
		UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	10.2	420	4.20	4.17	.28	.14	.021			
12840	7.1	1800	18.00	18.73	13.78	33.88	6.36	3.22	3.83	6.94
12842	6.2	8100	81.00	20.00	6.65	5.40	3.05	3.01	3.70	6.35
12844	9.5	8150	81.50	19.30	3.78	4.32	2.08	3.34	4.47	9.28
12854	9.6	3800	38.00	5.38	1.67	1.40	.42	3.47	4.34	13.78
12856	9.3	3100	31.00	5.79	1.67	1.40	.42	3.47	4.14	13.78
12862	9.8	3200	32.00	4.36	1.62	1.73	1.85	2.69	3.54	3.54
12868	9.5	4600	46.00	6.35	2.51	2.50	1.63	2.54	2.56	3.90
BACKGROUND	10.8	4100	41.00	5.28	2.09	2.09	1.57			



GAS RATIO EVALUATION: X oil gas cond. tit wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other MRSLT  
%: ( 20 ) ( 30 ) ( 0 ) ( 30 ) ( ) ( 30 )

Color wh. gr Grain/Xtal Size fine Shape shag Sorting poor Cmt & Mtx calc Acc carb

POROSITY: n p m f g X intgran intdn weldic X frac wuggy other

STAIN: Color lt brn X even spotted pinpoint bleeding % in total cuttings 15

FLUORESCENCE: Color wh. yel. grn even X spotted pinpoint % in total cuttings 10 % mmtl ---

CHLOROTHEME CUT: Color same Development --- Residual ---

CUT FLUORESCENCE: Color brn wh. blk Development u. blk Residual wh. yel. ring

MUD PROPERTIES: WR 12.5 PV 40 FI 30.2 %OH 1 CI 525 pH 12 WOB 20/22 RPM 410 SPM 53 PP 2000

REMARKS: SHAPE 10000, 303, 885 units with g. oil over shaker and 90° gas flame Bkt Type --- Hrs --- Footage ---

NOTES: 12854 began to run through gas buster

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

WETTABILITY TEST: + -



OPERATOR QUINEX ENERGY CORP  
WELL REDCAP J.B.C 30-4- A1

SEC 30 TWP 18 RNG 2E  
JOB# 84660 MUFAN CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 22 Formation WASATCH FM.  
Time 1:00 am  
Date 5/18/85

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

Depth Interval from 12916' to 12930' with ☒ liberated ☒ produced gas

Gross Ft 14 Net Ft       

G F P	DEPTH	MMFT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
	BACKGROUND	13.3	5500	55.0	4.20	2.15	2.60	1.92			
	12916	12.5	8000	80.0	16.21	4.86	3.78	2.05	4.43	3.78	199.2
	12918	12.3	8500	85.0	16.55	5.28	4.19	2.60	3.95	7.77	18.16
	12920	13.3	8600	86.0	17.24	5.56	4.32	2.635	4.15	7.58	18.84
	12922	9.7	8600	86.0	17.24	5.56	4.32	2.64	4.15	7.58	18.24
	12924	12.8	8500	85.0	16.55	5.28	4.19	2.60	3.95	7.77	18.16
	12926	12.4	8400	84.0	17.93	5.83	4.50	2.60	3.73	7.22	20.19
	12928	12.8	8400	84.0	17.93	5.83	4.50	2.60	3.73	7.22	20.19
	BACKGROUND										



GAS RATIO EVALUATION: ☒ oil ☒ gas ☐ cond. ☒ no ☐ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other GILSONITE  
% ( 30 ) ( 60 ) ( ) ( 10 ) ( ) ( 10 )

Color wh, air, SLP Grain/Coal Size 3-6 Shape striat-stria Sorting med Cmt & Mtx calc Acc       

POROSITY: n p m f g ☒ Intgran ☐ Inbkn ☐ moldic ☐ frac ☐ vuggy ☐ other       

STAIN: Color lt brn ☐ even ☒ spotted ☐ pinpoint ☐ bleeding % in total cuttings 0-10%

FLUORESCENCE: Color dl yel ☐ even ☒ spotted ☐ pinpoint % in total cuttings 0 % mvt       

CHLOROTHENE CUT: Color yel Development good streaming Residual       

CUT FLUORESCENCE: Color yel Development good Residual       

MUD PROPERTIES: WR 12.6 PV 47 FH 30 %OH br CI 525 pH 11.5 WOB 30/22 RPM 110 SPW 53 PP 2000

REMARKS: shot blk oil over shaker, 18,876 calc units, GRADE 1--

Sh Type        Hrs        Footage       


Amstar cannot and does not guarantee the accuracy or correctness of this data and interpretation. Amstar shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 25 Formation MUSKIE PNL Time 6:00 am  
Date 5/10/85

RATIO PLOT:  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 12948' to 12953' with X liberated X produced gas

Gross Ft 10 Net Ft           

[illegible]

GAS RATIO EVALUATION: 1 oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lbs \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( 10 ) ( 70 ) ( ) ( 20 ) ( ) ( )

Color \_\_\_\_\_ Grain/Meal Size \_\_\_\_\_ Shape \_\_\_\_\_ Sorting \_\_\_\_\_ Cnt & Mtx \_\_\_\_\_ Acc \_\_\_\_\_

POROSITY: n p m f g \_\_\_\_\_ isgran \_\_\_\_\_ isdn \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color pink even spotted pinpoint bleeding % in total cuttings           

FLUORESCENCE: Color None even spotted pinpoint % in total cuttings        % moist       

CHLOROTHENE CUT: Color same Development                      Residual                     

**CUT FLUORESCENCE:** Color       2400       Development                      Residual                     

**ODOR:** n sl gas

**WETTABILITY TEST:** + -

MUD PROPERTIES: Wt 12.6 P<sub>v</sub> 47 P<sub>n</sub> 90 %OH 88 Cl 385 pH 11.5 WOB 20/22 RPM 110 RPM 51 L 2000

REMARKS: Shot gas oil over shaker (three gas burner), 20' flare, 122,500 calc units, GRADE 1---      BN Type \_\_\_\_\_      Hrs \_\_\_\_\_      Feet/Sec \_\_\_\_\_

Ausdex cannot and does not guarantee the accuracy or completeness of this data and interpretation. Ausdex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SEC 30 TWP 1 S 5 RNG 2 E  
JOB# BA-660 STAN CO., STAN

**analex**  
DIVISION OF XCO

SHOW REPORT# 96 Formation WASATCH Time 2:00 AM  
Date 5/11/85

Depth Interval from 13000 to 13004 with x liberated \_\_\_\_\_ produced gas

Gross Ft 4 Net Ft 2

	DEPTH	MINIFT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	C1 C2	C1 C3	C1 C4
G F P	BACKGROUND	10	2000	20.00	.375	.286	.77	.67			
	13000	9.8	2200	22.00	1.10	.700	1.18	1.25	1.57	.93	.88
	13082	2.2	3900	39.00	2.36	1.190	1.70	1.64	1.98	1.39	1.44
	13004	6.7	2000	20.00	.375	.286	.77	.67	1.31	.49	.56
	BACKGROUND	10.0	2000	20.00	.375	.386	.77	.67			

GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. \_\_\_\_\_ lbs. X wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other NEUST  
%: ( ) ( 20 ) ( ) ( ) ( ) ( 10 )

Color tan, lt brown Grain/Meal Size Chilly-Crumb Shape \_\_\_\_\_ Sorting \_\_\_\_\_ Cmt & Mtx \_\_\_\_\_ Acc \_\_\_\_\_

POROSITY: n p m f g \_\_\_\_\_ integran X intrin \_\_\_\_\_ motile \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color BROWN even spotted pinpoint bleeding % in total cuttings           

FLUORESCENCE: Color same even spotted pinpoint % in total cuttings        % max       

CHLOROTHENE CUT: Color 2070 Development                      Residual                     


**CUT FLUORESCENCE:** Color                         Development             Fixative       

MUD PROPERTIES: WR 13.1 PV 26 FI 30.0 %OB 2 CI 525 SH 10.1 WOB 22/24 RPM 120 SPM 51 TP 2100

REMARKS: SPARE 1, 19564 calc units, sl liner in oil over shaker

Sh Type \_\_\_\_\_ Nos \_\_\_\_\_ Footage \_\_\_\_\_

gas dropped off immediately, flare inar from 0' to 2', died back to 0' in 15 min.



Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any losses, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof or by any of its agents, servants or employees.

SHOW REPORT# 37 Formation WESLEY Time 4:00 AM  
Date 5/11/85

Depth Interval from 13025 to 13030 with        liberated x produced gas

Gross Ft 2 Net Ft 2

G F P	DEPTH	MINIFT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
			UNITS	% M.E.	C1	C2	C3	Σ C4	MINUS BACKGROUND		
	BACKGROUND								C1 C2	C1 C3	C1 C4
		12.2	4200	42.00	5.77	2.02	2.17	1.74			
	13028	13.2	8200	82.00	26.6	7.92	4.04	2.01	5.36	5.50	13.2
	13030	12.5	8000	80.00	24.4	6.54	4.42	1.85	3.73	5.52	13.2
	BACKGROUND	14.1	6500	65.00	7.03	4.00	3.33	1.88			

**GAS RATIO EVALUATION:** 2 oil        gas        cond.        H<sub>2</sub>O        vent

LITHOLOGY TYPE: SS SH SLTST LS DOL Other \_\_\_\_\_  
%: ( ) ( 70 ) ( ) ( 30 ) ( ) ( )

Color brn. w/ green Grain/Meal Size slimy-crypsis Shape \_\_\_\_\_ Sorting \_\_\_\_\_ Cmt & Mtx \_\_\_\_\_ Acc loss free

POROSITY: n p m f g x intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic x frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color none even    spotted    pinpoint    bleeding    % in total cuttings   

FLUORESCENCE: Color None \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint % in total cuttings \_\_\_\_\_ % marl \_\_\_\_\_


CHLOROTHENE CUT: Color 2000 Development                      Residual                     

**CUT FLUORESCENCE:** Color None Development                      Residual                     

MUD PROPERTIES: WA 13.1 PV 46 FH 30.0 %OH 5 CI 525 pH 10.4 WOB 80/34 RPM 110 GPM 53 FT 2400

REMARKS: SHANK 3, 20111 scale units, sl mud liner in oil over shaker, steady liner in total SH Type Wts Footage  
gas. Place liner from 0' to 4'.

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$



**Analisis cannot and does not guarantee the accuracy or completeness of this data and interpretation. Analisis shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customers resulting from the use of this information or interpretation flows of by any of its agents, servants or employees.**

**ODOR:** n n g

WETTABILITY TEST: + -

#### DIVISION OF XCO

SHOW REPORT# 30 Formation WASATCH FNL

Time 12:30 pm

Date 5/11/05

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 13066' to 13072' with 1 liberated        produced gas

Gross Ft 6 Net Ft         

[illegible]

GAS RATIO EVALUATION:        oil   1   gas        cond.        the   1   wet

LITHOLOGY TYPE: SS BH SLTST LS DOL Other \_\_\_\_\_

%: ( 20 ) ( 30 ) ( ) ( 40 ) ( ) (

Color wh, air Grain/Can Size 1-11 Shape shrd-shang Sorting med Cmt & Mix sale Acc

POROSITY: n   d   m   f   g     X   inorgan          in situ          moldic          frac          vuggy          other

SPUN: Color lt brn 1 even        spotted        pinpoint        bleeding % in total cuttings 12

FLUORESCENCE: Color br. yellow X even        spotted        pinpoint        % in total cuttings 42 % moist       

CHLOROTHENE CUT: Color no1 Development near enough out Residual           


CUT FLUORESCENCE: Color            351            Development            3005            Residual           

MUD PROPERTIES: WA 95.4 PV 46 FI 20 %OIL 35 CI 525 PH 80.4

WOB 20/24 RPM 110 BPM 53 PP 2200

REMARKS: Methane background doubled, 11,397 calc units, GRADE 1 ++

Est Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_



Analix cannot and does not guarantee the accuracy or completeness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



SEC 30 TWP 1 2 RNG 2 2  
JOB# 24-660 WYMAN CO., WYAN

**analex**  
DIVISION OF XCO

SHOW REPORT# 39 Formation INSURE

**Time 11:00 AM**

**Date** 5/12/05

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$

Depth Interval from 13170 to 13180 with        liberated 1 produced gas

Gross Ft 10 Net Ft 10

				TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
		DEPTH	MWFT	UNITS	% M.E.	C1	C2	C3	Σ C4	MINUS BACKGROUND		
										$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
G F P		BACKGROUND	12.2	1730	17.5	3.18	.87	.65	.90			
		13172	11.2	5300	55.0	18.18	4.10	2.29	1.04	4.43	7.94	17.4
		13174	12.1	3600	36.0	20.20	4.41	2.89	1.04	4.58	8.82	19.4
		13176	12.6	7000	70.0	25.80	5.85	3.88	1.04	4.41	8.96	24.8
		13178	13.2	9000	90.0	26.90	9.02	5.47	1.97	2.98	4.92	15.6
		13180	11.4	8400	84.0	23.90	8.41	5.17	2.11	2.84	4.62	11.3

**GAS RATIO EVALUATION:** 1 oil        gas        cond.        lbs        wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other SILTSTONE  
%: ( 10 ) ( 70 ) ( 10 ) ( 10 ) ( ) ( tr )

Color wh. blk Grain/Meal Size fine Shape spn-shrd Sorting yr-med Cnt & Mix nil Acc perh

POROSITY: n p m f g x Intgran \_\_\_\_\_ Intdn \_\_\_\_\_ moldic \_\_\_\_\_ fac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

SPAN: Color blue even X spotted pinpoint bleeding % in total cuttings 3

FLUORESCENCE: Color dark yellow even X spotted        pinpoint        % in total cuttings 3 % resin       

CHLOROTHRENE CUT: Color None Development                      Residual                     

ODOR: n of 95


CUT FLUORESCENCE: Color none Development                      Residual                     

**WETTABILITY TEST:** + -

MUD PROPERTIES: Wt 11.8/13.0 PV 2.2 FR 10.4 %W 4 CI 225 pH 9.6 WOB 22/24 RPM 110 SPN 53 FP 2200

REMARKS: GRADE 1- 34092 units, a liver oil over shaker which died at 13180. Flare liver from 9" Net Type Mrs Footage

to 4', and out with gas 75.1 in. 11.9 out.



Amicus cannot and does not guarantee the accuracy or completeness of this data and interpretation. Amicus shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof or by any of its agents, servants or employees.




OPERATOR QUINEX ENERGYSEC 30 TWP 1 S RNG 2 EWELL RECAP JEC 20-4-A1JOB# 24-660 HURTAN CO., UTAH

analex

DIVISION OF XCO

SHOW REPORT# 40 Formation WASATCHTime 7:00AMDate 5/13/85RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$ Depth Interval from 13274 to 13294 with      liberated X produced gasGross Ft 20 Net Ft 10

	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS		
			UNITS	% M.E.	C1	C2	C3	Σ C4	MINUS BACKGROUND		
									$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
BACKGROUND	12.5	1490	14.90	2.92	.87	.69	.38				
13284	8.9	11900	119.00	35.36	12.31	6.88	2.54	2.89	5.17	14.0	
13286	11.0	11900	119.00	37.22	12.51	7.37	2.94	2.98	5.05	12.6	
13288	9.4	10400	104.00	30.00	11.49	6.88	3.18	2.61	4.36	9.4	
13290	10.2	11000	110.00	34.44	14.56	6.88	3.18	2.36	5.00	30.8	
13292	11.4	11900	119.00	34.44	14.56	6.88	3.18	2.36	5.00	30.8	
BACKGROUND	14.0	10900	109.00	36.4	21.13	6.45	2.88				

GAS RATIO EVALUATION: X oil      gas      cond.      titr      watLITHOLOGY TYPE: SS SH SLTST LS DOL Other ALLSOMITE

%: ( 20 ) ( 60 ) ( ) ( 10 ) ( ) ( 10 )

Color SLT, wh Grain/Size 2 Shape shrd-sbang Sorting 2 Cmt & Mtx gal.9 Acc     POROSITY: n p m f g 2 Ingran      inbdr      moldic      frac      vuggy      other     STAIN: Color same      even      spotted      pinpoint      bleeding      % in total cuttings     FLUORESCENCE: Color same      even      spotted      pinpoint      % in total cuttings      % mwt     CHLOROTHENE CUT: Color same Development      Residual     CUT FLUORESCENCE: Color same Development      Residual     MUD PROPERTIES: VR 33.1 FV 30 FI 30.4 %OH 4 CI 325 pH 9.7 WOB 22/34 RPM 440 GPM 54 PP 3200REMARKS: GRADE 1++, 49.457 scale units, prod gas show w/ val incr oil over shaker.Bit Type      Hrs      Footage     

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.



OPERATOR QUINCY ENERGY  
WELL RESCAP JIC 30-4-81

SEC 30 TWP 1 S 5 RNG 2 E  
JOB# 24-660 HENTON CO., UTAH

**analex**  
DIVISION OF XCO


SHOW REPORT# 41 Formation WASATCH Time 6:00PM  
Date 5/13/85

Depth Interval from 13320 to 13352 with X liberated \_\_\_\_\_ produced gas

Gross Ft 32 Net Ft 28

RATIO PLOT:  $\frac{C1}{C2}$   $\frac{C1}{C3}$   $\frac{C1}{C4}$

G F P	DEPTH	MIN/FT	TOTAL GAS		GAS CHROMATOGRAPHY %				SHOW GAS MINUS BACKGROUND		
			UNITS	% M.E.	C1	C2	C3	Σ C4	$\frac{C1}{C2}$	$\frac{C1}{C3}$	$\frac{C1}{C4}$
			BACKGROUND								
		11.7	6000	60.00	15.3	4.92	3.48	4.45			
	13326	9.8	6200	62.00	17.2	4.62	2.98	.94	3.72	5.77	18.30
	13328	9.2	6300	62.00	17.2	4.62	2.98	.94	3.72	5.77	18.30
	13340	8.6	5200	52.00	17.0	4.31	2.79	.83	3.94	6.09	18.28
	13342	6.0	8200	82.0	32.2	8.21	3.93	4.02	3.92	4.49	34.57
	13344	4.5	8400	84.00	28.5	7.99	4.58	2.34	3.75	6.22	24.76
	13346	5.0	8800	88.00	26.8	7.90	4.78	1.85	3.64	6.02	15.57
	13348	4.6	7400	74.00	23.8	6.46	3.98	4.34	3.68	5.98	18.47
	13350	4.6	7400	74.00	23.8	6.46	3.98	4.34	3.68	5.98	18.47
	13352	8.6	7400	74.00	23.8	6.46	3.98	4.34	3.68	5.98	18.47
	BACKGROUND	12.4	5300	53.00	11.9	4.31	3.48	1.48			



GAS RATIO EVALUATION: X oil \_\_\_\_\_ gas \_\_\_\_\_ cond. X the \_\_\_\_\_ wet

LITHOLOGY TYPE: GS SH SLTST LS DOL Other ALUMINITE

%: ( 20 ) ( 40 ) ( ) ( 10 ) ( ) ( 30 )

Color sh. air Grain/Xtal Size fine Shape sharp-shrd Sorting imp Crnt & Mtr sale, sl Acc carb mat

POROSITY: n p m f g X Ingran \_\_\_\_\_ Inbdr \_\_\_\_\_ moldic \_\_\_\_\_ frac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color a hrs \_\_\_\_\_ even X spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ bleeding \_\_\_\_\_ % in total cuttings 5

FLUORESCENCE: Color none \_\_\_\_\_ even \_\_\_\_\_ spotted \_\_\_\_\_ pinpoint \_\_\_\_\_ % in total cuttings \_\_\_\_\_ % mtrl \_\_\_\_\_

CHLOROTHENE CUT: Color clear Development \_\_\_\_\_ Residual \_\_\_\_\_

CUT FLUORESCENCE: Color dark gold Development dist., clear Residual \_\_\_\_\_

MUD PROPERTIES: WA 14.1 PV 30 FH 10.4 WOI A CI 325 PH 9.7 WOB 22/24 RPM 110 GPM 51 PP 2800

REMARKS: SHALE 9-11, 22509 scale units, sl liner in gas w/ g liner in oil from 13320-13330 BK Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_


g liner in gas w/ a liner in oil from 13340-13352

Analex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analox shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 42      Formation      WASATCH FM.      Time 3:00 pm  
Date 5/14/85

Depth Interval from 13457' to 13474' with X liberated X produced gas

Gross Ft 7 Net Ft       

[illegible]

**GAS RATIO EVALUATION:** 1 oil 1 gas        cond.        the        wet

LITHOLOGY TYPE: SS SH SLTST LS SOL OtherSLSEISE

9: ( 20 ) ( 20 ) ( ) ( 20 ) ( ) ( 20 )

Color wh, lt brn, blk Grain/Obj Size med Shape bird-stung Sorting med Cmt & Mtr calc-sil Acc       

POROSITY: n p 6 l g 8 integran \_\_\_\_\_ intrin \_\_\_\_\_ moldic \_\_\_\_\_ trac \_\_\_\_\_ wuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color lt brn X even    spotted    pinpoint    bleeding % in total cuttings   

FLUORESCENCE: Color None even spotted pinpoint - % in total cuttings        % mmt       

CHLOROTHRENE CUT: Color        pH        Development        Residual       

**CUT FLUORESCENCE:** Date June Development                      Result                     

MUD PROPERTIES: WR 15 PV 45 FI 50.2 %OH 4 GI 505 PH WOB RPM SPM PP

REMARKS: PR smt 4k ga oil over shaker, 25,469 calc units, GRADE 4-1, 5' FLARE Bit Type \_\_\_\_\_ Hrs \_\_\_\_\_ Footage \_\_\_\_\_

Aamlex cannot and does not guarantee the accuracy or correctness of this data and interpretation. Aamlex shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

SHOW REPORT# 43 Formation WASATCH Time 8:00 PM  
Date 5/14/95

Depth Interval from 13402 to 13400 with        liberated        produced gas         

Gross Ft 6 Net Ft 6

[illegible]

GAS RATIO EVALUATION: ~~oil~~ gas \_\_\_\_\_ cond. \_\_\_\_\_ the \_\_\_\_\_ wet

LITHOLOGY TYPE: SS SH SLTST LS DOL Other WILSONITE  
%: ( 20 ) ( 40 ) ( 30 ) ( ) ( ) ( 10 )

Color wh. clr Grain/Meal Size VF-M Shape ang-ctang Sorting M Cmt & Mtx sil Acc carb met

POROSITY: n p m f g 8 intgran \_\_\_\_\_ intdn \_\_\_\_\_ moldic \_\_\_\_\_ trac \_\_\_\_\_ vuggy \_\_\_\_\_ other \_\_\_\_\_

STAIN: Color green X even - X spotted        pinpoint        bleeding % in total cuttings       

FLUORESCENCE: Color lt. yel. green X even        spotted        pinpoint % in total cuttings 5 % marl 0

CHLOROTRINE CUT: Color Blue-Itrel Development                      Residual                     


CUT FLUORESCENCE: Color g/l Development                      Residual                     

MUD PROPERTIES: WR 45.2 PV 46 FI 50.2 %OH 1 CI 525 ph WOB 22/26 RPM 110 SPM 51 PP 2200

REMARKS: MINOR SNOW, 2-3 calc units w/ no liner in gas and no oil over shaker or in samples.      RT Type \_\_\_\_\_      Hrs \_\_\_\_\_      Footage \_\_\_\_\_

~~SS #14 have some stains. GILSHUTE also covered with heavy oil.~~

**RATIO PLOT:**  $\frac{C_1}{C_2}$        $\frac{C_1}{C_3}$        $\frac{C_1}{C_4}$



Analix cannot and does not guarantee the accuracy or correctness of this data and interpretation. Analix shall not be held liable or responsible for any loss, cost, damage or expense incurred or sustained by customer resulting from the use of this information or interpretation thereof by any of its agents, servants or employees.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other in-  
structions on  
reverse side)Form approved.  
Budget Bureau No. 42-R355.5.

5. LEASE DESIGNATION AND SERIAL NO.

14-20-H62 4065

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Redcap

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

9. WELL NO.

Redcap JDC 30-4-1A

10. FIELD AND POOL, OR WILDCAT

Bluebell

11. SEC., T., R., M., OR BLOCK AND SURVEY  
OR AREANW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E12. COUNTY OR  
PARISH

Uintah

13. STATE

Utah

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☒ DRY ☐ Other \_\_\_\_\_  
b. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other \_\_\_\_\_2. NAME OF OPERATOR  
QUINEX ENERGY CORPORATION3. ADDRESS OF OPERATOR  
4527 S 2300 East, #106 Salt Lake City, Utah 84117

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface C NW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E

At top prod. interval reported below

876 FNL 669 FWL  
Same

At total depth

14. PERMIT NO.

43-047-31591

DATE ISSUED

12-11-84

15. DATE SPUDDED 2/15/85 16. DATE T.D. REACHED 5/15/85 17. DATE COMPL. (Ready to prod.) 6/25/85 18. ELEVATIONS (DF, REB, RT, GR, ETC.)\* GR 5344' / KB 5369' 19. ELEV. CASINGHEAD 5344'

20. TOTAL DEPTH, MD &amp; TVD 13,550' 21. PLUG, BACK T.D., MD &amp; TVD 13,510' 22. IF MULTIPLE COMPL., HOW MANY\* 13 zones 23. INTERVALS DRILLED BY → Rotary TOOLS ROTARY TOOLS Rotary CABLE TOOLS None

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\*

12,101' - 13,476' Wasatch

25. WAS DIRECTIONAL  
SURVEY MADE

None

26. TYPE ELECTRIC AND OTHER LOGS RUN

DI-SFL, FDC, CNL, NST, BH-Sonic

NAT GR SPECTROMETRY  
mud log CBL

27. WAS WELL CORED

12 side wall cores

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
10 3/4	40.5	1540.0	14 3/4"	200 sks Class "H", 790 sk lite	Surface
7 5/8	26.4 & 29.7	10,362.79'	9 7/8"	270 sk lite, 300 Class "H"	
5 1/2	22.5	3,371.66	6 3/4"	990 sks Class "H"	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)
5 1/2	10,178	13,550	990 Class H	

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8"	11,984.75	12,003.55
1.9	7,392.38	

31. PERFORATION RECORD (Interval, size and number)

See attached list.

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
12,101-13,476	10,000 Gal HCl 28%
	2,900 CCF N <sup>2</sup> Nitrogen
	160 Gal Corr inhibitor
	2,100# frac divertive agent

33.\* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
6/23/85		Flowing				Flow/testing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
6/26/85	24	12/48	→	673.4	420	18.54	1000/.624
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
2200		→	673.4	420	18.54	43°	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used on lease &amp; vented excess

TEST WITNESSED BY

Paul Wells &amp; H.J. Payne

35. LIST OF ATTACHMENTS

Electric logs, mud logs, Geologic reports, perforations, &amp; Frac.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

*Shells*

TITLE

*Pres.*

DATE

*Aug 6, '85"*

\*(See Instructions and Spaces for Additional Data on Reverse Side)

CONFIDENTIAL

# INSTRUCTIONS

**General:** This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

**Item 4:** If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

**Item 18:** Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

**Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

**Item 29: "Sacks Cement":** Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

**Item 33:** Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

## 37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.
Uinta	4,580	4,600	Water
Uinta	5,150	5,180	Water
Green River	6,210	9,030	Oil & Gas
Wasatch	9,890	9,918	Oil
Wasatch	11,890	11,986	Oil & Gas
Wasatch	12,100	13,476	Oil & Gas

## 38.

## GEOLOGIC MARKERS

NAME	TOP	
	MEAS. DEPTH	TRUE VERT. DEPTH
Uinta Fm.	2,315	+3057'
Green River	5,323	- 456'
Black Shale Mbr.	8,906	-3534'
Wasatch Trans.	9,104	-3732'
Wasatch Fm	9,547	-4175'
Wasatch B	12,596	-7224'
Neola 3 Fingers	12,969	-7597'

# QUINEX ENERGY CORPORATION

Redcap J.D.C. No. 30-4-1A

NE $\frac{1}{4}$ , NE $\frac{1}{4}$ , Section 30, Township 1 South, Range 2 East  
Uintah County, Utah

## PROPOSED PERFORATIONS BASED ON GAMMA RAY B.H.B. SONIC LOG

### 3-SPF

<u>Interval</u>	<u>No. of Shots</u>
1) 13,472; 73, 74, 75, 76	15
2) 13,440; 42, 44, 45	12
3) 13,302; 04, 14, 16	12
4) 13,262; 64, 68, 70	12
5) 13,174; 76, 77, 86, 88, 90	18
6) 13,009; 10, 11, 23, 25, 26	18
7) 12,986; 88, 90	9
8) 12,938; 39, 40, 41, 42, 43	18
9) 12,904; 06, 08, 10, 12, 14, 16, 18, 20	27
10) 12,866; 68, 70, 72	12
11) 12,834; 36, 38, 40	12
12) 12,817; 18, 19, 20, 23, 24	18
13) 12,768; 69, 70, 84, 86, 87	18
14) 12,688; 90, 92, 94	12
15) 12,608; 09, 12, 13, 16	15
16) 12,576; 78, 80, 82	12
17) 12,324; 26, 31, 33, 37, 39	18
18) 12,283; 84, 85	9
19) 12,264; 66, 70, 71, 73, 74	18
20) 12,148; 49, 50, 53, 54	15
21) 12,101; 03, 05, 07, 09	15
Total Shots	315

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN THIS CASE

RECEIVED

Form approved.  
Budget Bureau No. 42-RBFor other in-  
structions on  
reverse side)

SEP 23 1985

5. LEASE DESIGNATION AND SERIAL NO.

14-20-H62 4065

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Redcap

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

9. WELL NO.

Redcap JDC 30-4-1A

10. FIELD AND POOL, OR WILDCAT

Bluebell

11. SEC., T., R., M., OR BLOCK AND SURVEY  
OR AREANW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E12. COUNTY OR  
PARISH

Utah

13. STATE

Utah

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☒ DRY ☐ Other

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ OtherDIVISION OF  
GAS & MINING

2. NAME OF OPERATOR

QUINEX ENERGY CORPORATION

3. ADDRESS OF OPERATOR

4527 S 2300 East, #106 Salt Lake City, Utah 84117

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface C NW $\frac{1}{4}$  Sec. 30, T 1 S, R 2 E

At top prod. interval reported below

Same

At total depth

14. PERMIT NO.

43-047-31591

DATE ISSUED

12-11-84

15. DATE SPUDDED

2/15/85

16. DATE T.D. REACHED

5/15/85

17. DATE COMPL. (Ready to prod.)

6/25/85

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\*

GR 5344' / KB 5369'

19. ELEV. CASINGHEAD

5344'

20. TOTAL DEPTH, MD &amp; TVD

13,550'

21. PLUG, BACK T.D., MD &amp; TVD

13,510'

22. IF MULTIPLE COMPL.,  
HOW MANY\*

13 zones

23. INTERVALS  
DRILLED BY

Rotary

ROTARY TOOLS

Rotary

CABLE TOOLS

None

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\*

12,101' - 13,475'

25. WAS DIRECTIONAL  
SURVEY MADE

None

26. TYPE ELECTRIC AND OTHER LOGS RUN

DI-SFL, FDC, CNL, NST, BH-Sonic

27. WAS WELL CORED

12 side wall cores

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
10 3/4	40.5	1540.0	14 3/4"	200 sks Class "H", 790 sk lite	Surface
7 5/8	26.4 & 29.7	10,362.79'	9 7/8"	270 sk lite, 300 Class "H"	
5 1/2	22.5	3,371.66	6 3/4"	990 sks Class "H"	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
5 $\frac{1}{2}$	10,178	13,550	990 Class H		2 7/8"	11,984.75	12,003.55
					1.9	7,392.38	

31. PERFORATION RECORD (Interval, size and number)

See attached list.

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
12,101-13,476'	10,000 Gal HCl 28%
	2,900 CCF N $_2$ Nitrogen
	160 Gal Corr inhibitor
	2,100# frac divertive agent

33.\* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
6/23/85		Flowing				Flow/testing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
6/26/85	24	12/48	→	673.4	420	18.54	1000/.624
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
2200		→	673.4	420	18.54	43°	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used on lease &amp; vented excess

TEST WITNESSED BY

Paul Wells &amp; H.J. Payne

35. LIST OF ATTACHMENTS

Electric logs, mud logs, Geologic reports, perforations, &amp; Frac.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

TITLE

DATE

\*(See Instructions and Spaces for Additional Data on Reverse Side)

CONFIDENTIAL





DIVISION OF XCO

RECEIVED

AUG 07 1985

DIVISION OF OIL  
GAS & MINING

1860 Lincoln Street, Suite 780, Denver, Colorado 80203

(303) 863-0014

QUINEX ENERGY CORPORATION

REDCAP J.D.C. 30-4-A1

SECTION 30 - T1S - R2E

UINTAH COUNTY, UTAH

CONFIDENTIAL

LOGGING GEOLOGISTS: Forrest A. Smouse  
Kevin R. Stank  
ANALEX

RESUME

OPERATOR: Quinex Energy Corporation  
WELL NAME & NUMBER: Redcap J.D.C. 30-4-A1  
LOCATION: Section 30 - T1S - R2E  
COUNTY & STATE: Uintah County, Utah  
SPUD DATE: March 11, 1985  
COMPLETION DATE: May 15, 1985  
ELEVATIONS: 5,344' GL 5,373' KB  
TOTAL DEPTH: 13,550' DRLR  
CONTRACTOR: Montgomery Drilling  
RIG: #32  
TYPE RIG: National 110  
PUMPS: PZ10 10" x 6"  
GEOLOGIST: DeForrest Smouse  
ENGINEER: H. J. Payne  
TOOL PUSHER: Dick Polland  
TYPE DRILLING MUD: Fresh water to Wt & Chem  
MUD COMPANY: Davis Mud  
MUD ENGINEER: Gary Knothe  
HOLE SIZES: 12½" to 1,500'; 9-7/8" to 10,400'; 6-3/4" to 13,550'  
CASING: 10-3/4" to 1,500'; 7-5/8" to 10,400'; 5½" to 13,550'  
LOGGING GEOLOGISTS: Forrest A. Smouse, Kevin R. Stank - ANALEX  
TYPE UNIT: 2-Man, FID Total Hydrocarbon Analyzer, FID Gas Chromatograph  
ELECTRIC LOGS BY: Schlumberger, Gearhart  
TYPE LOGS: Dual Induction, Sonic, NGT, Sidewall Cores  
BOTTOM FORMATION: Wasatch Formation  
WELL STATUS: Completion for production

## SUMMARY AND CONCLUSIONS

Quinex Energy's Redcap J.D.C. 30-4-A1 well was spudded on March 11, 1985. Drilling progressed with few delays and a total depth of 13,550' (driller) was reached on May 15, 1985.

Hydrocarbon logging commenced at 5,000' on March 22, 1985 through total depth. The stratigraphic units encountered during this time ranged from the Uinta formation to the basal Wasatch formation. The primary objectives were the Lower Wasatch formation with secondary objectives in the Lower Green River formation, and the Black Shale Facies.

The Uinta formation was topped at 3,040' (e-log depth) with hydrocarbon logging employed at 5,000'. A 1200 unit gas increase was recorded from 5,532'-5,540'. The samples consisted of 70% sandstone and showed light oil staining and bright yellow-green fluorescence with a good streaming cut, but was evaluated as being wet.

The top of the Green River formation was cut at 5,828'. There were nine shows observed in this zone; all sandstone with varying degrees of oil staining and fluorescence.

The top of the Black Shale Facies of the Green River formation was cut at 8,906'. There was only one show (#10). The sample was 60% sandstone with light brown oil stain, with yellow-green fluorescence and good streaming cut.

The top of the Wasatch transition was cut at 9,104' with only one show (#11). The sample was 60% sandstone with light to dark brown even to spotty oil staining, dull yellow-green fluorescence, and slow streaming cut.

The top of the Wasatch formation was cut at 9,547'. Thirty-one shows were cut in this formation, consisting of fractured shales and sands to porous sandstones. The best production comes from Show #32 through Show #43.

## FORMATION SUMMARY

NOTE: All tops are based upon samples and electric log evaluation. All other zones of interest are based upon samples and information obtained during the drilling process. Footage and penetration rate were obtained from the drilling contractor's geolograph.

### UINTA FORMATION

3,040' ( 2,333')

Geologic sampling commenced within the Uinta formation. Drill rate averaged 2 min/ft. Samples consisted primarily of unconsolidated, fine to medium grained sandstone, and red, light gray, yellow, purple, light brown, gray-green, occasionally silty, slightly calcareous shales (mudstones). One minor show with fluorescence and oil cut was observed.

### GREEN RIVER FORMATION

5,828' (-455')

The Green River formation drilled smoothly with a drill rate of 2 to 4 min/ft and no significant breaks were observed. The Green River consists of light to medium gray, gray-green, light brown, slightly silty to slightly calcareous shales; brown, dark gray to gray-green, slightly silty marlstones; white to clear, poor to moderately indurated, very fine to medium grained, subround to subangular and moderately sorted sandstones, some of which showed slight oil stains and fluorescence. Samples also contained minor amounts of white to light gray siltstones; light gray, light to dark brown limestones; amorphous anhydrites; and water-lain and reworked light gray to white, micaceous tuffs.

### BLACK SHALE FACIES

8,906' (-3,533')

The Black Shale drilled with an average of 4 min/ft and no significant drilling breaks. The interval was characterized by dark brown to black, yellow, occasional light gray to gray-green, moderately silty, moderately calcareous, and occasionally fissile shales. Samples also showed a predominance of white to clear, fine grained, subround to subangular, moderately sorted, calcareous sandstones, with minor oil staining in some of the samples.

### WASATCH TRANSITION ZONE

9,104' (-3,731')

The Transition Zone drill rate slowed to an average of 6.5 min/ft. Samples were red to reddish brown, dark to medium gray, light brown, slightly silty, slightly calcareous, and occasionally micaceous shales. Samples showed an abundance of white to clear, moderately indurated, very fine to medium grained, subround to subangular, moderately sorted, calcareous to silica cemented sandstones with one minor show (#11) having a spotty brown oil stain, dull yellow fluorescence, and poor streaming cut.

### WASATCH FORMATION

9,547' (-4,174')

The Wasatch had an erratic drill rate varying from 5 min/ft to 25 min/ft. Samples from the Wasatch were red, light to dark gray, dark brown, gray-green, smooth to slightly silty, none to moderately calcareous shales. Minor amounts of buff to cream, light gray-brown to dark brown, cryptocrystalline to micro-crystalline, chalky in part, none to moderately argillaceous, lacustrine limestone, with an abundance of Ostracods and fish bone and scale fragments.

FORMATION SUMMARY (Cont.)

Sandstones were white to clear, light brown, moderate to well indurated, very fine to medium grained, moderately sorted, calcareous to silica cemented, occasionally glauconitic. The Wasatch formation had an unusual amount of Gilsonite throughout, which is seldom seen in the rest of the Uintah Basin. Show #32 at 12,836' (-7,463') produced dark green oil which ran through the gasbuster and continued until total depth. Most shows below 12,836' were very good.

Total depth was reached in the Basal Wasatch formation.

## WELL TREATMENT REPORT

DOWELL

JUN 28 1985

DWL-494-N PRINTED IN U.S.A.

DOWELL DIVISION OF DOW CHEMICAL U.S.A.

DATE

6-24-85

WELL NAME AND NUMBER

LOCATION (LEGAL)

DOWELL LOCATION

TREATMENT NUMBER

Redcap JDC 30-4-18

30 1st 2E

Jurnal Lake

PAGE 1 OF 2 PAGES

POOL / FIELD

FORMATION

JOB DONE DOWN

ALLOWABLE PRESSURE

COUNTY / PARISH

STATE

TYPE OF WELL

TBG: 10000

CSG: 3000

OIL API GRAVITY

VAPOR PSI

TYPE OF SERVICE

SERVICE NAME

AGE OF WELL

TOTAL DEPTH

BHT. (LOG)

☐ Acidizing  
☐ Fracturing☐ Sand Control  
☐ Other15% HCl + N<sub>2</sub>

NEW WELL

REWORK

CASING SIZE

WT.

DEPTH

TUBING SIZE

WT.

DEPTH

TYPE OR GRADE

TYPE OR GRADE

LINER SIZE

WT.

TOP-BOTTOM

PACKER TYPE

PACKER DEPTH

OPEN HOLE

CASING VOL.

TUBING VOL.

ANNULAR VOL.

CUST. NAME

Quinex Energy Co.

ADDRESS

CITY, STATE  
ZIP CODE

SERVICE INSTRUCTIONS:

Treat with 20000 gal 15%  
HCl, 8/1000 A-200 inhibitor, 1/1000 W-27 non-emulsifier,  
5/1000 U-42 Iron Control, 1/1000 J-321 Friction Reducer,  
2/1000 Rock Salt 310 lbs BAF, 315 1.3 Balls 280000 SCF N<sub>2</sub>  
FOR CONVERSION PURPOSES 24 BBLs EQUALS 1000 GALLONS

ARRIVED ON LOCATION:

LEFT LOCATION:

DIAMETER OF PERFORATIONS =

## PERFORATED INTERVALS

TOP	TO	BOTTOM	NO. OF HOLES	TOP	TO	BOTTOM	NO. OF HOLES
12101	TO	13476	315		TO		
	TO				TO		
	TO				TO		
	TO				TO		

TIME (0701 to 2400)	INJECTION RECORD							PRESSURE		NOTATIONS
	RATE BPM	TYPE OF FLUID	DENSITY	INCREMENT VOL BBLs	CUM. VOL BBLs	PROP TYPE	PROP #/GAL	CSG.	TBG.	
										Pre-Job Safety Meeting
										Pre-Job Pressure Test To _____ psi
8:43		15% Acid		80						start acid + 500 SCF N <sub>2</sub> /BBL
					80					shut down change A.T.R.
10		2% KCl		12	80			8000		Div. 300 R.S. 300 BAF 45 Balls
10		15% Acid		60	92			8500		
11		2% KCl		12	152			3000	10070	Div. 300 R.S. 300 BAF, 45 Balls
11		15% Acid		60	164			9990		
12		2% KCl		12	224			10080		Div. 300 R.S. 300 BAF 45 Balls
11 1/2		15% Acid		60	236			9920		
11		2% KCl		12	296			10050		Div 300 R.S. 300 BAF 45 Balls
11		15% Acid		60	308			3050	9870	
11		2% KCl		12	368			10140		Div 300 R.S. 300 BAF 45 Balls
10.8		15% Acid		60	380			9930		
9:46	11	2% KCl		12	440			10040		Div 300 R.S. 300 BAF 45 Balls
9:47	11	15% Acid		60	452			3100	9780	
11		2% KCl		12	512			10140		Div 300 R.S. 300 BAF 45 Balls

FRAC. GRADIENT

AVG. INJECTION RATES

13 1/2 with N<sub>2</sub>

118 BPM. Fluid

W-27 500 SCF/BBL N<sub>2</sub>

MATERIALS CHARGED FOR:

TOTAL FLUID

TOTAL PROP

MTRL

QUANTITY

MTRL

QUANTITY-

685 BBLs

LBS

TREATING PRESSURE SUMMARY

5900

MAX 10 210

FINAL 9300

AVG. 9742

IMMED. S.D.P.

15 MIN. SIP

PRODUCTION PRIOR TO THIS TR.

☐ Test Stabilized

CUSTOMER REPRESENTATIVE

DOWELL SERVICE SUPERVISOR

Smoky Daine

L. Davis



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ well gas ☐ well other ☐  
2. NAME OF OPERATOR  
QUINEX ENERGY CORPORATION  
3. ADDRESS OF OPERATOR  
4527 S. 2300 East #106, SLC, Utah 84117  
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: 876' S of N line, 669' E of W line  
AT TOP PROD. INTERVAL: Sec. 30  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other) Water disposal approval		

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Production water stored on location in #1 power water tank. Tank capacity 480 bbls.

Water disposal will be by truck to Murray's or Dalbo's disposal pit. Average water production for well as of 3/15/86 is less than 1/10 bbl. per day.

5. LEASE 14-20-H62-4065
6. IF INDIAN, ALLOTTEE OR INDIAN NAME Redcap
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
9. WELL NO. Redcap JDC 30-4-1A
10. FIELD OR WILDCAT NAME East Bluebell
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 30, T 1 S, R 2 E
12. COUNTY OR PARISH Uintah
13. STATE Utah
14. API NO. 43-047-31591
15. ELEVATIONS (SHOW DF, KDB, AND WD) 5344 GR 5369 KB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct.

SIGNED [Signature] TITLE President DATE Mar 20, 86

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

Federal approval of this action  
is required before commencing  
operations.

ACCEPTED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE 3-25-86  
BY [Signature]

\*See Instructions on Reverse Side



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☒ gas well ☐ other ☐

2. NAME OF OPERATOR  
QUINEX ENERGY CORPORATION

3. ADDRESS OF OPERATOR  
4527 So. 2300 East #106 SLC, Utah 84117

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: 876' S of N line, 669' E of W line  
AT TOP PROD. INTERVAL: Sec. 30  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>

(other) Emergency pit approval

5. LEASE  
14-20-H62-4065

6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
Redcap

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

9. WELL NO.

Redcap JDC 30-4-1A

10. FIELD OR WILDCAT NAME  
East Bluebell

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA  
Sec. 30, T 1 S, R 2 E

12. COUNTY OR PARISH  
Uintah

13. STATE  
Utah

14. API NO.  
43-047-31591

15. ELEVATIONS (SHOW DF, KDB, AND WD)  
5344 GR 5369 KB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Request for emergency pit to be located on southwest corner of location to facilitate emergency production operation and safety.

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE

DATE

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

**Federal approval of this action  
is required before commencing  
operations.**

\*See Instructions on Reverse Side

**ACCEPTED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**

DATE: 3-25-86

BY: John R. Baya



STATE OF UTAH  
NATURAL RESOURCES  
Oil, Gas & Mining

Norman H. Bangerter, Governor  
Dee C. Hansen, Executive Director  
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

April 28, 1986

Quinex Energy Corporation  
4527 South 2300 East #106  
Salt Lake City, Utah 84117

Gentlemen:

Re: Well No. Redcap J.D.C. 30-4-1A - Sec. 30, T. 1S., R. 2E.,  
Uintah County, Utah - API #43-047-31591

A review of our records indicates that copies of the side wall cores which were run on the referenced well as indicated on the Well Completion Report dated August 6, 1985, have not been received.

Rule 312, Oil and Gas Conservation  
copies of the well logs and cores by  
completion.

Please provide copies of the re  
earliest convenience.

NORM SAID IF WE  
DON'T HAVE LOGS GO  
AHEAD AND REQUEST  
LOGS AND 12 SIDEWALL  
CORE.

cc: Dianne R. Nielson  
Ronald J. Firth  
John R. Baza  
File

WE HAVE THE LOGS  
SO HE SAID DON'T ASK  
FOR THE CORES.

0170S/21

UC 7-21-87



STATE OF UTAH  
NATURAL RESOURCES  
Oil, Gas & Mining

Norman H. Bangerter, Governor  
Dee C. Hansen, Executive Director  
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

April 28, 1986

Quinex Energy Corporation  
4527 South 2300 East #106  
Salt Lake City, Utah 84117

Gentlemen:

Re: Well No. Redcap J.D.C. 30-4-1A - Sec. 30, T. 1S., R. 2E.,  
Uintah County, Utah - API #43-047-31591

A review of our records indicates that copies of the side wall cores which were run on the referenced well as indicated on the Well Completion Report dated August 6, 1985, have not been received.

Rule 312, Oil and Gas Conservation General Rules, requires that copies of the well logs and cores be submitted within 90 days of completion.

Please provide copies of the required side wall cores at your earliest convenience.

Respectfully,

Norman C. Stout  
Administrative Assistant

cc: Dianne R. Nielson  
Ronald J. Firth  
John R. Baza  
File

0170S/21

NOV 16 1987

DIVISION OF  
OIL, GAS & MINING

REFERRAL FORM  
Division of Environmental Health  
288 North 1460 West  
P.O.B. 16700  
Salt Lake City, Utah 84116-0700  
(801) 538-6121

Environmental Health 24-Hour Emergency Phone Number 538-6333  
Phone #s 538- 6108 Air Quality 6734 Radiation Control  
6163 General Sanitation 6170 Solid & Hazardous Waste  
6159 Public Water Supplies ~~6171~~ Water Pollution Control

REFERRED TO: ~~6108~~ <sup>6108</sup> AND Oil Gas Mining

GENERAL INFORMATION

Date 11-11-87 Time of Observation 11:15 AM

Company/Industry/Community/Individual: Site: Quinex  
Energy Corp.

Contact \_\_\_\_\_ Phone # \_\_\_\_\_

Location NW 1/4 Sec 30 T150 R2E Uintah Co.

County Uintah

COMPLAINANT

Name \_\_\_\_\_

Address \_\_\_\_\_

Phone # \_\_\_\_\_

OBSERVER

Name Ed Riege AS.

Agency Uintah Basin Dist H.D.

TYPE OF INCIDENT

- ☐ New Construction
- ☐ Visible Emission
- ☒ Open Burning
- ☐ Impoundment
- ☐ Bypass
- ☐ Spill
- ☐ Odor
- ☐ Food
- ☐ Abandoned Waste
- ☐ Radiation
- ☐ Drinking Water
- ☐ Other (indicate) \_\_\_\_\_

PLOT DESCRIPTION/DIAGRAM

COMMENTS

It was observed on this date open burning of  
oil pits at the above location, large black-gray  
plumes could be seen coming from Redcap JDC  
#30-4-1A, Lease # API #43-047-3159/  
#14-20-H62 4065

orig file  
R. Firth  
J. Bara  
FYB  
Well file

112432

Pow


Redcap JDC #30-4-1A SEC 39 T 1 So, 2W Chubby 11/23/88

N

emergency  
pit



boiler



propane tank




meter run



Wellhead.


separator




pump




H<sub>2</sub>O tank



production  
tanks





## QUINEX ENERGY CORPORATION

465 South 200 West • Suite 300 • Bountiful, Utah 84010 • (801) 292-3800 • FAX (801) 295-5858

November 16, 1992

State of Utah  
Division of Oil, Gas & Mining  
355 West North Temple  
3 Triad Center, Suite 350  
Salt Lake City, Utah 84180-1203

Ref: Quinex Energy Corporation  
Malnar Pike 1-17, API No. 43-047-31714  
Sam Houston 24-4, API No. 43-047-31653  
Leslie Taylor 24-5, API No. 43-047-31828  
CMS 1-13A1, API No. 43-047-31711  
Einerson 1-4B1E, API No. 43-047-31940  
Allred 2-32A1E, API No. 43-047-31889  
JDC Redcap 30-4, API No. 43-047-31591  
Chasel Sprouse 1-18, API No. 43-047-31695  
Merlene 2-36A3, API No. 43-013-31247  
Bowen-Bastian 1-14A1, API No. 43-047-31713  
Uinta-Sam 28-2R, API No. 43-047-30127

RECEIVED

NOV 16 1992


DIVISION OF  
OIL GAS & MINING

Gentlemen:

Quinex Energy Corporation plans to install into the present site of the overflow pit a 400 barrel tank, cut in half longitudinally. The tank will be laid on rock or, if necessary on small concrete walls allowing a check for leakage. The proposed layout of the overflow tank is indicated on the enclosed drawing.

Quinex Energy Corporation expects to have the installation of the overflow tank accomplished by 1 January 1994.

Sincerely,

  
DeForrest Smouse,  
Vice President, Quinex Energy


RECEIVED

NOV 18 1992

DIVISION OF  
OIL GAS & MINING

QUINEX ENERGY CORPORATION

# OVERFLOW TANK PLAN



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE  
(Other instructions on reverse side)

Form approved.  
Budget Bureau No. 1004-0135  
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. 14-20-H62 4065	
2. NAME OF OPERATOR QUINEX ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME Redcap	
3. ADDRESS OF OPERATOR 465 SOUTH 200 WEST, SUITE #300, BOUNTIFUL, UTAH 84010		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface C NW $\frac{1}{4}$ , Section 30, T1S, R2E		8. FARM OR LEASE NAME	
14. PERMIT NO. 43-047-31591		9. WELL NO. Redcap JDC #30-4-1A	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 5344' / KB5369'		10. FIELD AND POOL, OR WILDCAT Bluebell	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW $\frac{1}{4}$ Sec. 30, T1S, R2E	
		12. COUNTY OR PARISH Uintah	
		13. STATE Utah	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	<input checked="" type="checkbox"/>

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) Notice of Gas Venting <input type="checkbox"/>	
(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

On or about 7/21/90 Gary Williams Energy had an explosion at their Wasatch Gas Plant. Due to the explosion of the plant we are unable to make gas deliveries and found it necessary to vent our gas.

The Gas Plant should be back on line within a month and normal deliveries of gas will resume.

OIL AND GAS	
DFN	RJF
JPB <input checked="" type="checkbox"/>	GLH
DIS	SLS
2-DME	
3- MICROFILM <input checked="" type="checkbox"/>	
4- FILE	

18. I hereby certify that the foregoing is true and correct

SIGNED Robert S. Smith

TITLE Vice-President

DATE August 1, 1990

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

Federal approval of this action is required before commencing operations.

TITLE \_\_\_\_\_

ACCEPTED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 8-16-90

BY: John R. Bay

\*See Instructions on Reverse Side



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE  
(Other instructions on reverse side)

Form approved.  
Budget Bureau No. 1004-0135  
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. 14-20-H62-4065
2. NAME OF OPERATOR QUINEX ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME REDCAP
3. ADDRESS OF OPERATOR 465 SOUTH 200 WEST, SUITE 300, BOUNTIFUL, UTAH 84010		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface NW $\frac{1}{4}$ NW $\frac{1}{4}$ Section 30, Township 1 South, Range 2 East		8. FARM OR LEASE NAME J.D.C. REDCAP
14. PERMIT NO. 43-047-31591		9. WELL NO. 30-4-1A
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 5344' ; KB 5369'		10. FIELD AND POOL, OR WILDCAT BLUEBELL
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW $\frac{1}{4}$ NW $\frac{1}{4}$ Sec 30, T1S, R2E
		12. COUNTY OR PARISH UINTAH
		13. STATE UTAH

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON\*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT\*

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Sept 22-28, 1992 The well developed a leak in its production tubing and while tubing was being pulled the string parted. Retrieved same and replaced 7200' with new tubing. Removed production packer and after scraping well replaced Modle R Packer at 12,023'.

Sept 30, 1992 Acid treatment of well with 3000 gallons 15% Hcl & 510 gallons of Methanal plus 1000# Kcl. Maximum pressure 950#. Average rate 3 barrels per minute. ISIP 510# dropped off to 0 in 1 minute.

RECEIVED

OCT 26 1992

DIVISION OF  
OIL GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED

*Robert L. Moore*

TITLE

Vice Pres/Quinex

DATE

10/23/92

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE\*  
(Other instruction on re-  
verse side)

Budget Bureau No. 1004-0135  
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. 14-20-H62-4065	
2. NAME OF OPERATOR QUINEX ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME REDCAP	
3. ADDRESS OF OPERATOR 465 SOUTH 200 WEST, SUITE 300, BOUNRIDUL, UTAH 84010		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 876' FNL 669' FWL Section 30, T 1 S R 2 E UINTAH, COUNTY, UTAH		8. FARM OR LEASE NAME J.D.C. REDCAP	
14. PERMIT NO. 43-047-31591		9. WELL NO. 30-4	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) KB - 5366' GR - 5344'		10. FIELD AND POOL, OR WILDCAT BLUEBELL	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW $\frac{1}{4}$ , NW $\frac{1}{4}$ , Sec 30, T1S, R2E	
		12. COUNTY OR PARISH UINTAH	13. STATE UTAH

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) Install Overflow Tank	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

1. Remove contaminated soil in and around present pit and dispose of in an appropriate manner.
2. Install a 12' diameter x 5' tall flat bottomed tank, constructed of 10 guage steel, capacity 100 bbls fluid, mounted on 4 $\frac{1}{2}$ " drill pipe skid into present site of overflow pit. All flow lines from tank battery run directly into tank.
3. Cleaned pit will remain as an emergency containment for emergency containment of fluid in excess of 100 bbls.

\*Accepted by the State  
of Utah Division of  
Oil, Gas and Mining

Date: 4-19-93

By: [Signature]

RECEIVED

APR 14 1993

DIVISION OF  
OIL GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature]

TITLE Vice President

DATE 4/13/93

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

\* Follows BOCAL Guidance for pit lining  
and cleanup levels.

\*See Instructions on Reverse Side

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE  
(Other instructions on reverse side)

Form approved.  
Budget Bureau No. 1004-0135  
Expires August 31, 1985

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. 14-20-H62-4065
2. NAME OF OPERATOR Quinex Energy Corporation		6. IF INDIAN, ALLOTTEE OR TRIBE NAME Redcap
3. ADDRESS OF OPERATOR 465 South 200 West, Suite #300, Bountiful, Utah 84010		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 876' FNL 669' FWL Section 30, T1S, R2E		8. FARM OR LEASE NAME J.D.C. Redcap
14. PERMIT NO. 43-047-31591		9. WELL NO. #30-4-1A
15. ELEVATIONS (Show whether DF, RT, GR, etc.) KB 5366' GR 5344'		10. FIELD AND POOL, OR WILDCAT Bluebell
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW $\frac{1}{4}$ , NW $\frac{1}{4}$ Section 30, T1S, R2E
		12. COUNTY OR PARISH Uintah
		13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

PULL OR ALTER CASING

WATER SHUT-OFF

REPAIRING WELL

FRACTURE TREAT

MULTIPLE COMPLETE

FRACTURE TREATMENT

ALTERING CASING

SHOOT OR ACIDIZE

ABANDON\*

SHOOTING OR ACIDIZING

ABANDONMENT\*

REPAIR WELL


CHANGE PLANS

(Other)

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

12/15-17/93 Swabbed well down to 6400'. Injected 50 barrels warm condensate with 15 gallons scale inhibitor. Displace same with 50 barrels hot water.



18. I hereby certify that the foregoing is true and correct

SIGNED

*D. Stuart Brown*

TITLE

President

DATE

3/9/94 ✓

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5 APR ' 5 1994	
2. NAME OF OPERATOR QUINEX ENERGY CORPORATION			
3. ADDRESS OF OPERATOR 465 SOUTH 200 WEST, SUITE #300, BOUNTIFUL, UTAH 84010			
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 876' FNL 669' FWL SECTION 30, T. 1 S., R. 2 E., USBM			
14. API NUMBER 43-047-31591		15. ELEVATIONS (Show whether OF, RT, GR, etc.) KB - 5566' GR - 5544'	
5. LEASE DESIGNATION AND SERIAL NO. 14-20-H62-4065		6. IF INDIAN, ALLOTTEE OR TRIBE NAME REDCAP	
7. UNIT AGREEMENT NAME		8. FARM OR LEASE NAME J.D.C. REDCAP	
9. WELL NO. 30-4-1A		10. FIELD AND POOL, OR WILDCAT BLUEBELL	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW $\frac{1}{4}$ , NW $\frac{1}{4}$ SEC 30, T1S, R2E		12. COUNTY OR PARISH UINTAH	
13. STATE UTAH			

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <u>PRODUCTION ENHANCEMENT</u> <input checked="" type="checkbox"/>	
(Other) <input type="checkbox"/>		(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) \*

1. PULLED DOWNHOLE PUMP FROM HOLE.
2. SWABBED WELL DOWN THREE DAYS. PULLED HARD TO RELIEVE HYDROSTATIC PRESSURE. RAN BLANKING SLEEVE.
3. TREATED WITH 100 BARRELS CONDENSATE WITH 20 GALLONS TC 4201 AND TWENTY GALLONS TH 767. DISPLACE WITH WATER. HOT OIL SYSTEM.
4. RETURNED TO PRODUCTION.

18. I hereby certify that the foregoing is true and correct

SIGNED <u>[Signature]</u>	TITLE <u>PRESIDENT</u>	DATE <u>4/14/94</u>
(This space for Federal or State office use)		
APPROVED BY _____	TITLE _____	DATE <u>5/25/95</u>
CONDITIONS OF APPROVAL, IF ANY:		

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well:    OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: 14-20-H62-4065
2. Name of Operator: QUINEX ENERGY CORPORATION	6. If Indian, Allottee or Tribe Name: REDCAP
3. Address and Telephone Number: 465 South 200 West, Bountiful, Utah 84010 #300 (801) 292-3800	7. Unit Agreement Name:
4. Location of Well Footages:        876' FNL 669' FWL OQ, Sec., T., R., M.:    NW $\frac{1}{4}$ , NW $\frac{1}{4}$ , Section 30, T1S, R2E	8. Well Name and Number: J.D.C. REDCAP #30-4-1A  9. API Well Number: 43-047-31591  10. Field and Pool, or Wildcat: BLUEBELL
County:    UINTAH State:      UTAH	

### 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<div style="display: flex; justify-content: space-between;"> <div> <input type="checkbox"/> Abandonment  <input type="checkbox"/> Casing Repair  <input type="checkbox"/> Change of Plans  <input type="checkbox"/> Conversion to Injection  <input type="checkbox"/> Fracture Treat  <input type="checkbox"/> Multiple Completion  <input type="checkbox"/> Other _____         </div> <div> <input type="checkbox"/> New Construction  <input type="checkbox"/> Pull or Alter Casing  <input type="checkbox"/> Recompletion  <input type="checkbox"/> Shoot or Acidize  <input type="checkbox"/> Vent or Flare  <input type="checkbox"/> Water Shut-Off         </div> </div>	<div style="display: flex; justify-content: space-between;"> <div> <input type="checkbox"/> Abandonment  <input type="checkbox"/> Casing Repair  <input type="checkbox"/> Change of Plans  <input type="checkbox"/> Conversion to Injection  <input type="checkbox"/> Fracture Treat  <input checked="" type="checkbox"/> Other <u>NOTICE OF GAS VENTING</u> </div> <div> <input type="checkbox"/> New Construction  <input type="checkbox"/> Pull or Alter Casing  <input type="checkbox"/> Shoot or Acidize  <input type="checkbox"/> Vent or Flare  <input type="checkbox"/> Water Shut-Off         </div> </div>
Approximate date work will start _____	Date of work completion _____  <small>Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.</small> <small>* Must be accompanied by a cement verification report.</small>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

On or about 10/15/94 Gary Williams Energy Corporation had an explosion at their Montwell Gas Plant. Due to the explosion we were unable to make gas deliveries or purchase dry gas for well operations. Quinex Energy Corporation was forced to burn wet gas and to vent excess gas.

The gas plant status has not been released and the date of re-opening purchase lines should occur within the month.

13. Name & Signature: DeForrest Smouse Title: President Date: 10/18/94

(This space for State use only)

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: 14-20-H62-4065
2. Name of Operator: QUINEX ENERGY CORPORATION	6. If Indian, Allottee or Tribe Name: REDCAP
3. Address and Telephone Number: 465 SOUTH 200 WEST, SUITE 300, BOUNTIFUL, UTAH 84010	7. Unit Agreement Name:
4. Location of Well Footages: 876' FNL, 669' FWL NW $\frac{1}{4}$ NW $\frac{1}{4}$ , Section 30, T1S, R2E	8. Well Name and Number: J.D.C. REDCAP #30-4-1A
County: UINTAH State: UTAH	9. API Well Number: 43-047-31591
10. Field and Pool, or Wildcat: BLUEBELL	

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

### NOTICE OF INTENT (Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment             | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair           | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans         | <input type="checkbox"/> Recompletion         |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Fracture Treat          | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion     | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____             |   |

Approximate date work will start \_\_\_\_\_

### SUBSEQUENT REPORT (Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment *   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair   | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans   | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Conversion to Injection                                 | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat  | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <u>Swab &amp; Distillate Treatment</u> |   |

Date of work completion 4/8/94

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Swab formation, making 28 swab runs. Initial fluid level @7400'. Recovered 241 barrels oil and 76 barrels water. Treat formation with 75 barrels condensate with 20 gallons TL 201 and 20 gallons TH 767. Swab formation, initial fluid level after treatment 6700', final fluid level 6500'. Recovered 90 barrels of oil and 12 barrels water.

OCT 24

13. Name & Signature: DeForrest Smouse Title: President Date: 10/21/94

(This space for State use only)

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

RECEIVED  
MAR 7 1996

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator:

QUINEX ENERGY CORPORATION

3. Address and Telephone Number:

465 South 200 West, Bountiful, Utah 84010 (801) 292-3800

4. Location of Well

Footages: 876' FNL 669' FWL

QQ, Sec., T., R., M.: NW $\frac{1}{4}$ , NW $\frac{1}{4}$ , Section 30, T1S, R2E

5. Lease Designation and Serial Number:

14-20-H62-4065

6. If Indian, Allottee or Tribe Name:

Redcap

7. Unit Agreement Name:

8. Well Name and Number:

J.D.C. Redcap #30-4-1A

9. API Well Number:

43-047-31591

10. Field and Pool, or Wildcat:

Bluebell

County: Uintah

State: Utah

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

### NOTICE OF INTENT

(Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment             | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair           | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans         | <input type="checkbox"/> Recompletion         |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Fracture Treat          | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion     | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____             |   |

Approximate date work will start \_\_\_\_\_

### SUBSEQUENT REPORT

(Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment *                         | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair                         | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                       | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Conversion to Injection               | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat                        | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other Condensate Treatment |   |

Date of work completion \_\_\_\_\_

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

8/6/95 Swabbed well down, then hot oil treatment with 100 barrels of condensate.

13. Name & Signature: DeForrest Smouse Title: President

Date: 3/6/96

(This space for State use only)

tax credit  
3/1/96

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator: **QUINEX ENERGY CORPORATION**

3. Address and Telephone Number:  
**465 S. 200 W., Bountiful, Utah 84010 (801) 292-3800**

4. Location of Well  
Footages: **876' FNL, 669' FWL**

QQ, Sec., T., R., M.: **NW $\frac{1}{4}$ , NW $\frac{1}{4}$ , Sec. 30, T. 1 S., R. 2 E.**

5. Lease Designation and Serial Number:

**14-20-H62-4065**

6. If Indian, Allottee or Tribe Name:

**Redcap**

7. Unit Agreement Name:

8. Well Name and Number:

**JDC Redcap 30-4-1A**

9. API Well Number:

**43-047-31591**

10. Field and Pool, or Wildcat:

**BLUEBELL**

County: **UINTAH**

State: **UTAH**

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

### NOTICE OF INTENT (Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete           |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Perforate            |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____               |   |

Approximate date work will start \_\_\_\_\_

### SUBSEQUENT REPORT (Submit Original Form Only)

- |   |   |
|---|---|
| <input type="checkbox"/> Abandon *                          | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing                      | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                    | <input type="checkbox"/> Perforate            |
| <input type="checkbox"/> Convert to Injection               | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat or Acidize          | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <b>Treat well</b> |   |

Date of work completion **11/15/95**

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

**Pumped 100 bbls heated condensate down well bore to treat well & bore.**

**Placed back on pump.**

13.

Name & Signature: *Dr. Stuart Brown*

Title: **President**

Date: **5/29/96**

(This space for State use only)

*tax credit  
3/12/96*



STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: <b>14-20-H62-4065</b>
2. Name of Operator: <b>QUINEX ENERGY CORPORATION</b>	6. If Indian, Allottee or Tribe Name: <b>Redcap</b>
3. Address and Telephone Number: <b>465 S. 200 W., Bountiful, Utah 84010</b>	7. Unit Agreement Name:
4. Location of Well Footages: <b>876' FNL, 669' FWL</b>	8. Well Name and Number: <b>JDC Redcap 30-4-1A</b>
QQ, Sec., T., R., M.: <b>NW<sup>1</sup>/<sub>4</sub>, NW<sup>1</sup>/<sub>4</sub>, Sec. <sup>30</sup>20, T1S, R2E, USM</b>	9. API Well Number: <b>43-047-31591</b>
	10. Field and Pool, or Wildcat: <b>BLUEBELL</b>
	County: <b>UINTAH</b>
	State: <b>UTAH</b>

## CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other _____	<input type="checkbox"/> Abandon * <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input checked="" type="checkbox"/> Other <u>Treat well</u>
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start _____	Date of work completion <u>15 Sept. 1996</u>
	Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.
	* Must be accompanied by a cement verification report.


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Sep. 13-15, 1996. Swabbed well down. Pulled Standing valve & ran blanking sleeve. Swab well till equalized. Pumped 100 bbl. Condensate.

13. Name & Signature: Dr. Fred Shunse Title: President Date: 8/13/97

(This space for State use only)

WO fax credit denied - 9/97.



STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER:		5. Lease Designation and Serial Number: <b>14-20-H62-4065</b>
2. Name of Operator: <b>QUINEX ENERGY CORPORATION</b>		6. If Indian, Allottee or Tribe Name: <b>REDCAP</b>
3. Address and Telephone Number: <b>465 South 200 West, Bountiful, UT. 292-3800</b>		7. Unit Agreement Name:
4. Location of Well Footages: <b>876' FNL. 669' FWL</b> NW, NW, Section 30, T1S, R2E		8. Well Name and Number: <b>JDC Redcap 30-4-1A</b>
9. API Well Number: <b>43-047-31591</b>		10. Field and Pool, or Wildcat: <b>43-047-31591</b>
County: <b>Uintah</b> State: <b>Utah</b>		

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

**NOTICE OF INTENT**  
(Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete           |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____               |   |

Approximate date work will start \_\_\_\_\_

**SUBSEQUENT REPORT**  
(Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing   | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans   | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Convert to Injection                                    | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat or Acidize                               | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <u>Swab down, Cond. chem treatment</u> |   |


Date of work completion 9 Sept. 1997

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Tried to pull pump. Would not come. Swab well down and pulled pump with sand line. Pull standing valve and ran blanking sleeve. Pumped 100 barrels of condensate with paraffin solvent. Replaced standing valve. Hot oil well.



13.

Name & Signature: DeForrest Smouse

DeForrest Smouse Title: President

Date: 1/9/98

(This space for State use only)

FORM 9

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

5. Lease Designation and Serial Number:

14-20-H62-4065

6. If Indian, Aborigine or Tribe Name:

Redcap

7. Unit Agreement Name:

J.D.C. Redcap

8. Well Name and Number:

JDC Redcap 30-4-1A

9. API Well Number:

43-047-31591

10. Field and Pool, or Wildcat:

BLUEBELL.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator:

QUINEX ENERGY CORPORATION

3. Address and Telephone Number:

801 - 292- 3800  
465 S. 200 W. Suite 300, Bountiful, Utah 84010

4. Location of Well:

Footages: 876' FNL, 669' FWL

County: Uintah

CO. Sec., T., R., M.: Section 30, T1S, R2E, USBM

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT  
(Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete           |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other                     |   |

Approximate date work will start 3/2/98

SUBSEQUENT REPORT  
(Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other          | Hot oil, replace pump                         |

Date of work completion March 5, 1998

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Tried to pull pump, would not pull due to dehydrated paraffin in tubing. Swab well for 4 days, then pumped 200 bbls. condensated to remove paraffin from tubing & casing. Ran new pump, and placed well back on production.

*Red*  
12-28-98

13.

Name &amp; Signature: DeForrest Smouse

Title: President

Date: 6-15-98

(This space for State use only)

WTC  
12-28-98  
RSH

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator: QUINEX ENERGY CORPORATION

3. Address and Telephone Number: 801 - 292- 3800  
465 S. 200 W. Suite 300, Bountiful, Utah 84010

4. Location of Well  
Footages: 876' FNL, 669' FWL

QQ, Sec., T., R., M.: Section 30, T1S, R2E, USBM

5. Lease Designation and Serial Number:

14-20-H62-4065

6. If Indian, Allottee or Tribe Name:

Redcap

7. Unit Agreement Name:

J.D.C. Redcap

8. Well Name and Number:

JDC Redcap 30-4-1A

9. API Well Number:

43-047-31591

10. Field and Pool, or Wildcat:

BLUEBELL.

County: Uintah

State: Utah

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

### NOTICE OF INTENT (Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandon                   | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing             | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans           | <input type="checkbox"/> Recomplete           |
| <input type="checkbox"/> Convert to Injection      | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion       | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____               |   |

Approximate date work will start \_\_\_\_\_

### SUBSEQUENT REPORT (Submit Original Form Only)

- |   |   |
|---|---|
| <input type="checkbox"/> Abandon *                                      | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Repair Casing                                  | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                                | <input type="checkbox"/> Reperforate          |
| <input type="checkbox"/> Convert to Injection                           | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat or Acidize                      | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <u>Hot oil, replace pump.</u> |   |


Date of work completion March 2, 1998

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Tried to pull pump, would not pull due to dehydrated paraffin in tubing. Swab well for 4 days, then pumped 200 bbls. condensated to remove paraffin from tubing & casing. Ran new pump, and placed well back on production.



13.

Name & Signature: DeForrest Smouse

Title: President

Date: 6-15-98

(This space for State use only)

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator:

**QUINEX ENERGY CORPORATION**

3. Address and Telephone Number:

**292-3800**

**465 S. 200 W., Suite 300, Bountiful, Utah 84010**

4. Location of Well

Footages: **876' FNL, 669' FWL**

QQ, Sec., T., R., M.: **Sec. 30, T. 1 S, R. 2 E., USM**

5. Lease Designation and Serial Number:

**14-20-H62-4063**

6. If Indian, Allottee or Tribe Name:

**REDCAP**

7. Unit Agreement Name:

**J.D.C. Redcap**

8. Well Name and Number:

**30-4-A1**

9. API Well Number:

**43-047-31591**

10. Field and Pool, or Wildcat:

**BLUEBELL**

County: **Uintah**

State: **Utah**

### 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

#### NOTICE OF INTENT

(Submit in Duplicate)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment             | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair           | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans         | <input type="checkbox"/> Recompletion         |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Fracture Treat          | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion     | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other _____             |   |

Approximate date work will start **16 February 1999**

#### SUBSEQUENT REPORT

(Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment *                                       | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair                                       | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                                     | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Conversion to Injection                             | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat                                      | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other <u><b>acid wash &amp; replace tubing.</b></u> |   |

Date of work completion **28 February 1999**

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Washed tubing w/acid to remove excessive scale. Ran Dummy pump to find hole in tubing. Dummy pump parted while trying to retrieve on wireline. Reverse pump and pumped dummy pump out of hole. Cut off tubing between packer & pump cavity when unable to release packer. Picked up overshot & jars to retrieve packer. Unable to release packer & overshot stuck in hole. Cut tubing off above workover shoe. Picked up 10 drill collars, new jars & overshot to try and release packer. Jarred on packer until jars wore out. Could not move packer. Ran shot string on wireline to release overshot & work string from fish. Shot string 4 times to release. Backed off at packer. Packer still in hole. Ran casing scraper through 5½" 7 7 5/8" to remove scale. Ran new 5½" Model R-dounle grip packe & set same @ 11,990'. Place well back on pump.

13.

Name & Signature:

*DeForrest Smouse*

**DeForrest Smouse**

Title:

**President**

Date:

**3/2/99**

(This space for State use only)

RECEIVED

MAR 04 1999

**RECEIVED**  
FORM 9  
**AUG 11 1999**  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: <b>14-20-H62-4063</b>
2. Name of Operator: <b>QUINEX ENERGY CORPORATION</b>	6. If Indian, Allottee or Tribe Name: <b>REDCAP</b>
3. Address and Telephone Number: <b>465 S. 200 W., Suite 300, Bountiful, Utah 84010</b>	7. Unit Agreement Name: <b>J.D.C. Redcap</b>
4. Location of Well Footages: <b>876' FNL, 669' FWL</b> QQ, Sec., T., R., M.: <b>Sec. 30, T. 1 S, R. 2 E., USM</b>	8. Well Name and Number: <b>30-4-A1</b>
	9. API Well Number: <b>43-047-31591</b>
	10. Field and Pool, or Wildcat: <b>BLUEBELL</b>

County: **Uintah**  
State: **Utah**

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandonment <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other _____	<input type="checkbox"/> Abandonment <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Other <u>acid wash &amp; replace tubing.</u>
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recompletion <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start <u>16 February 1999</u>	Date of work completion <u>28 February 1999</u> Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form. * Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Washed tubing w/acid to remove excessive scale. Ran Dummy pump to find hole in tubing. Dummy pump parted while trying to retrieve on wireline. Reverse pump and pumped dummy pump out of hole. Cut off tubing between packer & pump cavity when unable to release packer. Picked up overshot & jars to retrieve packer. Unable to release packer & overshot stuck in hole. Cut tubing off above workover shoe. Picked up 10 drill collars, new jars & overshot to try and release packer. Jarred on packer until jars wore out. Could not move packer. Ran shot string on wireline to release overshot & work string from fish. Shot string 4 times to release. Backed off at packer. Packer still in hole. Ran casing scraper through 5 1/2" 7 7 5/8" to remove scale. Ran new 5 1/2" Model R-dounle grip packe & set same @ 11,990'. Place well back on pump.

13. Name & Signature: DeForrest Smouse Title: President Date: 3/2/99

(This space for State use only)

*WTC denied 4-1-99. 90 day-rule RSE.*

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>FEE</b>
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>FEE</b>
1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME: <b>FEE</b>
2. NAME OF OPERATOR: <b>QUINEX ENERGY CORPORATION</b>		8. WELL NAME and NUMBER: <b>J.D.C. Redcap 30-4-1A</b>
3. ADDRESS OF OPERATOR: <b>465 SOUTH 200 WEST BOUNTIFUL UT 84010</b>		9. API NUMBER: <b>43-047-31591</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>876' FNL, 669' FWL, Section 30, T 1 S, R 2 E, USBM</b>		10. FIELD AND POOL, OR WILDCAT: <b>BLUEBELL</b>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NWNW 30 1S 2E</b>		COUNTY: <b>UINTAH</b>  STATE: <b>UTAH</b>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: _____  <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: <b>2-22-07</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The 7 5/8" casing parted at 4,780 ' allowing drilling mud into the hole and wrecking the integrity of the well. Quinex Energy entered with a drill to open the casing allowing the casing to be swedged out. The drill bit commenced to stick in the hole so Quinex decided to mill out the bad spot. The mill deviated outside the casing. Quinex Energy then proceeded to try to pull the casing. The casing was shot off just above the bad zone. We were unable to pull the 7 5/8" casing with up to 100K tension. Quinex Energy then proceeded to wash over the casing and cut it off in units of about 100'. The weather dropped to 15 degrees below zero, and operations were suspended until better weather would allow full day operations.

NAME (PLEASE PRINT) <b>DEFORREST SMOUSE</b>	TITLE <b>PRESIDENT</b>
SIGNATURE	DATE <b>4/9/2007</b>

(This space for State use only)

**RECEIVED**

**APR 10 2007**

DIV. OF OIL, GAS & MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL      OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>FEE</b>
2. NAME OF OPERATOR: <b>QUINEX ENERGY CORPORATION</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <b>FEE</b>
3. ADDRESS OF OPERATOR: <b>465 S 200 W</b> CITY <b>BOUNTIFUL</b> STATE <b>U</b> ZIP <b>84010</b>		7. UNIT or CA AGREEMENT NAME: <b>FEE</b>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>876' FNL, 669' FWL , SECTION 30, T 1 S, R 2 E, USBM</b>		8. WELL NAME and NUMBER: <b>JDC REDCAP 30-4-1A</b>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NWNW 30 1S 2E</b>		9. API NUMBER: <b>047-31591</b>
COUNTY: <b>UINTAH</b>		10. FIELD AND POOL, OR WILDCAT: <b>BLUEBELL</b>
STATE: <b>UTAH</b>		

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: <u>10/12/2006</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: <u>11/30/2007</u>	<input checked="" type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.**

10/04/2007 Continued workover, attempting to mill out tubing and clean hole for recovery of tubing fish, and repair casing. Built mud to facilitate circulation out formation and milled metal shavings. Cut and pulled 7 5/8" casing and got only 4 joints, because casing parted. Speared casing and ran three point to find free-point. Tight spot was at the base of the 10 3/4" surface casing @ 1,500'. Ran logging tool down hole to 3 joints below Bowen Patch. The 7 5/8" casing appeared to be in good shape. Ran in with a 6 3/4" watermelon mill & started milling on tight spot @ 4,790'. Change over to 5 1/2" bull-nose mill and started milling @ 4898'. Milled down from 4989' to 4950' getting formation and metal shavings. Ran Impression Block which showed the casing 2" of center. Tried to pull 7 5/8" casing but it would not move at 30K tension. Found the tite spot @ base of 10 3/4" surface casing. Cut of the 7 5/8" casing at 1,439' & pulled 1431' 7 5/8" casing and laid it down. Milled out lip at base of 10 3/4" casing. Milled out tight hole and caught 7 5/8" casing fish and pulled same down to cut. Was able to mill down to 6900' inside of tubing then mill fell through to 7732'. Swiveled 1 1/4" drill pipe to 9,400'. Ran in tubing with a 1 3/8" spud bar, stacked out @ 9,500', and spudded through bridge & tool went down to 11,680'. Picked up a 1 7/8" chemical cutter. Cut off tubing @ 11,500', with 120K strain on tubing. Tension dropped to 90K. Pulled 6500' of 2 7/8" tubing, leaving 480' tubing and packer in hole. Milled from 5144' to 5165' with 5 3/4" mill & 6 5/8" string mill. Continued milling on casing with formation, rock and metal shaving returns. Milled down to 7450'. Milled down with washover pipe to 4,870'. The weather ddropped to below 0 degrees F & decision was made to stop workover operation until weather moderated allowing full day workover operation.

NAME (PLEASE PRINT) <u>DeForrest Smouse PhD</u>	TITLE <u>President, Quinex Energy Corp.</u>
SIGNATURE <u><i>DeForrest Smouse</i></u>	DATE <u>12/10/2007</u>

(This space for State use only)

**RECEIVED**

**DEC 11 2007**



**From:** "Mike Hebertson" <mike@quinexenergy.com>  
**To:** <CAROLDANIELS@UTAH.GOV>  
**Date:** 8/20/2008 4:03 PM  
**Subject:** Well Information Changes  
**Attachments:** Wells Stat Sheet.xls

The attached spreadsheet contains corrections to Quinex wells that will help update your files

43 047 31591  
Redcap 30-4-2E  
1S 2E 30

RECEIVED

AUG 20 2008

DIV. OF OIL, GAS & MINING

# QUINEX ENERGY CORP

API Well Number	Well Name	County	Qtr/Qtr	Sec	T-R	Ft. NS	NS	Ft. EW	EW	Well Status	Well Type
43-047-31889	ALLRED 2-32A1E	Uintah	SESW	32	1S-1E	660	S	1521	W	POW	Oil Well
43-047-31713	BOWEN-BASTIAN 1-14A1	Uintah	SESW	14	1S-1W	398	S	2030	W	POW	Oil Well
43-013-32162	BRITTANY 4-12A3	Duchesne	C-NE	12	1S-3W	1320	N	1320	E	POW	Oil Well
43-047-31695	CHASEL-SPROUSE 1-18A1E	Uintah	SWNW	18	1S-1E	1516	N	804	W	POW	Oil Well
43-047-31711	CMS 1-13A1	Uintah	NENW	13	1S-1W	1300	N	1530	W	POW	Oil Well
43-047-39983	D.C. FED 1-11	Uintah	NENE	11	11S-20E	839	N	650	E	Permit	Gas Well
43-047-39982	D.C. FED 2-11	Uintah	NENE	11	11S-20E	829	N	621	E	Permit	Gas Well
43-013-32149	DAVID 3-7B2	Duchesne	NWSE	7	2S-2W	1547	S	1749	E	POW	Oil Well
43-047-31874	DEEP CREEK 2-19A2E	Uintah	NWSW	19	1S-2E	2421	S	980	W	POW	Oil Well
43-013-32787	DS FED 3-23	Duchesne	NWSW	23	9S-17E	1986	N	612	W	SI	Oil Well
43-047-39196	HELEN FED 1-26	Uintah	SWNW	26	9S-17E	1367	N	721	W	New Permit	Oil Well
43-047-39195	JANS FED 1-25	Uintah	NWNW	25	9S-17E	660	N	660	W	Permit	Oil Well
43-013-32789	JDC FED 4-23	Duchesne	SWSW	23	9S-17E	600	S	661	W	SI	Oil Well
43-013-31248	JODIE 3-36A3	Duchesne	NWNE	36	1S-3W	752	N	1662	E	POW	Oil Well
43-013-32786	JODIE FED 1-23	Duchesne	NWNW	23	9S-17E	563	N	832	W	POW	Oil Well
43-047-39198	JOELYN FED 1-27	Uintah	CNNW	27	9S-17E	660	N	1320	W	New Permit	Oil Well
43-013-31216	JOHN 2-7B2	Duchesne	NWNW	7	2S-2W	484	N	671	W	POW	Oil Well
43-013-31882	JOHN CHASEL 3-6A2	Duchesne	SWSE	6	1S-2W	660	S	1400	E	SI	Oil Well
43-013-33617	JSW FED 2-26	Duchesne	NWNW	26	9S-17E	660	N	660	W	POW	Oil Well
43-013-33618	JW FED 2-27	Duchesne	NENE	27	9S-17E	656	N	705	E	Permit	Oil Well
43-047-31828	LESLIE TAYLOR 24-5	Uintah	SWNW	24	1S-1W	2450	N	1260	W	POW	Oil Well
43-013-32788	LFW FED 2-23	Duchesne	SWNW	23	9S-17E	1980	N	661	W	POW	Oil Well
43-047-31714	MALNAR-PIKE 1-17A1E	Uintah	SWSW	17	1S-1E	660	S	660	W	POW	Oil Well
43-013-31247	MERLENE 2-36A3	Duchesne	SESE	36	1S-3W	1040	S	1100	E	SI	Oil Well
43-047-31390	MICHELLE UTE 7-1	Uintah	NESW	7	1S-1E	1539	S	2439	W	POW	Oil Well
43-013-30381	UTE TRBL 11-6A2	Duchesne	SENW	6	1S-2W	2227	N	1561	W	POW	Oil Well
43-047-31591	REDCAP J D C 30-4-1A	Uintah	NWNW	30	1S-2E	876	N	669	W	SI	Oil Well
43-047-31653	SAM HOUSTON 24-4	Uintah	NWSE	24	1S-1W	1350	S	1400	E	POW	Oil Well
43-013-32129	SASHA 4-6A2	Duchesne	SWSW	6	1S-2W	660	S	660	W	SI	Oil Well
43-047-31940	EINERSON 1-4B1E	Uintah	SWSW	4	2S-1E	1056	S	795	W	POW	Oil Well
43-013-32131	TRISTAN 5-6A2	Duchesne	NWNW	6	1S-2W	660	N	660	W	POW	Oil Well
43-047-30127	UINTAH-SAM 28-2R	Uintah	NESW	28	1N-1E	2111	S	1847	W	POW	Oil Well
43-013-30042	UTE TRIBAL U 2-12A3	Duchesne	SWSW	12	1S-3W	1322	S	1325	W	SI	Oil Well
43-047-33179	WADE COOK 2-14A1	Uintah	NWNW	14	1S-1W	705	N	662	W	POW	Oil Well
43-047-31845	MARY R. U. 278	Uintah	NWSE	13	1S-1W	1971	S	2072	E	POW	Oil Well

RECEIVED

AUG 20 2008

DIV. OF OIL, GAS & MINING

Field Name	Surface	Mineral	UTM E	UTM N	Elev. GR	Elev. KB	TD	PBTD	
BLUEBELL	Fee	Fee	592565	4466702	5362	5383	12750	12743	
BLUEBELL	Fee	Fee	587831	4471387	5610	5634	14055	13982	
BLUEBELL	Indian	Indian	570808	4473805	6532	6553	15790	15782	
BLUEBELL	Fee	Fee	590665	4472468	5571	5595	14300	14300	
BLUEBELL	Fee	Fee	589279	4472503	5608	5622	14200	14161	
HILL CREEK	Federal	Federal	616404	4415106	5095				
HILL CREEK	Federal	Federal	616412	4415109	5087				
BLUEBELL	Fee	Fee	572323	4463431	5848	5869	13527	13523	
BLUEBELL	Fee	Fee	600377	4470560	5392	5418	13900	13859	
MONUMENT BUTTE	Federal	Federal	587015	4429669	5224	5238	5800	5280	
UNDESIGNATED	Federal	Federal	587054	4428648	5290				
8 MILE FLAT NORTH	Federal	Federal	588644	4428882	5290				
MONUMENT BUTTE	Federal	Federal	587029	4429265	5260	5272	5700	5700	
BLUEBELL	Indian	Indian	570762	4467531	6302	6324	14145	14019	
MONUMENT BUTTE	Federal	Federal	587065	4430504	5192	5204	6001	5967	
UNDESIGNATED	Federal	Federal	585635	4428865	5312				
BLUEBELL	Indian	Indian	571502	4464416	5922	5943	14030	13994	
BLUEBELL	Indian	Indian	572320	4474433	6455	5477	15878	15877	
UNDESIGNATED	Federal	Federal	587033	4428863	5280	5298	5607	5606	
UNDESIGNATED	Federal	Federal	586617	4428863	5282				
BLUEBELL	Fee	Fee	589220	4470543	5497	5518	14022	13990	
MONUMENT BUTTE	Federal	Federal	587019	4430071	5226	5242	5655	5419	
BLUEBELL	Fee	Fee	592230	4471526	5502	5523	14403	13470	
BLUEBELL	Indian	Indian	570933	4466471	6259	6280	13860	13860	
BLUEBELL	Indian	Indian	591145	4473399	5617	5643	14711	14638	
BLUEBELL	Indian	Indian	571672	4475277	6639	6663	16800	13780	
BLUEBELL	Indian	Indian	600302	4469555	5344	5369	13550	13510	
BLUEBELL	Fee	Fee	590012	4470087	5460	5483	13865	13826	
BLUEBELL	Indian	Indian	571441	4474432	6533	6554	15830	15828	
BLUEBELL	Fee	Fee	593962	4465212	5274	5293	12833	12804	
BLUEBELL	Indian	Indian	571397	4475754	6646	6657	16782	16747	
ROBIDOUX	Indian	Indian	594136	4478438	5892	5917	16000	15345	
BLUEBELL	Indian	Indian	570014	4473004	6467	6483	15700	15693	
BLUEBELL	Fee	Fee	587414	4472656	5699	5720	14212	14150	
BLUEBELL	Indian	Indian	589788	4471891	5555	5576	16998	13914	

RECEIVED

AUG 20 2008

DIV OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: 40-20-H62-4065
2. NAME OF OPERATOR: QUINEX ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Allottee
3. ADDRESS OF OPERATOR: 465 South 200 West CITY: Bountiful STATE: U ZIP: 84010		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 876 FWT, 669 FWT QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NW 30 1S 2E USM Per Mike Hoverson		8. WELL NAME and NUMBER: Redcap JDC 30-4-1A
PHONE NUMBER: (801) 292-3800		9. API NUMBER: 047-31591
10. FIELD AND POOL, OR WILDCAT: BLUEBELL		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 8/18/2008	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input checked="" type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Quinex Energy has moved a Workover Rig and Crew onto the Redcap 30-4 well and is rigging up. We are to planning continue the workover, milling out and cutting of the 7 5/8" casing. The well was milled out to 7450' with a 6 5/8" mill and then milled over the 7 5/8" casing with a Washover Pipe to 4,870'. The operations were suspended due to extreme low temperatures (- 0 degrees F) because we were getting only a short time of actual work, the remainder time was in thawing out the mud and getting the rig started. The rig was moved off on December 10, 2007, and the well shut in until temperatures moderated.

Quinex Energy Corporation moved a Workover Rig on to the location on August 18, 2008 and it is now being rigged up. We plan to continue the previous workover plans.

COPY SENT TO OPERATOR

Date: 9.17.2008

Initials: KS

NAME (PLEASE PRINT) DeForrest Smouse	TITLE President, Quinex Energy Corp.
SIGNATURE <i>DeForrest Smouse</i>	DATE 8/19/2008

(This space for State use only)

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Date: 9/4/08

By: *[Signature]*

(See Instructions on Reverse Side)

Federal Approval Of This  
Action Is Necessary

RECEIVED

AUG 21 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-4065
2. NAME OF OPERATOR: QUINEX ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE ALLOTTEE
3. ADDRESS OF OPERATOR: 465 South 200 West CITY BOUNTIFUL STATE UT ZIP 84010		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (801) 292-3800		8. WELL NAME and NUMBER: Redcap JDC 30-4-1A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 876' FNL, 669' FWL Section 30, T 1 S, R 2 E, USBM		9. API NUMBER: 047-31591
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 30 1S 2E		10. FIELD AND POOL, OR WILDCAT: BLUEBELL
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input checked="" type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please find attached Work-over of the JDC Redcap 30-4 well attempting to tie back to surface with a 5 1/2" casing from the top of the top of the 5 1/2" liner hanger. Workover on the well began during the fall of 2007. The 7 5/8" casing collapsed and parted. There is sands in the well containing very corrosive water that corrodes and pits iron casing and tubing.

NAME (PLEASE PRINT) DeForrest Smouse PhD	TITLE President Quinex Energy Corporation
SIGNATURE <i>DeForrest Smouse</i>	DATE 8/20/2008

(This space for State use only)

RECEIVED

AUG 25 2008

DIV. OF OIL, GAS & MINING

2 feet then mill slowly down. Tripped out and the mill was worn out, and the mill was also cored out in center. Picked up and ran a new 6 3/4" tapered mill with a 12 foot sub. Milled down and when it slowed down and it's appeared that the mill was inside the 7 5/8" casing. Rigged down 6 days waiting for new rig parts. Picked up a 4 3/4" bit and tripped down to the top of the fish @ 4816'. Drilled down to 4824' the it slowed down, hard drilling. Pulled the bit and it looked OK, but sub and collars showed wear. Picked up a 5 1/2" flat mill and tripped in hole. Circulated out fill that contained considerable iron shavings at 4824'. Milled down to 4842'. Tripped string up inside surface casing. Finished pulling string and mill was worn and cored out. Picked up a new 4 3/4" bladed mill and tripped in the hole. Milled down to 4883.5' & mill stopped. Pulled mill which was worn and cored out. Picked up a new 5" muncher mill and tripped in hole and caught fish @ 4882'. Milled very hard down to 4890'. While tripping out hung up @ 4820'. Tripped back in hole & tagged and milled down to 4856' and mill plugged off. Tripped it out and found several pieces of casing stuck in mill. Tripped back in hole with a new aggressive flat bottomed mill. Circulated, it was very ratt for 8 feet then found no problem down to 4996'. Tagged some fill. Milled down to 6390' getting back sand, rock and formation. Tripped out and put on impression block, and tripped in hole and stacked out @ 4898'. When pulled the block showed a 1/2 circle impression. Picked up a 5" tapered mill, a 8 foot sub and a 5 1/8" mill. Tagged fish @ 4845'. Milled down to 5000'.

9/1-30/2007 Picked up 1 joint and tagged @ 7177' then circulated the hole. Milled down to 7450' getting back sand, formation and iron shavings. Last foot had some rocks but started to torque up. Circulated hole clean, laid down 1 joint & drained pump & lines. Picked up 1 joint & tagged @ 7450'. Circulated down to 7787' getting back rocks, sand and formation. Cleaned out hole, pulled 1 joint. From this time drained pump and lines every day after operations. Picked up 1 joint and tagged @ 8595'. Circulated hole getting back rocks, sand and formation. Samples contained some hard paraffin. Picked up 1 joint & milled down to 8877' getting back rocks, sand and formation. Pulled 42 joints and laid down. Picked up 22 stands out of derrick. Picked up 1 joint & tagged @ 9910'. Milled down to 10140' & tagged top of 5 1/2" casing. Tripped out hanging up @ 4890' and had to pull 35K over up to 4790' then pulled free. Laid down tapered mill, sub and jars. The bottom of mill was worn off, the bumper sub was washed out with a hole in its side. Picked up wash over pipe & 7 joints of 2 7/8" tubing. Weld together and with 5 5/8" tapered mill on bottom. Tripped in hole and stacked out @ 4800'. Tried to work mill into casing making 5 feet of hole. Felt we were outside of casing. Tripped out and cut off welded units & broke off 5 5/8" mill. Welled together with a 2 7/8" mule shoe on bottom. Picked up a 6 1/2" string mill, jars, bumper sub and ran in hole. Tagged and started milling. Made it down to 4847' with string mill. Hard drilling, mule shoe @ 5100'. Circulated hole clean. Ran back down and started milling down to 4829' then pulled & inspected mule shoe. Picked up a 2 7/8" mule shoe bumper sub and jars and tagged @ 4,900'. Swiveled down to 4936' and stopped. Tripped out and picked up a 5' concave mill, bumper sup, jars and collars, then tripped in hole to 4840'. Circulated tubing clean getting back sand, formation with some iron shavings and small rocks. Swiveled down to 4932' getting back formation with some iron shavings. Circulated tubing clean and pulled out of hole.. Rig down to get additional equipment.

10/4-31/2007 Moved in equipment and blew through 1 1/4" drill pipe. Picked up 25 joints of 1 1/4" drill pipe with a 2 7/8", and then 2 7/8" tubing. String plugged off with scale & rust. Cleaned out and tripped in circulating every 25 joints. Trip through 2 7/8" tubing then started milling through plug in 2 7/8" tubing in hole @ 5000'. Milled down to 6000'. Went through plug easily. Returns came back clean from 5500-6000'. Tripped out & laid down 1 1/4" drill pipe. Ran in hole with wire line and spud bar to 6038', where it stacked out. Spudded down 2 feet then pulled wire line. Picked up 185 joints of 1 1/4" drill pipe. Ran in hole to 5800' where it stacked out on paraffin and formation. Milled through paraffin from 7732'. Rigged up hot oiler and circulated hole clean down to 9400' Pulled 1 14" drill string an went in hole. Rigged up wire line and tripped in hole to 9500' where it stacked out. Spudded through bridge an tool went down to 11,680'. Pulled out then went in hole with chemical cutter to cut 2 7/8" tubing at 11,500'. Took 120K tension on tubing and tension dropped to 90K when cut was completed. Tripped 2 7/8: tubing

out strapping. Left 480' of 2 7/8" tubing in hole. Mixed good mud and went in hole with 150 joints of 2 7/8" tubing with string mill then 1 joint of 2 7/8". Hauled in 120 bbls. of 12.6# mud. Tripped in hole to 4700' and mixed mud and circulated hole clean. Tripped in to 4700' while circulating hole clean. and while swiveling pipe. Swiveled down to 4890' slowly to prevent breaking off large chunks of 7 5/8" of badly pitted casing. Circulated hole clean. Tripped out and string stacked out with 15K over string weight. Worked string and had to pull 30K over to pull free. Tripped down into 7 5/8" casing with a 5 1/4" mill and a 6 5/8" string mill. Tagged up @ 5144' then milled down to 5165'. Milled hard to 5240' then fell free to 5351'. Swivel down 10 joints and tripped out of hole. Laid down tools. Picked up a Wetherford mill and cutter to dress off casing top. Tripped in hole and had hard time getting inside 7 5/8" casing. Tripped down to 5916', then circulated for 90 min. and got back rock, sand, metal shaving and junk. Circulated down to 5838'. Worked to clean out casing. Got down to 6100' and picked up string. Tripped back down and tagged @ 6,048'. Circulated hole and swiveled down 60' easily. Started to pressure up. Picked off bottom & circulated hole clean. Swivel down to 6158' and slowed down. Picked up and circulated out 1 1/2" rocks and chunks of cement. Lost 50 bbls of mud. Pulled out and laid down tools. Picked up 6 1/2" bit, bumper sub & jars and ran back in hole. Tagged at 6987'. Circulated hole & milled down to 7177' getting back rocks, sand & formation. Pulled up 1 joint & circulated hole clean.

11/01-30/2007 Tagged @ 7177' and milled down to 7450' getting rocks, sand & formation. Milled to 7787' and circulated hole clean. Milled down to 8877'. Has hard paraffin from 8688' to 8775'. Pulled out and laid down tools. Tools had a ring worn in it just above cut right. Picked up a mule shoe and tripped in hole to 4750'. Circulated hole clean. Pulled & laid down mule shoe, then picked up 9 7/8" washover pipe, jars, bumper sub and collars. Freezing all day. Ran in hole to 2200' and stacked out. Drilled down 60 feet then fell through. Fell 120 feet and stacked out, then drilled 60 feet and fell through, stacked out and drilled 10 feet and fell through. Fell 23 stands and stacked out, then drilled 60 feet and fell free. Pulled up into surface pipe. Ran back and tagged @ 4803'. Started milling. Milled on top of casing for 30 min. then washover pipe fell down to 4870'. Tripped out and laid down work string, washover pipe an equipment. Decision was made to rig down and start again when weather conditions were better. Freezing temperatures made actual operations less than 1/3 day, but workover charges were for full day

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.**

5. Lease Serial No.  
14-20-H62-4065

6. If Indian, Allottee or Tribe Name  
UTE

**SUBMIT IN TRIPLICATE** – Other instructions on page 2.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Quinex Energy Corporation

3a. Address

465 South 200 West Bountiful Utah, 84010

3b. Phone No. (include area code)

801-292-3800

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NWNW, SEC. 30, T1S, R2E, 876' FNL 669' FWL

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

REDCAP J.D.C. 30-4-1A

9. API Well No.

43-047-31591

10. Field and Pool or Exploratory Area

ALTAMONT/BLUEBELL

11. Country or Parish, State

UINTAH

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Change Name</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)


Quinex Energy proposes to change the name Redcap JDC 30-4-1A to Redcap 30-4A2E

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

DeForrest Smouse

Title President Quinex Energy Corporation

Signature



Date 09/11/2008

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

SEP 15 2008

DIV. OF OIL, GAS & MINING



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.**

5. Lease Serial No.  
14-20-H62-4065

6. If Indian, Allottee or Tribe Name  
UTE

**SUBMIT IN TRIPLICATE** - Other instructions on page 2.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Quinex Energy Corporation

3a. Address

465 South 200 West Bountiful Utah, 84010

3b. Phone No. (include area code)

801-292-3800

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NNW, SEC. 30, T1S, R2E, 876' FNL 669' FWL

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

REDCAP J-B.C. 30-4-1A 30-4A2E OK

9. API Well No.

43-047-31591

10. Field and Pool or Exploratory Area

ALTAMONT/BLUEBELL

11. Country or Parish, State

UINTAH

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input checked="" type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input checked="" type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Quinex Energy is planing to run 10,178' of 5 1/2" N80 casing from the Liner Top to surface and cement same as follows:

Lead cement 785 sks Hi Fill 11.0 lb/gal.

16% Gel Yield 3.82 Ft3 /sk

10 lb/sk Gilsonite 23.0 gal/sk

3 lb/sk GR-3

3% salt

1/4 lb Flocele

Tail cement 425 sks 50/50 POZ

2% gel

1.31 Ft3 /sk

10% Dalt B W O W

0.2% CFL-115

0.1% CR 180

1/4LB/SK Flocele

COPY SENT TO OPERATOR

Date: 11.16.2008

Initials: KS

RECEIVED

SEP 30 2008

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Federal Approval Of This  
Action Is Necessary

DIV. OF OIL, GAS & MINING

Date: 11/4/08

By: [Signature]

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

DeForrest Smouse PhD

Title President Quinex Energy Corporation

Signature

[Signature]

Date

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.**

5. Lease Serial No.  
14-20-H62-4065  
6. If Indian, Allottee or Tribe Name  
UTE

**SUBMIT IN TRIPLICATE – Other instructions on page 2.**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Quinex Energy Corporation

3a. Address

465 South 200 West Bountiful Utah, 84010

3b. Phone No. (include area code)

801-292-3800

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NWNW, SEC. 30, T1S, R2E, 876' FNL 689' FWL

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

REDCAP ~~1-D.C.~~ 30-4-1A <sup>2A</sup>

9. API Well No.

43-047-31591

10. Field and Pool or Exploratory Area

ALTAMONT/BLUEBELL

11. Country or Parish, State

UINTAH

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input checked="" type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Cement of 5 1/2" casing.
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

9/28 -10/01/2008 Polished of top of 5 1/2" liner. Picked up 151 JTS, 5 1/2" 17lb/ft N80 casing and 106 JTS J55 17lb/ft and ran in hole to 10,178' (Top of Liner Hanger). Circulated well clean.


10/01/2008 Finished running casing and Cemented same from liner top up to surface with 1210 sacks cement as approved on previous Sundry. Had indication of cement to surface. Landed casing in slips with 20K to 50K on liner. Tested Tieback seat with 2,550 lbs to test seal integrity. Held for 5 minutes. Pulled up leaving 20K lbs on liner seat flowed back 2 BBLS waited 10 minutes pressured to 2,550 lbs no leak off, left pressure on the plug and set the casing in the slips.

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

DeForrest Smouse

Title President, Quinex Energy Corporation

Signature



Date 10/02/2008

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

OCT 06 2008

DIV. OF OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.**

5. Lease Serial No.  
14-20-H62-4065

6. If Indian, Allottee or Tribe Name  
UTE

**SUBMIT IN TRIPLICATE** – Other instructions on page 2.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Quinex Energy Corporation

3a. Address

465 South 200 West Bountiful Utah, 84010

3b. Phone No. (include area code)

801-292-3800

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NWNW, SEC. 30, T1S, R2E, 876' FNL 669' FWL

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

REDCAP J.D.E. 30-41A

9. API Well No.

43-047-31591

10. Field and Pool or Exploratory Area

ALTAMONT/BLUEBELL

11. Country or Parish, State

UINTAH

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

10/06-11/2008 Quinex Energy Ran a Cement Bond Log without pressure & with pressure on back side.

10/12-19/Drilled out cement and fill down to 13,282' getting back formation, sand & cement. Picked up a 5 1/2" Model R3 Packer, pump cavity & 6' pup joint Hydro testing tubing on trip in hole. . Packer would not go through liner top. Pulled packer & ran a new 5 1/2" Hornet Packer. It went through liner top and tripped it in hole to 12,034'. Set packer W/ 18K tension. Nippled down BOPs and Nipple up Well-head. Drop Standin vale and tested to 1500 psi. Pressure held good. Hooked up production line and tested them with Triplex. Pulled standing valve Circulated hole. Cleaned up flat tanks and put well back into production

**RECEIVED**

**DEC 11 2008**

**DIV. OF OIL, GAS & MINING**

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

DeForrest Smouse PhD

Title President- Quinex Energy Corporation

Signature

*DeForrest Smouse*

Date 12/09/2008

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS  
UINTAH & OURAY AGENCY  
P.O. Box 130 or 7002 East 1400 South  
Fort Duchesne, Utah 84026  
Ph: (435) 722-4300 Fax: (435) 722-2323



In Reply Refer To:  
RES, Minerals & Mining (MS-420)

JUL 16 2015

RECEIVED

AUG 06 2015

DIV. OF OIL, GAS & MINING

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
For Record Only

Quinex Energy Corporation  
Attention: John H. Wells  
465 South 200 West  
Bountiful, Utah 84010

Dear Mr. Wells:

We have received your letter dated May 13, 2015, regarding oil and gas lease proposals on certain allotments located in the following locations:

Section 18-Township 1 South, Range 1 East, Chasel-Sprouse Well #1-18-A1E  
(Former Allotted Oil and Gas Lease Nos. 14-20-H62-4131, 4132, 4177, 4146,  
4147, 4148, 4375) 43047 31695

Section 7-Township 1 South, Range 1 East; Michelle-Ute #7-1 Well 43047 31390  
(Former Allotted Oil and Gas Lease Nos. 14-20-H62-3918, 3919, 3920, 3921, 4173)

Section 30-Township 1 South, Range 2 East; Redcap JDC #30-4 Well 43047 31591  
(Former Allotted Oil and Gas Lease Nos. 14-20-H62-4047, 4048, 4065)

Please be advised that we are currently notifying the Indian mineral owners of the allotted leases advising them of your offer. Because of the numerous owners involved, this will take a few weeks to complete, and a meeting will be scheduled so that Quinex will be able to answer any questions the Indian mineral owners have at that time. Please keep us informed on the renewals of the tribal oil and gas leases that may also reside within these locations.

This office will also be formally notifying the current Lessee's of Record of the expiration of the existing oil and gas leases, and advise the Bureau of Land Management and Office of Natural Resource Revenue of the lease expirations.

New Communitization Agreements for each Section will need to be filed with this office for approval prior to production of any new or existing wells.

JUL 20 2015

We appreciate your patience in this matter. If you have any questions regarding the above, please contact Paula Black, Realty Specialist at (435) 722-4313, or Antonio Pingree, Deputy Superintendent-Trust Services at (435) 722-4302.

Sincerely,

A handwritten signature in black ink, appearing to read "Antonio Pingree". The signature is fluid and cursive, with a large initial "A" and a long, sweeping underline.

**Acting** Superintendent



## QUINEX ENERGY CORPORATION

RECEIVED  
AUG 06 2015  
DIV. OF OIL, GAS & MINING

July 27, 2015

Certified No: 7014 3490 0001 3699 0055

Utah Department of Natural Resources  
Division of Oil, Gas & Mining  
1594 West North Temple, Suite 1210 / Box 145801  
Salt Lake City, Utah 84114-5801

Attention: Mr. Dustin Dorsett

Re: 1. HB Yulia #3-2 43-047-51283  
2. Einerson #1-4B1E 43-047-31940  
3. Chasel Sprouse #1-18A1E 43-047-31695

Dear Mister Dorsett:

As per our conversation on July 7, 2015 I am forwarding on to you the Sundry Notices that you requested for the HB Yulia #3-4 and the Einerson #1-4B1E wells. Quinex plans to have the Workovers done by the end of September 2015.

Also enclosed is a copy of a letter from the BIA Acting Deputy Superintendent - Antonio Pingree regarding the re-issuing of Tribal Leases that terminated the first part of May 2015. The Chasel Sprouse #1-18A1E referenced above is on the list. This well had a new liner installed in 2011 and therefore has no issues with the integrity of the well casing. Quinex will begin production on this well as soon as the BIA issues the new leases.

If you should have any questions or concerns please let me know.

Sincerely,

A handwritten signature in black ink, appearing to be 'JW', is written over the printed name of John Wells.

QUINEX ENERGY CORPORATION  
John Wells / President

JW/sp

Enclosures